ATTACHMENT 2 Closure Design Plans



SITE LOCATION WARDS CORPS TICO

DRAWING INDEX GAI DRAWING FILE NUMBER DRAWING TITLE SHEET NUMBER C150132-00-000-C-D1-001 TITLE SHEET 1 OF 65 C150132-00-000-C-D1-002 2 OF 65 GENERAL NOTES PROJECT CHECKLISTS AND LEGENDS C150132-00-000-C-D1-002 3 OF 65 4 OF 65 EXISTING CONDITIONS PLAN (1 OF 2) C150132-00-000-C-D1-004 EXISTING CONDITIONS PLAN (2 OF 2) C150132-00-000-C-D1-004 5 OF 65 SITE MASTER/ACCESS PLAN (1 OF 2) 6 OF 65 C150132-00-000-C-D1-006 C150132-00-000-C-D1-006 7 OF 65 SITE MASTER/ACCESS PLAN (2 OF 2) C150132-00-000-C-D1-008 8 OF 65 SOIL BORROW AREA DEVELOPMENT PLAN C150132-00-000-C-D1-009 9 OF 65 PHASE 1 GRADING PLAN - POND A,B,C CLOSURE 10 OF 65 C150132-00-000-C-D1-010 SANITARY SEWER RELOCATION PLAN - POND A,B,C CLOSURE 11 OF 65 C150132-00-000-C-D1-011 PHASE 2 GRADING PLAN — POND A,B,C CLOSURE C150132-00-000-C-D1-012 12 OF 65 PHASE 3 GRADING PLAN - POND A,B,C CLOSURE C150132-00-000-C-D1-013 13 OF 65 OVERALL PHASE 1 GRADING PLAN - POND D CLOSURE C150132-00-000-C-D1-014 14 OF 65 PHASE 1 GRADING PLAN ENLARGEMENT — POND D CLOSURE (1 OF 7) PHASE 1 GRADING PLAN ENLARGEMENT — POND D CLOSURE (2 OF 7) C150132-00-000-C-D1-014 15 OF 65 16 OF 65 PHASE 1 GRADING PLAN ENLARGEMENT — POND D CLOSURE (3 OF 7) C150132-00-000-C-D1-014 17 OF 65 C150132-00-000-C-D1-014 PHASE 1 GRADING PLAN ENLARGEMENT — POND D CLOSURE (4 OF 7) PHASE 1 GRADING PLAN ENLARGEMENT - POND D CLOSURE (5 OF 7) C150132-00-000-C-D1-014 18 OF 65 C150132-00-000-C-D1-014 19 OF 65 PHASE 1 GRADING PLAN ENLARGEMENT — POND D CLOSURE (6 OF 7) C150132-00-000-C-D1-014 20 OF 65 PHASE 1 GRADING PLAN ENLARGEMENT — POND D CLOSURE (7 OF 7) C150132-00-000-C-D1-021 21 OF 65 OVERALL PHASE 2 GRADING PLAN - POND D CLOSURE C150132-00-000-C-D1-022 22 OF 65 PHASE 2 GRADING PLAN ENLARGEMENT — POND D CLOSURE (1 OF 7) C150132-00-000-C-D1-022 23 OF 65 PHASE 2 GRADING PLAN ENLARGEMENT — POND D CLOSURE (2 OF 7) C150132-00-000-C-D1-022 24 OF 65 PHASE 2 GRADING PLAN ENLARGEMENT - POND D CLOSURE (3 OF 7) C150132-00-000-C-D1-022 25 OF 65 PHASE 2 GRADING PLAN ENLARGEMENT — POND D CLOSURE (4 OF 7) C150132-00-000-C-D1-022 26 OF 65 PHASE 2 GRADING PLAN ENLARGEMENT — POND D CLOSURE (5 OF 7) C150132-00-000-C-D1-022 27 OF 65 PHASE 2 GRADING PLAN ENLARGEMENT — POND D CLOSURE (6 OF 7) 28 OF 65 PHASE 2 GRADING PLAN ENLARGEMENT — POND D CLOSURE (7 OF 7) C150132-00-000-C-D1-022 C150132-00-000-C-D1-029 29 OF 65 OVERALL PHASE 3 GRADING PLAN - POND D CLOSURE 30 OF 65 PHASE 3 GRADING PLAN ENLARGEMENT — POND D CLOSURE (1 OF 7) C150132-00-000-C-D1-030 C150132-00-000-C-D1-030 PHASE 3 GRADING PLAN ENLARGEMENT - POND D CLOSURE (2 OF 7) 31 OF 65 C150132-00-000-C-D1-030 32 OF 65 PHASE 3 GRADING PLAN ENLARGEMENT - POND D CLOSURE (3 OF 7) PHASE 3 GRADING PLAN ENLARGEMENT - POND D CLOSURE (4 OF 7) C150132-00-000-C-D1-030 33 OF 65

COAL COMBUSTION RESIDUAL SURFACE IMPOUNDMENT CLOSURES

POSSUM POINT POWER STATION

PRINCE WILLIAM COUNTY, VIRGINIA

PREPARED FOR:

DOMINION


5000 DOMINION BOULEVARD GLEN ALLEN, VIRGINIA 23060 PREPARED BY:

GAI CONSULTANTS, INC.
4198 COX BOAD, SUITE 114.

4198 COX ROAD, SUITE 114, GLEN ALLEN, VIRGINIA 23060

SOLID WASTE DISPOSAL FACILITY PART B PERMIT APPLICATION DECEMBER 7, 2015 NOT FOR CONSTRUCTION

| | | DRAWING INDEX | |
|-------------------------|--------------|--|--|
| GAI DRAWING FILE NUMBER | SHEET NUMBER | DRAWING TITLE | |
| C150132-00-000-C-D1-030 | 34 OF 65 | PHASE 3 GRADING PLAN ENLARGEMENT — POND D CLOSURE (5 OF 7) | |
| C150132-00-000-C-D1-030 | 35 OF 65 | PHASE 3 GRADING PLAN ENLARGEMENT — POND D CLOSURE (6 OF 7) | |
| C150132-00-000-C-D1-030 | 36 OF 65 | PHASE 3 GRADING PLAN ENLARGEMENT — POND D CLOSURE (7 OF 7) | |
| C150132-00-000-C-D1-037 | 37 OF 65 | OVERALL PHASE 1 GRADING PLAN — POND E CLOSURE | |
| C150132-00-000-C-D1-038 | 38 OF 65 | OVERALL PHASE 2 GRADING PLAN — POND E CLOSURE | |
| C150132-00-000-C-D1-039 | 39 OF 65 | PHASE 2 GRADING PLAN ENLARGEMENT — POND E CLOSURE (1 OF 3) | |
| C150132-00-000-C-D1-039 | 40 OF 65 | PHASE 2 GRADING PLAN ENLARGEMENT — POND E CLOSURE (2 OF 3) | |
| C150132-00-000-C-D1-039 | 41 OF 65 | PHASE 2 GRADING PLAN ENLARGEMENT — POND E CLOSURE (3 OF 3) | |
| C150132-00-000-C-D1-042 | 42 OF 65 | OVERALL PHASE 3 GRADING PLAN - POND E CLOSURE | |
| C150132-00-000-C-D1-043 | 43 OF 65 | PHASE 3 GRADING PLAN ENLARGEMENT — POND E CLOSURE (1 OF 3) | |
| C150132-00-000-C-D1-043 | 44 OF 65 | PHASE 3 GRADING PLAN ENLARGEMENT — POND E CLOSURE (2 OF 3) | |
| C150132-00-000-C-D1-043 | 45 OF 65 | PHASE 3 GRADING PLAN ENLARGEMENT — POND E CLOSURE (3 OF 3) | |
| C150132-00-000-C-D1-046 | 46 OF 65 | SITE CROSS SECTIONS (1 OF 4) | |
| C150132-00-000-C-D1-046 | 47 OF 65 | SITE CROSS SECTIONS (2 OF 4) | |
| C150132-00-000-C-D1-046 | 48 OF 65 | SITE CROSS SECTIONS (3 OF 4) | |
| C150132-00-000-C-D1-046 | 49 OF 65 | SITE CROSS SECTIONS (4 OF 4) | |
| C150132-00-000-C-D1-050 | 50 OF 65 | DETAILS - CAP SYSTEM (1 OF 2) | |
| C150132-00-000-C-D1-050 | 51 OF 65 | DETAILS - CAP SYSTEM (2 OF 2) | |
| C150132-00-000-C-D1-052 | 52 OF 65 | DETAILS — STORMWATER (1 OF 2) | |
| C150132-00-000-C-D1-053 | 53 OF 65 | DETAILS — STORMWATER (2 OF 2) | |
| C150132-00-000-C-D1-054 | 54 OF 65 | DETAILS - MISCELLANEOUS (1 OF 3) | |
| C150132-00-000-C-D1-055 | 55 OF 65 | DETAILS - MISCELLANEOUS (2 OF 3) | |
| C150132-00-000-C-D1-056 | 56 OF 65 | DETAILS - MISCELLANEOUS (3 OF 3) | |
| C150132-00-000-C-D1-057 | 57 OF 65 | DETAILS — EROSION AND SEDIMENT CONTROL | |
| C150132-00-000-C-D1-058 | 58 OF 65 | DRAINAGE AREA MAP - PREDEVELOPMENT (1 OF 2) | |
| C150132-00-000-C-D1-058 | 59 OF 65 | DRAINAGE AREA MAP - PREDEVELOPMENT (2 OF 2) | |
| C150132-00-000-C-D1-060 | 60 OF 65 | DRAINAGE AREA MAP - POST-DEVELOPMENT (1 OF 2) | |
| C150132-00-000-C-D1-060 | 61 OF 65 | DRAINAGE AREA MAP - POST-DEVELOPMENT (2 OF 2) | |
| C150132-00-000-C-D1-062 | 62 OF 65 | RESOURCE PROTECTION AREAS METES AND BOUNDS (1 OF 2) | |
| C150132-00-000-C-D1-062 | 63 OF 65 | RESOURCE PROTECTION AREAS METES AND BOUNDS (2 OF 2) | |
| C150132-00-000-C-D1-064 | 64 OF 65 | UNIT PRICE LISTS (1 OF 2) | |
| C150132-00-000-C-D1-064 | 65 OF 65 | UNIT PRICE LISTS (2 OF 2) | |



SHEET NO .:

GAI FILE NUMBER:

1 OF **65**

C150132-00-000-C-D1-001

ALT./CLIENT DRAWING NUMBER:

GAI DRAWING NUMBER:

GENERAL EROSION AND SEDIMENT CONTROL NOTES

- THE OWNER/DEVELOPER MUST NOTIFY THE DEPARTMENT OF PUBLIC WORKS AT (434) 792-7070 AT LEAST 24 HOURS PRIOR TO THE START OF CONSTRUCTION IN ACCORDANCE WITH APPLICABLE COUNTY ORDINACES AND POLICIES.
- THE OWNER/DEVELOPER GRANTS THE RIGHT-OF-ENTRY ONTO THIS PROPERTY TO THE DESIGNATED PRINCE WILLIAM COUNTY PERSONNEL FOR THE PURPOSE OF INSPECTING AND MONITORING FOR COMPLIANCE WITH TITLE 10.01, CHAPTER 5, ARTICLE 4 OF THE CODE OF VIRGINIA EROSION AND SEDIMENT CONTROL LAW AND THE DESIGN AND CONSTRUCTION STANDARDS MANUAL SECTION 750.04.C.
- ALL EROSION CONTROL MEASURES SHOWN ON THE APPROVED PLAN MUST BE IN PLACE AND INSPECTED AND APPROVED BY THE DEPARTMENT OF PUBLIC WORKS PRIOR TO CLEARING AND STRIPPING OF TOPSOIL, OR GRADING.
- A COPY OF THE APPROVED EROSION AND SEDIMENT CONTROL PLAN SHALL BE MAINTAINED ON THE SITE AT ALL TIMES.
- THE CONTRACTOR IS RESPONSIBLE FOR INSTALLATION OF ANY ADDITIONAL EROSION CONTROL MEASURES NECESSARY TO PREVENT EROSION AND SEDIMENTATION, AS DETERMINED BY PRINCE WILLIAM COUNTY.
- ALL DISTURBED AREAS ARE TO DRAIN TO APPROVED SEDIMENT CONTROL MEASURES AT ALL TIMES DURING LAND DISTURBANCE ACTIVITIES AND DURING SITE DEVELOPMENT UNTIL COMPLETE AND ADEQUATE STABILIZATION IS ACHIEVED.
- DURING DEWATERING OPERATIONS, WATER WILL BE PUMPED INTO AN APPROVED FILTERING OR WATER TREATMENT DEVICE.
- ALL EROSION AND SEDIMENT CONTROL PRACTICES MUST BE CONSTRUCTED AND MAINTAINED IN ACCORDANCE WITH THE MINIMUM STANDARDS AND SPECIFICATIONS OF THE <u>VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK</u> AND THE VIRGINIA REGULATIONS VR 625-02-00 EROSION AND SEDIMENT CONTROL REGULATIONS AND TO THE PRINCE WILLIAM COUNTY DESIGN AND CONSTRUCTION STANDARDS MANUAL.
- THE CONTRACTOR WILL BE RESPONSIBLE FOR THE INSTALLATION AND MAINTENANCE OF ALL EROSION AND SEDIMENT CONTROL PRACTICES AT ALL TIMES.
- D. THE CONTRACTOR SHALL INSPECT ALL EROSION AND SEDIMENT CONTROL MEASURES AT LEAST ONCE EVERY 2 WEEKS AND WITHIN 48 HOURS FOLLOWING ANY RUNOFF PRODUCING STORMEVENT. THE FOLLOWING ITEMS WILL BE CHECKED IN PARTICULAR:
- a. Sediment basins will be cleaned out when the level of sediment buildup reaches the cleanout elevation indicated in the details of THE PLAN DRAWINGS. SEDIMENT SHALL BE DISPOSED OF IN SUITABLE AREAS AND IN SUCH A MANNER THAT IT WILL NOT ERODE OR CAUSE
- b. THE BASIN EMBANKMENTS WILL BE CHECKED REGULARLY TO ENSURE THAT THEY ARE STRUCTURALLY SOUND AND HAVE NOT BEEN DAMAGED BY EROSION OR CONSTRUCTION EQUIPMENT.
- c. EMERGENCY SPILLWAYS WILL BE CHECKED REGULARLY TO ENSURE THAT THE LININGS ARE WELL ESTABLISHED AND EROSION RESISTANT.
- d. Sediment traps will be checked regularly for sediment cleanout. Sediment shall be removed and the trap restored to its original dimensions when the sediment has accumulated to one half the design volume of the wet storage. Sediment removed from the trap shall be disposed of in a suitable area and in such a manner that it does not erode or cause sedimentation problems.
- B. RIPRAP PROTECTION WILL BE CHECKED REGULARLY FOR SEDIMENT BUILDUP WHICH WILL PREVENT DRAINAGE AND SCOUR. RUNOFF THAT IS SEDIMENT-LADEN MUST BE CONSIDERED WHEN CONSTRUCTION TAKES PLACE.
- f. SILT FENCE BARRIERS WILL BE CHECKED REGULARLY FOR UNDERMINING OR DETERIORATION OF THE FABRIC, AND IMMEDIATELY AFTER EACH RUNOFF PRODUCING RAINFALL EVENT AND AT LEAST DAILY DURING PROLONGED RAINFALL. SEDIMENT SHALL BE REMOVED WHEN THE LEVEL OF SEDIMENT DEPOSITION REACHES HALF THE HEIGHT OF THE BARRIER.
- g. SEEDED AREAS WILL BE CHECKED REGULARLY TO ENSURE THAT A GOOD STAND OF VEGETATION IS MAINTAINED. AREAS WILL BE FERTILIZED AND
- h. Stream diversions and storm conveyance channels shall be inspected regularly and within 48 hours following a runoff producing rain event to ensure they are functioning properly and that the integrity of the linings are not impaired.
- ANY NECESSARY REPAIRS OR CLEANUP TO MAINTAIN THE EFFECTIVENESS OF THE EROSION CONTROL DEVICES MUST BE MADE <u>IMMEDIATELY</u> AFTER THE
- SEDIMENT BASINS, SEDIMENT TRAPS, PERIMETER DIKES, SEDIMENT BARRIERS, AND OTHER MEASURES INTENDED TO TRAP SEDIMENT, IF NEEDED, SHALL BE CONSTRUCTED AS A FIRST STEP IN ANY LAND-DISTURBING ACTIVITY AND SHALL BE MADE FUNCTIONAL, BY SEEDING AND MULCHING IMMEDIATELY FOLLOWING
- SEDIMENT TRAPS AND BASINS SHALL BE DESIGNED AND CONSTRUCTED BASED UPON THE TOTAL DRAINAGE AREA TO BE SERVED BY THE TRAP OR BASIN AS FOLLOWS:

ONLY CONTROL DRAINAGE AREAS LESS THAN 3 ACRES MINIMUM STORAGE CAPACITY OF 134 CUBIC YARDS PER ACRE OF DRAINAGE AREA

- CONTROL DRAINAGE AREAS GREATER THAN OR EQUAL TO 3 ACRES MINIMUM STORAGE CAPACITY OF 134 CUBIC YARDS PER ACRE OF DRAINAGE AREA
- THE OUTFALL SYSTEM SHALL, AT A MINIMUM, MAINTAIN THE STRUCTURAL INTEGRITY OF THE BASIN DURING A 25-YEAR STORM OF 24-HOUR DURATION

- PERMANENT OR TEMPORARY SOIL STABILIZATION SHALL BE APPLIED TO DENUDED AREAS WITHIN SEVEN (7) DAYS AFTER FINAL GRADE IS REACHED ON
- TEMPORARY SOIL STABILIZATION SHALL BE APPLIED WITHIN SEVEN (7) DAYS TO DENUDED AREAS THAT MAY NOT BE AT FINAL GRADE BUT WILL REMAIN
- PERMANT STABILIZATION SHALL BE APPLIED TO AREAS THAT ARE TO BE LEFT DORMANT FOR MORE THAN SIX (6) MONTHS.
- SEEDING AND SELECTION OF THE SEED MIXTURE SHALL BE IN ACCORDANCE WITH THE VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK STANDARD AND SPECIFICATION 3.32 AND AS INDICATED ON THESE PLANS.
- ROADS AND PARKING AREAS SHALL BE STABILIZED IMMEDIATELY AFTER FINAL GRADE IS REACHED.
- ROCK CHECK DAMS SHOULD BE INSPECTED AFTER EACH RUNOFF-PRODUCING STORM EVENT AND SEDIMENT SHOULD BE REMOVED AFTER LEVELS HAVE
- ALL TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES SHALL BE REMOVED WITHIN 30 DAYS AFTER FINAL SITE STABILIZATION OR AFTER THE TEMPORARY MEASURES ARE NO LONGER NEEDED, UNLESS OTHERWISE AUTHORIZED BY PRINCE WILLIAM COUNTY INSPECTORS. TRAPPED SEDIMENT AND THE DISTURBED SOIL AREAS RESULTING FROM THE DISPOSITION OF TEMPORARY MEASURES SHALL BE PERMANENTLY STABILIZED TO PREVENT FURTHER EROSION
- DURING CONSTRUCTION, SOIL STOCKPILES AND BORROW AREAS SHALL BE STABILIZED OR PROTECTED WITH SEDIMENT TRAPPING MEASURES. TEMPORARY PROTECTION AND PERMANENT STABILIZATION SHALL BE APPLIED TO ALL SOIL STOCKPILES ON SITE AND BORROW AREAS OR SOIL INTENTIONALLY
- . PERMANENT VEGETATIVE COVER SHALL BE ESTABLISHED ON DENUDED AREAS NOT OTHERWISE PERMANENTLY STABILIZED. PERMANENT VEGETATION SHALL NOT BE CONSIDERED ESTABLISHED UNTIL A GROUND COVER IS ACHIEVED THAT IS:
- MATURE ENOUGH TO SURVIVE
- 9. STABILIZATION MEASURES SHALL BE APPLIED TO EARTHEN STRUCTURES SUCH AS DAMS, DIKES, AND DIVERSIONS IMMEDIATELY AFTER INSTALLATION.
- D. CUT AND FILL SLOPES SHALL BE DESIGNED AND CONSTRUCTED IN A MANNER THAT WILL MINIMIZE EROSION. SLOPES FOUND TO BE ERODING EXCESSIVEL WITHIN ONE YEAR OF PERMANENT STABILIZATION SHALL BE PROVIDED WITH ADDITIONAL SLOPE STABILIZING MEASURES UNTIL THE PROBLEM IS CORRECTED.
- CONCENTRATED RUNOFF SHALL NOT FLOW DOWN CUT OR FILL SLOPES UNLESS CONTAINED WITHIN AN ADEQUATE TEMPORARY OR PERMANENT CHANNEL, FLUME, OR SLOPE DRAIN STRUCTURE.
- 22. WHENEVER WATER SEEPS FROM A SLOPE FACE, ADEQUATE DRAINAGE OR OTHER PROTECTION SHALL BE PROVIDED.
- 23. ALL STORM SEWER INLETS MADE OPERABLE DURING CONSTRUCTION SHALL BE PROTECTED SO THAT SEDIMENT-LADEN WATER CANNOT ENTER THE STORMWATER CONVEYANCE SYSTEM WITHOUT FIRST BEING FILTERED OR OTHERWISE TREATED TO REMOVE SEDIMENT.
- 4. BEFORE NEWLY CONSTRUCTED STORMWATER CONVEYANCE CHANNELS OR PIPES ARE MADE OPERATIONAL, ADEQUATE OUTLET PROTECTION AND ANY REQUIRED TEMPORARY OR PERMANENT CHANNEL LINING SHALL BE INSTALLED IN BOTH THE CONVEYANCE CHANNEL AND THE RECEIVING CHANNEL.
- 25. WHEN WORK IN A LIVE WATERCOURSE IS PERFORMED:
- PRECAUTIONS SHALL BE TAKEN TO MINIMIZE ENCROACHMENT, CONTROL SEDIMENT TRANSPORT, AND STABILIZE THE WORK AREA TO THE GREATEST
- NONERODIBLE MATERIAL SHALL BE USED FOR THE CONSTRUCTION OF THE CAUSEWAYS AND COFFERDAMS.
- EARTHEN FILL MAY BE USED FOR THESE STRUCTURES IF ARMORED BY NONERODIBLE COVER DETAILS.
- : WHEN A LIVE WATERCOURSE MUST BE CROSSED BY CONSTRUCTION VEHICLES MORE THAN TWICE IN ANY SIX (6) MONTH PERIOD, A TEMPORARY VEHICULAR STREAM CROSSING CONSTRUCTED OF NONERODIBLE MATERIAL SHALL BE PROVIDED.
- 27. ALL APPLICALBE FEDERAL, STATE, AND LOCAL REGULATIONS PERTAINING TO WORKING IN OR CROSSING LIVE WATERCOURSES SHALL BE MET.
- 28. THE BED AND BANKS OF A WATERCOURSE SHALL BE STABILIZED IMMEDIATELY AFTER WORK IN THE WATERCOURSE IS COMPLETED.

29. UNDERGROUND UTILITY LINES SHALL BE INSTALLED IN ACCORDANCE WITH THE FOLLOWING STANDARDS IN ADDITION TO OTHER APPLICABLE CRITERIA:

- NO MORE THAN 500 LINEAR FEET OF TRENCH MAY BE OPENED AT ONE TIME.
- EFFLUENT FROM DEWATERING OPERATIONS SHALL BE FILTERED OR PASSED THROUGH AN APPROVED SEDIMENT TRAPPING DEVICE, OR BOTH, AND DISCHARGED IN A MANNER THAT DOES NOT ADVERSELY AFFECT FLOWING STREAMS OR OFF-SITE PROPERTY. MATERIAL USED FOR BACKFILLING TRENCHES SHALL BE PROPERLY COMPACTED IN ORDER TO MINIMIZE EROSION AND PROMOTE STABILIZATION. RESTABILIZATION SHALL BE ACCOMPLISHED IN ACCORDANCE WITH THE EROSION AND SEDIMENTATION CONTROL REGUALTIONS FOR PRINCE WILLIAM
- COUNTY, (SECTION 700-ENVIRONMENTAL SYSTEMS). EXCAVATIONS SHALL COMPLY WITH APPLICABLE SAFETY REGULATIONS.
- EROSION, AND DAMAGE DUE TO INCREASES IN VOLUME, VELOCITY, AND PEAK FLOW RATE, FOR THE STATED FREQUENCY STORM OF 24-HOUR DURATION, IN
- CONCENTRATED STORMWATER RUNOFF LEAVING A DEVELOPMENT SITE SHALL BE DISCHARGED DIRECTLY INTO AN ADEQUATE, NATURAL OR MAN-MADE RECEIVING CHANNEL, PIPE, OR STORM SEWER SYSTEM. FOR THOSE SITES WHERE RUNOFF IS DISCHARGED INTO A PIPE OR PIPE SYSTEM, A DOWNSTREAM STABILITY ANALYSIS AT THE OUTFALL OF THE PIPE OR PIPE SYSTEM SHALL BE PERFORMED.
- + NATURAL CHANNELS USE 2-YEAR STORM EVENT
- + MANMADE CHANNELS USE 2-, 10-, AND 25-YEAR STORM EVENT + PIPE AND PIPE SYSTEMS - USE 10-YEAR STORM EVENT
- IF EXISTING NATURAL RECEIVING CHANNELS OR PREVIOUSLY CONSTRUCTED MAN-MADE CHANNELS OR PIPES ARE NOT ADEQUATE, THE APPLICANT SHALL PROVIDE CHANNEL, PIPE, OR PIPE SYSTEM IMPROVEMENTS OR PROVIDE A COMBINATION OF CHANNEL IMPROVEMENTS, SITE DESIGN, STORMWATER DETENTION, OR OTHER MEASURES THAT ARE SATISFACTORY TO THE PROGRAM AUTHORITY TO PREVENT DOWNSTREAM EROSION.
- PROVIDE EVIDENCE OF PERMISSION TO MAKE IMPROVEMENTS IF THE APPLICANT CHOOSES AN OPTION THAT INCLUDES STORMWATER DETENTION HE SHALL OBTAIN APPROVAL FROM THE LOCALITY OF A PLAN FOR MAINTENANCE OF THE DETENTION FACILITIES. THE PLAN SHALL SET FORTH THE MAINTENANCE REQUIREMENTS OF THE FACILITY AND THE PERSON
- OUTFALL FROM A DETENTION FACILITY SHALL BE DISCHARGED TO A RECEIVING CHANNEL, AND ENERGY DISSIPATORS SHALL BE PLACED AT THE OUTFALL OF ALL DETENTION FACILITIES AS NECESSARY TO PROVIDE A STABILIZED TRANSITION FROM THE FACILITY TO THE RECEIVING CHANNEL. INCREASED VOLUMES OF SHEET FLOWS, THAT MAY CAUSE EROSION OR SEDIMENTATION ON ADJACENT PROPERTIES, SHALL BE DIVERTED TO A STABLE OUTLET, ADEQUATE CHANNEL, PIPE OR PIPE SYSTEM, OR TO A DETENTION FACILITY.
- IN APPLYING THESE STORMWATER RUNOFF CRITERIA, INDIVIDUAL LOTS OR PARCELS IN A RESIDENTIAL, COMMERCIAL OR INDUSTRIAL DEVELOPMENT SHALL NOT BE CONSIDERED TO BE SEPARATE DEVELOPMENT PROJECTS. INSTEAD, THE DEVELOPMENT AS A WHOLE SHALL BE CONSIDERED TO BE A
- ALL MEASURES USED TO PROTECT PROPERTIES AND WATERWAYS SHALL BE EMPLOYED IN A MANNER THAT MINIMIZES IMPACTS ON THE PHYSICAL, CHEMICAL, AND BIOLOGICAL INTEGRITY OF RIVERS, STREAMS AND OTHER WATERS OF THE STATE.
- 31. UNLESS OTHERWISE INDICATED, ALL VEGETATIVE AND STRUCTURAL EROSION AND SEDIMENT CONTROL PRACTICES WILL BE CONSTRUCTED AND MAINTAINED ACCORDING TO MINIMUM STANDARDS AND SPECIFICATIONS OF THE VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK AND VIRGINIA REGULATIONS 4VAC50-30, EROSION AND SEDIMENT CONTROL REGULATIONS.
- 32. THE PLAN APPROVING AUTHORITY MUST BE NOTIFIED ONE WEEK PRIOR TO THE PRE-CONSTRUCTION CONFERENCE, ONE WEEK PRIOR TO THE COMMENCEMENT OF LAND DISTURBING ACTIVITY, AND ONE WEEK PRIOR TO THE FINAL INSPECTION.
- 33. WHERE CONSTRUCTION VEHICLE ACCESS ROUTES INTERSECT PAVED OR PUBLIC ROADS:
- PROVISIONS SHALL BE MADE TO MINIMIZE THE TRANSPORT OF SEDIMENT BY VEHICULAR TRACKING ONTO THE PAVED SURFACE
- WHERE SEDIMENT IS TRANSPORTED ONTO A PAVED OR PUBLIC ROAD SURFACE, THE ROAD SURFACE SHALL BE CLEANED THOROUGHLY AT THE END OF SEDIMENT SHALL BE REMOVED FROM THE ROADS BY SHOVELING OR SWEEPING, AND TRANSPORTED TO A SEDIMENT CONTROL DISPOSAL AREA. STREET
- 34. AREAS WHICH ARE NOT TO BE DISTURBED WILL BE CLEARLY MARKED BY FLAGS, SIGNS, ETC.

WASHING SHALL BE ALLOWED ONLY AFTER SEDIMENT IS REMOVED IN THIS MANNER.

- 35. RPA AND FLOOD PLAIN LIMITS SHALL BE CLEARLY MARKED IN THE FIELD BY FLAGS, SIGNS, ETC.
- 36. TREES SHOULD BE CLEARED AS NECESSARY WITHIN THE LIMITS OF DISTURBANCE TO COMPLETE THE WORK. THE LIMITS OF CLEARING SHOULD BE MINIMIZED
- 37. TREE SAVE AREAS SHALL BE CLEARLY MARKED IN THE FIELD BY ORANGE SAFETY FENCE. APPROPRIATE TREE PRESERVATION SIGNS (WATERPROOF) 1 IDENTIFY TREE PRESERVATION AREAS SHALL BE LOCATED ON TREE PROTECTION FENCING (INCLUDES SUPER SILT FENCING) AND SHOULD ALTERNATE ENGLISH
- 38. ORANGE SAFETY FENCE MUST BE INSTALLED AROUND ALL SILT TRAPS AND SEDIMENT BASINS IMMEDIATELY AFTER THEIR FACILITIES ARE CONSTRUCTED.

EROSION CONTROL NARRATIVE:

1. PROJECT DESCRIPTION: LOCATED IN PRINCE WILLIAM COUNTY. WORK FOR THE PROPOSED CLOSURE PLAN IS ANTICIPATED TO OCCUR OVER THE NEXT THREE (3) YEARS. THE GENERAL CONSTRUCTION PLANS INCLUDE DEWATERING THE PONDS, MECHANICALLY DREDGING CCR FROM PONDS A, B, C, AND E, REGRADING THE AREA WITHIN THE PONDS, MODIFICATION OF IMPOUNDING STRUCTURES, CONSTRUCTION OF STORMWATER AND EROSION AND SEDIMENT CONTROL MEASURES, REMOVAL OF TEMPORARY SEDIMENTATION BASINS, AND POST-CLOSURE VEGETATION. THE PROPOSED WORK IS ANTICIPATED TO DISTURB UP TO 120 ACRES OF EXISTING POND AREA, AND 24.61 ACRES OF NEW AREA IN THE PROPOSED BORROWED AREAS.

THE POSSUM POINT POWER STATION IS LOCATED NEAR DUMFRIES, VA AND IS ACCESSED BY POSSUM POINT ROAD (ROUTE 633) AND IS ADJACENT TO THE POTOMAC RIVER AND QUANTICO CREEK. THE STATION SLUICED CCR INTO THE CCR PONDS UNTIL 2003, WHEN THE STATION STOPPED USING COAL AS FUEL. THE CCR PONDS AT THE STATION CONSIST OF THE FOLLOWING IMPOUNDMENT AREAS: POND A, POND B, POND C, POND D, AND POND E. THE CONSERVATION AND RECREATION (DCR) FOR THE IMPOUNDING STRUCTURES FOR EACH POND AND DISCHARGE FROM THE PONDS IS PERMITTED UNDER THE STATION'S INDUSTRIAL VIRGINIA POLLUTANT DISCHARGE ELIMINATION SYSTEM PERMIT NO. VA0002071. THE PONDS ARE DESCRIBED BELOW:

- a. Ponds A, B, and C cover an area of approximately 18 acres. Ponds A, B, and C were constructed in 1955 and utilized until the 1960s. The DAM that impounds ponds A, B, and C is considered a single structure. However, there are three distinct areas within THE IMPOUNDMENT THAT ARE REFERRED TO AS POND A, POND B, AND POND C. AS OF AUGUST 2015, THE CCR IN PONDS A, B, AND C ARE BEING DREDGED AND PLACED IN POND D IN ACCORDANCE WITH VPDES PERMIT NO. VA0002071. DRAINAGE FROM PONDS A, B, AND C IS BEING PUMPED TO POND D FOR STORAGE BEFORE IT CAN BE DISCHARGED IN ACCORDANCE WITH VPDES PERMIT NO. VA0002071
- b. POND D COVERS AN AREA OF APPROXIMATELY 64 ACRES. POND D WAS CONSTRUCTED IN 1988 TO REPLACE AN EXISTING CCR POND D WHICH WAS LOCATED IN THE SAME LOCATION. CCR GENERATED BY THE STATION WERE SLUICED INTO POND D UNTIL 2003. FREE WATER IN POND D COVERS AN AREA OF APPROXIMATELY 29 ACRES. THE REMAINDER OF THE POND AREA IS VEGETATED WITH WEEDS AND BRUSH AND SMALL TREES. DRAINAGE FROM THE POND D WATERSHED IS BEING STORED IN POND D BEFORE IT CAN BE DISCHARGED TO A PERMITTED OUTFALL IN ACCORDANCE WITH
- C. POND E COVERS AN AREA OF APPROXIMATELY 38 ACRES. POND E WAS CONSTRUCTED IN 1967 AND WAS UTILIZED FOR CCR DISPOSAL UNTIL 2003. AS OF JUNE 2015, THE CCR IN POND E IS BEING DREDGED AND PLACED IN POND D IN ACCORDANCE WITH VPDES PERMIT NO. VA0002071. DRAINAGE FROM PONDS A, B, AND C IS BEING PUMPED TO POND D FOR STORAGE BEFORE IT CAN BE DISCHARGED IN ACCORDANCE WITH VPDES

ADJACENT AREAS:

THE PROPOSED SITE IS BOUNDED BY QUANTICO CREEK ON THE SOUTH AND AN UNNAMED TRIBUTARY OF QUANTICO CREEK ON THE WEST. EAST OF THE SITE IS COCKPIT POINT ROAD (ROUTE 783). TO THE NORTH OF THE SITE IS PRIVATE PROPERTY THAT IS HEAVILY WOODED. THE MAJORITY OF THE CONTRIBUTING DRAINAGE AREA INTO THE PONDS INCLUDE VEGETATED AREAS CONSISTING OF BRUSH AND FORESTLAND.

4. OFF-SITE AREAS:

SOIL BORROW AREAS WILL BE LOCATED WITHIN THE PROPERTY AND ARE COVERED UNDER THIS PLAN. THERE ARE NO OFF-SITE AREAS PROPOSED TO BE DISTURBED.

SOILS:

ACCORDING TO THE NRCS WEB SOIL SURVEY REPORT FOR THE PROJECT AREA, THE SOILS AT THE SITE CONTAIN MOSTLY HYDROLOGIC SOIL GROUP TYPE A AND TYPE B SOILS, WITH TYPE B SOILS BEING PREDOMINANT. A LESSER PORTION OF THE PROJECT CONSISTS OF TYPE D SOILS. TYPE A SOILS EXIST IN 7. PARTIALLY REMOVE POND E EMBANKMENT AND USE AS FILL WITHIN THE LIMITS OF POND E THE POND EMBANKMENTS AND AREAS IMMEDIATELY ADJACENT TO THE PONDS. TYPE B SOILS MAKE UP THE MAJORITY OF THE CONTRIBUTING DRAINAGE AREA UPLAND OF THE PONDS. GROUP A SOILS HAVE A HIGH INFILTRATION RATE AND LOW RUN-OFF POTENTIAL WHEN THOUROUGHLY WETTED. THESE SOILS CONSIST MAINLY OF DEEP, WELL DRAINED TO EXCESSIVELY DRAINED SANDS OR GRAVELLY SANDS. THESE SOILS HAVE A HIGH RATE OF WATER TRANSMISSION (>0.3 IN/HR). GROUP B SOILS HAVE MODERATE INFILTRATION RATES WHEN THOROUGHLY WETTED AND CONSIST CHIEFLY OF MODERATELY DEEP TO DEEP, MODERATELY WELL TO WELL DRAINED SOILS WITH MODERATELY FINE TO MODERATELY COARSE TEXTURES. THESE SOILS HAVE A MODERATE RATE OF WATER TRANSMISSION (0.15-0.30 IN/HR). GROUP C SOILS HAVE LOW INFILTRATION RATES WHEN THROUGHLY WETTED AND CONSIST CHIEFLY OF SOILS WITH LAYERS THAT IMPEDE DOWNWARD MOVEMENT OF WATER AND SOILS WITH MODERATELY FINE TO FINE TEXTURES. THESE SOILS HAVE A LOW RATE OF WATER TRANSMISSION (0.05-0.15 IN/HR). GROUP D SOILS HAVE HIGH RUNOFF POTENTIAL. THEY HAVE VERY LOW INFILTRATION RATES WHEN THOROUGHLY WETTED AND CONSISTS CHIEFLY OF CLAY SOILS WITH HIGH SWELLING POTENTIAL, A PERMANENT HIGH WATER TABLE, A CLAY PAN OR CLAY LAYER AT OR NEAR THE SURFACE, AND SHALLOW NEARLY IMPERVIOUS MATERIAL. THESE SOILS HAVE A LOW RATE OF TRANSMISSION (0-0.05 IN/HR).

SEVERAL LOCATIONS EXIST WHERE THE PROPOSED LIMITS OF DISTRUBANCE (LOD) EXTEND TO WITHIN 10 FEET OF WETLAND AREAS AND THE FEMA FLOODPLAIN BOUNDARY. THE LOD ALSO ENCROACHES INTO THE RPA IN SEVERAL LOCATIONS. THESE ARE CONSIDERED CRITICAL AREAS DUE TO THE POTENTIAL DAMAGE OF SILTATION WITHIN THE WETLANDS, RPA, AND FLOODPLAIN. OTHER CRITICAL AREAS ON THE SITE INCLUDE STEEP SLOPE AREAS ASSOCIATED WITH THE POND EMBANKMENTS AND THE UPLAND PERIMETERS OF THE WORK AREA. THESE ARE CONSIDERED CRITICAL AREAS DUE TO THE INCREASED POTENTIAL FOR EROSION.

EROSION AND SEDIMENT CONTROL MEASURES:

UNLESS OTHERWISE INDICATED, ALL VEGETATIVE AND STRUCTURAL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE CONSTRUCTED AND MAINTAINED ACCORDING TO THE MINIMUM STANDARDS AND SPECIFICATIONS OF THE VIRGINIA EROSION AND SEDIMENT CONTROL HANDBOOK AND VIRGINIA REGULATIONS 4VAC50-30 EROSION AND SEDIMENT CONTROL REGULATIONS.

8. TEMPORARY STONE CONSTRUCTION ENTRANCE - 3.02

A STONE PAD, WILL BE INSTALLED AT POINTS OF VEHICULAR INGRESS AND EGRESS, TO REDUCE THE SOIL TRANSPORTED ONTO PUBLIC ROADS AND OTHER PAVED AREAS.

9. SILT FENCE - 3.05

SILT FENCES WILL BE CONSTRUCTED ALONG THE PERIMETER OF THE PROJECT TO INTERCEPT AND DETAIN RUN-OFF SEDIMENT FROM SMALL AREAS NOT BEING DIVERTED TO SEDIMENT BASINS OR OTHER STRUCTURAL CONTROLS. TO DECREASE FLOW VELOCITIES, SILT FENCES WILL ALSO BE CONSTRUCTED ALONG UPSTREAM AREAS OF THE SITE TO INHIBIT EROSION POTENTIAL. WIRE SUPPORTED SILT FENCE (SUPER SILT FENCE) IN TWO LAYERS WILL BE USED FOR PERIMETER RUNOFF AND FOR CRITICAL AREAS.

10. STORM DRAIN INLET PROTECTION -3.07

AS NECESSARY, EXISTING STORM DRAIN INLETS WILL BE PROTECTED FROM RUN-OFF BY USE OF SILT FENCE, GRAVEL/WIRE MESH, OR CATCH BASIN INSERTS. PROTECTION IS LIMITED TO DRAINAGE AREAS NOT EXCEEDING ONE (1) ACRE AND IS NOT INTENDED TO CONTROL LARGE. CONCENTRATED STORMWATER FLOWS. THERE ARE NO NEW STORM DRAIN INLETS THAT ARE PROPOSED TO BE INSTALLED ON THE SITE.

A SEDIMENT FILTER INSTALLED AT THE INLET OF A STORM SEWER CULVERT TO PREVENT THE ENTERING, ACCUMULATING, OR TRANSFERRING OF SEDIMENT THROUGH THE CULVERT. THIS MEASURE ALSO ALLOWS FOR EROSION CONTROL TO BE INPLACE DURING PHASES OF THE PROJECT WHERE ELEVATIONS AND DRAINAGE PATTERNS ARE CHANGING, AND WHERE ORIGINAL CONTROLS ARE INEFFECTIVE.

A RIDGE OF COMPACTED SOIL WILL BE CONSTRUCTED AT THE TOP OR BASE OF A SLOPING DISTURBED AREA TO DIVERT OFF-SITE RUNOFF AWAY FROM

UNPROTECTED SLOPES AND TO A STABILIZED OUTLET, OR TO DIVERT SEDIMENT—LADEN RUNOFF TO A SEDIMENT TRAPPING STRUCTURE.

13. TEMPORARY SEDIMENT TRAP - 3.13 TEMPORARY SEDIMENT TRAPS, SMALL PONDING AREAS, WILL BE CONSTRUCTED TO FILTER STORMWATER FROM THE SITE.

14. TEMPORARY SEDIMENT BASIN - 3.14 A TEMPORARY BARRIER OR DAM WITH A CONTROLLED STORMWATER RELEASE STRUCTURE WILL BE CONSTRUCTED TO FILTER STORMWATER FROM THE SITE.

15. STORMWATER CONVEYANCE CHANNELS - 3.17

PERMANENT CHANNELS, THAT CARRY CONCENTRATED FLOWS AND RESIST EROSION, WILL BE USED TO CONVEY STORMWATER TO SEDIMENT BASINS.

RIPRAP CHANNEL SECTIONS AND/OR STILLING BASINS WILL BE INSTALLED BELOW STORM DRAIN OUTLETS TO DECREASE EROSION AND UNDER-CUTTING, AND

REDUCE VELOCITIES BEFORE ENTERING RECEIVING CHANNELS.

SMALL, TEMPORARY STONE DAMS WILL BE INSTALLED AT SET INTERVALS THROUGHOUT CHANNELS TO REDUCE THE VELOCITY OF CONCENTRATED FLOWS, REDUCING THE EROSION OF THE CHANNELS.

18. SOIL STABILIZATION BLANKETS AND MATTING - 3.36

A PROTECTIVE BLANKET OR SOIL STABILIZATION MAT WILL BE INSTALLED FOR PREPARED PLANTING OF STEEP SLOPES AND CHANNELS.

TOPSOIL WILL BE PRESERVED AND USED TO ESTABLISH A SUITABLE MEDIUM FOR VEGETATION, WHICH WILL BE USED TO STABILZE DISTURBED AREAS.

RAPIDLY GROWING PLANTS, APPROPRAITE TO THE AREA, WILL BE APPLIED TO AREAS NOT RECEIVING FINAL GRADING FOR THIRTY (30) DAYS TO ONE (1)

PERMANENT VEGETATIVE COVER WILL BE APPLIED TO FINE GRADED AREAS OR AREAS THAT WILL BE LEFT DORMANT FOR 6 MONTHS OR MORE.

PLANT RESIDUALS OR OTHER SUITABLE MATERIALS WILL BE APPLIED TO DISTURBED SURFACES TO PREVENT EROSION AND REDUCE OVERLAND FLOW

- 20. MANAGEMENT STRATEGIES: 1. CONSTRUCTION WILL BE SEQUENCED SO THAT GRADING OPERATIONS CAN BEGIN AND END AS QUICKLY AS POSSIBLE WITH APPROPRIATE EROSION CONTROL MEASURES IN-PLACE. SEE "SEQUENCE OF CONSTRUCTION" ON THIS SHEET FOR FURTHER DETAILS.
- 2. REFER TO THE "GENERAL EROSION AND SEDIMENT CONTROL NOTES" FOR ADDITIONAL INFORMATION ON THE SCHEDULING OF EROSION CONTROL MEASURES AND SEEDING.
- 3. AREAS WHICH ARE NOT TO BE DISTURBED WILL BE CLEARLY MARKED BY FLAGS, SIGNS, ETC.
- 4. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE INSTALLATION AND MAINTENANCE OF ALL EROSION AND SEDIMENT CONTROL PRACTICES.

VS POST-DEVELOPMENT DISCHARGE COMPARISON AT THE DOWNSTREAM PROPERTY BOUNDARY STUDY POINT.

SEEDING WILL BE IN ACCORDANCE WITH THE TEMPORARY AND PERMANENT CHARTS PROVIDED BELOW, UNLESS OTHERWISE NOTED IN THE TECHNICAL

REACHED ON ANY PORTION OF THE SITE. TEMPORARY SOIL STABILIZATION SHALL BE APPLIED WITHIN SEVEN (7) DAYS TO DENUDED AREAS THAT MAY NOT BE AT FINAL GRADE BUT WILL REMAIN DORMANT FOR LONGER THAN FOURTEEN (14) DAYS. PERMANENT STABILIZATION SHALL BE APPLIED TO AREAS THAT ARE LEFT DORMANT FOR MORE THAN SIX (6) MONTHS. THE STORMWATER MANAGEMENT SYSTEM HAS BEEN DESIGNED TO HANDLE THE 25-YR STORM PER APPLICABLE SOLID WASTE REGULATIONS AND PER COUNTY REQUIREMENTS. THE PERMANENT CONVEYANCE CHANNEL OVER THE EMBANKMENT OF POND D HAS BEEN DESIGNED TO CONTAIN THE PMP STORM, PER APPLICABLE VDCR DAM SAFETY REGULATIONS. THE POND D-E SYSTEM, AS WELL AS PONDS A, B, AND C. ARE DESIGNED TO DISCHARGE INTO TIDAL

FLOODPLAINS, WITHIN WHICH WATER LEVELS ARE GOVERNED BY BACKWATER FROM THE POTOMAC RIVER. DUE TO THIS DISCHARGE CONDITION, AND PER

SPECIFICATIONS. PERMANENT OR TEMPORARY SOIL STABILIZATION SHALL BE APPLIED TO DENUDED AREAS WITHIN SEVEN (7) DAYS AFTER FINAL GRADE IS

DISCUSSION WITH PWC REPRESENTATIVES, STORMWATER QUANTITY MEASURES (i.e. STORMWATER BASINS) ARE NOT REQUIRED TO REDUCE THE PEAK RUNOFF RATE OR VOLUME. PERMANENT OUTLET STRUCTURES ARE DESIGNED TO INCORPORATE EROSION PROTECTION AND ENERGY DISSIPATION FOR THE 25-YEAR, 24-HOUR STORM, EXCEEDING THE REQUIREMENTS OF THE PWC DSCM FOR CHANNEL AND FLOOD PROTECTION. SEE THE HYDROLOGIC AND HYDRAULIC

ALL INSPECTIONS FOR THE SITE WILL BE MADE WEEKLY AND AFTER EACH RUNOFF PRODUCING RAIN EVENT. IN THE EVENT OF DAMAGE TO THE EROSION OR SEDIMENT CONTROL MEASURES, REPAIRS WILL BE MADE IMMEDIATELY. SEDIMENT TRAPPING DEVICES WILL BE CLEANED OUT WHEN SEDIMENT REACHES THE

CALCULATION BOOKLET PREPARED FOR THIS EROSION AND SEDIMENT CONTROL PLAN FOR THE EXISTING CONDITIONS HYDROLOGY AND A PRE-DEVELOPMENT

24. SOIL STOCKPILES AND BORROW AREAS:

SOIL WILL BE OBTAINED FROM ON-SITE BORROW AREAS AND WILL BE INCORPORATED INTO THE SUBGRADE AND THE CAP COVER SYSTEM. TOPSOIL WILL BE STORED IN TEMPORARY STOCKPILES FOR REDISTRIBUTION INTO THE FINAL SURFACE. EROSION AND SEDIMENT CONTROLS ASSOCIATED WITH THE TEMPORARY SOIL STOCKPILES AND BORROW AREAS WILL COMPLY WITH THE REQUIREMENTS OF THIS PLAN.

GENERALLY OCCUR IN THE WRITTEN ORDER BELOW OVER THE NEXT 3 YEARS. CONSTRUCTION ENTRANCES WILL BE CONSTRUCTED AS NEEDED. THE MAJORITY OF THE WORK WILL BE CONDUCTED WITHIN THE SITE. AS SUCH, VEHICLES

25. SEQUENCE OF CONSTRUCTION (SOC)

MUST PASS OVER GRAVEL ROADS INTERIOR TO THE SITE PRIOR TO ENTERING PUBLIC ROADS AND AN EQUIPMENT WASH FACILITY WILL BE AVAILABLE FOR SURFACE IMPOUNDMENT E SOC:

HE FOLLOWING IS A COMPILATION OF THE SOCS FOR THE CONSTRUCTION PROJECTS ANTICIPATED IN THE POND CLOSURE PLANS. THESE PROJECTS WILL

ITEMS 1 THROUGH 6 ARE OPERATIONAL ACTIVITIES REGULATED UNDER VIRGINIA POLLUTANT DISCHARGE ELIMINATION SYSTEM (VPDES) INDUSTRIAL DISCHARGE PERMIT AND ARE NOT SUBJECT TO PRINCE WILLIAM COUNTY (PWC) SITE PLAN APPROVAL.

2. INSTALL WATER PUMPING SYSTEM TO PUMP WATER FROM POND E TO POND D.

- 4. BEGIN MECHANICALLY DREDGING CCR FROM POND E AND PLACE IN A TEMPORARY STOCKPILE IN POND D.
- 6. BEGIN INITIAL GRADING OF POND E, WITHIN THE LIMITS OF THE POND E EMBANKMENT.
- 8. CONSTRUCT E&S CONTROLS AROUND POND E. CONSTRUCT TEMPORARY SEDIMENT BASIN (BASIN E-1). 9. INSTALL DRAINAGE CHANNELS WITHIN POND E, INCLUDING CHANNEL LININGS AND CHECK DAMS.
- 10. INSTALL DRAINAGE AND E&S CONTROLS FOR BORROW AREA 2.
- 12. PLACE FILL AND COMPLETE FINAL GRADING OF THE POND E SURFACE, UPGRADIENT OF BASIN E-1.
- 13. ADD SOIL AMENDMENTS, SEED AND STABILZE THE POND E SURFACE CONCURRENT WITH FINAL GRADING ACTIVITIES. 14. REMOVE TEMPORARY SEDIMENT BASIN (BASIN E-1).
- 15. REMOVE A PORTION OF THE POND E EMBANKMENT AND EXTEND DRAINAGE CHANNELS TO DISCHARGE OFFSITE. 16. ADD SOIL AMENDMENTS, SEED AND STABILZE THE REGRADED BASIN E-1 SURFACE

17. REMOVE PERIMETER CONTROLS FROM AROUND POND E UPON RECEIVING PERMISSION FROM THE PLAN APPROVING AUTHORITY.

THROUGH 5 ARE OPERATIONAL ACTIVITIES REGULATED UNDER VPDES INDUSTRIAL DISCHARGE PERMIT AND ARE NOT SUBJECT TO PWC SITE PLAN

3. DEWATER PONDS A, B, AND C.

. INSTALL WATER PUMPING SYSTEM TO PUMP WATER FROM PONDS A, B, AND C TO POND D.

4. BEGIN MECHANICALLY DREDGING CCR FROM PONDS A, B, AND C AND PLACE IN A TEMPORARY STOCKPILE IN POND D.

5. BEGIN INITIAL GRADING OF PONDS A, B, AND C, WITHIN THE LIMITS OF PONDS A, B, AND C EMBANKMENT. 6. CONSTRUCT E&S CONTROLS AROUND PONDS A, B, AND C.

- 6. CONSTRUCT THE SANITARY SEWER FORCEMAIN RELOCATION 7. EXCAVATE ANY REMAINING CCR FROM AREA WEST OF PONDS A, B, AND C AND HAUL CCR TO AN APPROVED OFFSITE DISPOSAL FACILITY, IF REQUIRED.
- 8. CONSTRUCT TEMPORARY SEDIMENT BASINS (BASIN B-1 AND BASIN C-1).
- 9. INSTALL DRAINAGE CHANNELS WITHIN PONDS A, B, AND C, INCLUDING CHANNEL LININGS AND CHECK DAMS. 10. IMPORT AND PLACE FILL, AND COMPLETE FINAL GRADING OF PONDS A, B, AND C SURFACES, UPGRADIENT OF BASIN B-1 AND BASIN C-1.
- 11. ADD SOIL AMENDMENTS, SEED AND STABILZE PONDS A, B, AND C SURFACE CONCURRENT WITH FINAL GRADING ACTIVITIES 12. REMOVE TEMPORARY SEDIMENT BASINS (BASIN B-1 AND BASIN C-1).

- 14. REMOVE A PORTION OF THE EMBANKMETNS FROM PONDS B AND C, AND EXTEND DRAINAGE CHANNELS TO DISCHARGE
- 15. ADD SOIL AMENDMENTS, SEED AND STABILZE THE REGRADED BASIN B-1 AND BASIN C-1 SURFACES. 16. REMOVE PERIMETER CONTROLS FROM AROUND PONDS A, B, AND C UPON RECEIVING PERMISSION FROM THE PLAN

POND D SOC:

ITEMS 1 THROUGH 6 ARE OPERATIONAL ACTIVITES REGULATED UNDER VPDES INDUSTRIAL DISCHARGE PERMIT AND ARE NOT SUBJECT TO PWC SITE PLAN APPROVAL.

- 1. CONSTRUCT PIPE/HOSE TO POND E TEMPORARY TREATMENT SYSTEM.
- 2. INSTALL WATER TREATMENT SYSTEM.
- DRAIN SURFACE WATER TO POND E THROUGH TREATMENT SYSTEM. 4. CONSTRUCT E&S CONTROLS AROUND POND D EMBANKMENT
- 5. DEWATER POND D ACTIVE (WELL POINTS AND RIM DITCH AND UNDERDRAINS)
- 6. CUT LOW POINT OF POND D STORMWATER RUNOFF CHANNEL ALONG DAM EMBANKMENT.
- 7. INSTALL UNDERDRAIN TO PHASE 1 CONFIGURATION
- 8. BORROW AREA NO. 1 DEVELOPMENT FOR POND D.
- 9. INSTALL GEOSYNTHETIC CLAY LINER ON SIDE SLOPES AS PHASE 1 FILL PROGRESSES 10. GRADE AND FILL POND D SUBGRADE (PHASE 1) - WITH ASH FROM STOCKPILE (PONDS A, B, C, & E)
- 11. PARTIALLY REMOVE POND D EMBANKMENT FOR FILL.
- 12. GRADE AND FILL POND D SUBGRADE (PHASE 1) WITH SOIL FILL FROM POND D EMBANKMENT AND BORROW 1 13. INSTALL GEOSYNTHETIC CAP SYSTEM AS PHASE 2 PROGRESSES.
- 14. CONSTRUCT POND D PHASE 2 GRADING
- 15. INSTALL SUB-SURFACE DRAIN SYSTEM AS PHASE 2 GRADING PROGRESSES.
- 16. INSTALL PHASE 2 CHANNEL LININGS
- 17. ESTABLISH PHASE 2 VEGETATION.
- 18. COMPLETE GEOSYNTHETIC CAP SYSTEM DURING PHASE 3. 19. MODIFY POND D STORMWATER CHANNEL TO FINAL DESIGN CONFIGURATION

PRINCE WILLIAM COUNTY CHECKLIST NOTE [APM, SECTION 4.05.3(B9L)]:

- 20. CONSTRUCT POND D PHASE 3 GRADING
- 21. COMPLETE CHANNEL LININGS 22. ADD SOIL AMENDMENTS, SEED, AND STABILIZE.
- $\hbox{23. REMOVE PERIMETER CONTROLS FROM AROUND POND D UPON RECEIVING PERMISSION FROM THE PLAN APPROVING } \\$ AUTHORITY.

- 1. INSTALL PERIMETER EROSION CONTROLS (SUPER SILT FENCE AND SILT FENCE, CULVERT INLET PROTECTION, ETC.).
- 2. INTIATE CONSTRUCTION OF SEDIMENT BASIN PRIOR TO CONDUCTING BORROW OPERATIONS 3. AFTER SEDIMENT BASIN RISER IS OPERATIONAL EXCAVATE BORROW AREA TO DRAIN TOWARDS SEDIMENT BASIN.
- COMPLETE EXCAVATION FOR BORROW AREA. 5. STABILIZE DENUDED AREAS

6. REMOVE PERIMETER CONTROLS UPON RECEIVING PERMISSION FROM THE PLAN APPROVING AUTHORITY.

1. A PHASE 1 ARCHAEOLOGICAL SURVEY WAS COMPLETED FOR THE PROJECT AND SENT TO THE VIRGINIA DEPARTMENT OF HISTORIC RESOURCES. THE PHASE 1 ARCHAEOLOGICAL SURVEY DEMONSTRATES THERE ARE NO KNOWN CEMETERIES OR

| ITES IN THE PROJECT AREA | · | | | |
|------------------------------------|--|-----------|------------------------------|--|
| TEMPO | DRARY SEEDING CHART (<u>TYPI</u> | CAL FOR A | ALL SHEETS) | |
| PLANTING DATES | SPECIES | | RATE (lbs/acre) | |
| SEPT. 1 - FEB. 15 | 50/50 MIX OF ANNUAL RY AND WINTER RYE | EGRASS | 75 | |
| FEB. 16 - APR. 30 | ANNUAL RYEGRASS | 5 | 80 | |
| MAY 1 - AUG. 31 | GERMAN MILLET | | 50 | |
| PERMANENT SEE | DING CHART (3:1 OR LESS) - A RPA MITIGATION A | | TSIDE OF THE RPA AND | |
| SPE | CIES | | RATE**(lbs/acre) | |
| KENTUCKY 31 | TALL FESCUE | | 128 | |
| RED TOP | P GRASS | | 2 | |
| SEASONAL N | SEASONAL NURSE CROP* | | 20 | |
| PERMANENT SEEDING | G CHART (STEEPER THAN 3:1) RPA MITIGATION A | | OUTSIDE OF THE RPA AND | |
| | SPECIES | | RATE**(lbs/acre) | |
| KENTUCK | / 31 TALL FESCUE | | 101 | |
| COMMON B | ERMUDAGRASS*** | | 7 | |
| RED | TOP GRASS | | 2 | |
| SEASONAL NURSE CROP* | | | 20 | |
| RED CLOVER | | | 20 | |
| * USE SEASONAL NURSE CR | OP IN ACCORDANCE WITH SI | EEDING D | ATES AS STATED BELOW: | |
| FEBRUARY - APRIL: MAY - AUGUST: | | | ANNUAL RYE FOXTAIL MILLET | |
| SEPTEMEBER - NOVEMBER 15: | | | ANNUAL RYE | |
| NOVEMBER 16 - IANIJARY | | | WINTER RYE | |

** TOTAL RATE IS 150 lbs/acro *** MAY THROUGH OCTOBER, USE HULLED SEED. ALL OTHER SEEDING PERIODS, USE UNHULLED. .. WEEPING LOVEGRASS MAY BE ADDED TO ANY SLOPE OR LOW MAINTENANCE MIX DURING

WARMER SEED PERIODS; ADD 10-20 lbs./acre IN MIXES . SUBMIT RECOMMENDATION FROM CERTIFIED AGRICULTURALIST FOR SEEDING AND SOIL AMENDMENTS BASED ON TESTING OF VEGETATIVE SOIL.

. UNLESS OTHERWISE INDICATED FROM SOIL-SPECIFIC ANALYSIS, SEED MIXTURES AND APPLICATION RATES SHALL BE IN ACCORDANCE WITH THESE PLANS. PERMANENT SEEDING CHART - AREAS WITHIN THE RPA AND RPA MITIGATION AREA VIRGINIA WILD RY BIG BLUESTEM REDTOP PANICGRASS PARTRIDGE PEA AUTUMN BENTGRASS BONESET MISTFLOWER COMMON SNEEZEWEED

APPLIED TO IMPACTED RPA AREAS AND RPA MITIGATION AREAS THE SEED APPLICATION RATES ARE SUBJECT TO CHANGE BASED ON TESTING OF VEGETATIVE S. SUBMIT RECOMMENDATION FROM CERTIFIED AGRICULTURALIST FOR SEEDING AND SOIL AMENDMENTS BASED ON TESTING OF VEGETATIVE SOIL.

. PERMANENT SEEDING WILL CONSIST OF A NATIVE MIXTURE SUCH AS LISTED ABOVE AND WILL BE

MARYLAND SENNA (SENNA MARILANDICA

TOTAL RATE IS 150 lbs/acr

AT A MINIMUM RATE OF 2000 lbs./ac. OR 45 lbs./1000 SQ.FT.

| 4. SERICEA LE | SPEDEZA WILL NOT BE APP | LIED AT THE SITE DURI | NG ANY SEEDING APPLICATION. | |
|--|--|-----------------------|---|------|
| | RATES: | | NOTES: | |
| MULCHES | PER ACRE | PER 1000 SQ. FT. | NOTES. | |
| STRAW AND HAY | 1 1/2 - 2 TONS (MINIMUM 2 TONS FOR WINTER COVER) | 70 - 90 lbs. | FREE FROM WEEDS AND COARSE M MUST BE ANCHORED. SPREAD W MULCH BLOWER OR BY HAND | /ITH |
| FIBER MULCH | MINIMUM 1500 lbs. | 35 lbs. | DO NOT USE AS MULCH FOR WIN COVER OR DURING HOT, DRY PERI APPLY AS SLURRY. | |
| * WHEN FIBER MULCH IS THE ONLY AVAILABLE MULCH DURING PERIODS WHEN STRAW SHOULD BE USED, APPLY | | | | PPLY |

| LIME AND FERTILIZER | RATES: | | NOTES: |
|---|------------|-------------------|---------------------------------|
| LIIVIE AIND FENTILIZEN | PER ACRE | PER 1,000 SQ. FT. | NOTES. |
| LIME | 2 TONS | 90 LBS. | AGRICULTURAL GRADE LIMESTONE |
| FERTILIZER | 1,000 LBS. | 23 LBS. | 10-20-10 |
| LIME AND FERTILIZER SHALL BE INCORPORATED INTO THE TOP 4-6 INCHES OF SOIL BY DISCING. | | | |
| SUBMIT RECOMMENDATION FROM CERTIFIED AGRICULTURALIST FOR SEEDING AND SOIL AMENDMENTS BASED ON TESTING OF VEGETATIVE SOIL. | | | |

IOHN R. KLAMU Lic. No. 048859

DRAWN BY: | CHECKED BY: | APPROVED BY

KINDEKW

SCALE:

C150132-00-000-C-D1-002

ALT./CLIENT DRAWING NUMBER:

KLAMUJR

ISSUE DATE:

12/7/2015

REVISION

DOYLEMP

DWG TYPE:

SHEET NO .:

2 OF 65

GAI DRAWING NUMBER:

GAI FILE NUMBER:

FOR EROSION AND SEDIMENT CONTROL PLANS

CHECKLIST

Minimum Standards - All applicable Minimum Standards must be addressed.

NARRATIVE

- Project description Briefly describes the nature and purpose of the land-disturbing activity, and the area (acres) to be disturbed.

 SEE SHEET 002: IN E&SC NARRATIVE SECTION PROJECT DESCRIPTION
- Existing site conditions A description of the existing topography, vegetation and drainage. SEE SHEET 002; IN E&SC NARRATIVE SECTION EXISTING CONDITIONS
- Adjacent areas A description of neighboring areas such as streams, lakes, residential areas, roads, etc., which might be affected by the land disturbance. SEE SHEET 002; IN E&SC NARRATIVE SECTION ADJACENT AREAS
- Off-site areas Describe any off-site land-disturbing activities that will occur (including borrow sites, waste or surplus areas, etc.). Will any other areas be disturbed? OFF-SITE AREAS ARE NOT ANTICIPATED TO BE DISTURBED
- Soils A brief description of the soils on the site giving such information as soil name, mapping unit, erodibility, permeability, depth, texture and soil structure. SEE SHEET 002; IN E&SC NARRATIVE SECTION SOILS
- X

 <u>Critical areas</u> A description of areas on the site which have potentially serious erosion problems (e.g., steep slopes, channels, wet weather/underground springs, etc.). SEE SHEET 002; IN E&SC NARRATIVE SECTION CRITICAL AREAS
- Erosion and sediment control measures A description of the methods which will be used to control erosion and sedimentation on the site. (Controls should meet the specifications in Chapter 3.)

 SEE SHEET 002; IN E&SC NARRATIVE SECTION E&SC MEASURES.
 SEE SHEET 002; IN E&SC NARRATIVE SECTION STRUCTURAL PRACTICES, SEE SHEET 11 THROUGH SHEET 45.
 SEE SHEET 002; IN E&SC NARRATIVE SECTION VEGETATIVE PRACTICES, SEE SHEET 11
- THROUGH SHEET 45.

 X

 Permanent stabilization A brief description, including specifications, of how the site will be stabilized after construction is completed.

 SEE SHEET 002; IN E&SC NARRATIVE SECTION PERMANENT AND TEMPORARY STABILIZATION.
- Stormwater runoff considerations Will the development site cause an increase in peak runoff rates? Will the increase in runoff cause flooding or channel degradation downstream? Describe the strategy to control stormwater runoff. SEE SHEET 002; IN E&SC NARRATIVE SECTION STORMWATER MANAGEMENT SEE SHEET 002; IN GENERAL E&SC NOTES, NOTE 30.
 - <u>Calculations</u> Detailed calculations for the design of temporary sediment basins, permanent stormwater detention basins, diversions, channels, etc. Include calculations for pre- and post-development runoff.

1992

Checklist (continued)

SITE PLAN

- Vicinity map A small map locating the site in relation to the surrounding area. Include any landmarks which might assist in locating the site.

 SEE SHEET 001
- X Indicate north The direction of north in relation to the site.
- X
 Limits of clearing and grading Areas which are to be cleared and graded.
- X

 THE PLANNED LIMITS OF DISTURBANCE ARE SHOWN ON THE PLAN SHEETS.

 Existing contours The existing contours of the site.
- X

 TYPICAL OF PLAN SHEETS

 Final contours Changes to the existing contours, including final drainage
- TYPICAL OF PLAN SHEETS

 X
 Existing vegetation The existing tree lines, grassed areas, or unique
- vegetation.

 TYPICAL OF PLAN SHEETS
- X Soils The boundaries of different soil types.
- SEE SHEETS 056 THROUGH 059
- Existing drainage patterns The dividing lines and the direction of flow for the different drainage areas. Include the size (acreage) of each drainage area.

 SEE SHEET 056 THROUGH SHEET 059
- Critical erosion areas Areas with potentially serious erosion problems. (See Chapter 6 for criteria.) AREAS LISTED UNDER CRITICAL AREAS IN E&SC NARRATIVE TYPICAL AMONG SHEET 11 THROUGH SHEET 45
- X Site Development Show all improvements such as buildings, parking lots, access roads, utility construction, etc.
- X

 TYPICAL OF PLAN DRAWINGS; SEE SHEET 004 THROUGH SHEET 045

 Location of practices The locations of erosion and sediment controls and
- stormwater management practices used on the site. Use the standard symbols and abbreviations in Chapter 3 of this handbook.

 SEE SHEET 011 THROUGH SHEET 045

 N/A

 Off-site areas Identify any off-site land-disturbing activities (e.g., borrow
- sites, waste areas, etc.). Show location of erosion controls. (Is there sufficient information to assure adequate protection and stabilization?)

 OFF-SITE AREAS ARE NOT ANTICIPATED
- Detail drawings Any structural practices used that are not referenced to the E&S handbook or local handbooks should be explained and illustrated with detail drawings.

 SEE SHEET 050 THROUGH SHEET 055
- X <u>Maintenance</u> A schedule of regular inspections and repair of erosion and sediment control structures should be set forth.
 - SEE SHEET 002; IN E&SC NARRATIVE SECTION MAINTENAMCE SCHEDULE SEE SHEET 002; GENERAL NOTES, NOTES 10, 11, &15

NOTES REGARDING BALD EAGLE BUFFERS:

- 1. ACCESS TO POND E IS RESTRICTED TO THOSE AREAS OUTSIDE OF THE PROTECTIVE 660' BALD EAGLE BUFFER. THIS WOULD INCLUDE EQUIPMENT ENTRY TO AND EXIT FROM THE POND, EQUIPMENT REFUELING AND ASSOCIATED MAINTENANCE/REPAIR IF NECESSARY.
- 2. EQUIPMENT MOVEMENT WITHIN POND E IS RESTRICTED TO THOSE AREAS OUTSIDE OF THE PROTECTIVE 660' BALD EAGLE BUFFER. THE ONLY EXCEPTION TO THIS REQUIREMENT WILL ALLOW FOR A LIMITED PRESENCE INSIDE THE 660' BUFFER, ESTIMATED TO OCCUR NO CLOSER THAN 420' TO THE NEST, NECESSARY TO REACH THIS AREA OF THE POND. THIS WORK INSIDE THE BUFFER MUST BE SEQUENCED TO BEGIN AFTER TREE LEAF OUT TO PROVIDE AN ENHANCED NOISE AND VISUAL BUFFER.
- 3. ACCESS TO POND D IS RESTRICTED TO THOSE AREAS OUTSIDE OF THE PROTECTIVE 660' BALD EAGLE BUFFER. THIS WOULD INCLUDE EQUIPMENT ENTRY TO AND EXIT FROM THE POND, EQUIPMENT REFUELING AND ASSOCIATED MAINTENANCE/REPAIR IF NECESSARY.
- 4. EQUIPMENT MOVEMENT WITHIN POND D IS LARGELY RESTRICTED TO THOSE AREAS OUTSIDE OF THE PROTECTIVE 660' BALD EAGLE BUFFER. NOTIFICATION SHALL BE PROVIDED TO ENVIRONMENTAL BIOLOGY PRIOR TO INITIATING WORK ACTIVITIES WITHIN THE 330' AND 660' BUFFER ZONE OF POND D. WORK WITHIN THE 660' ZONE SHOULD ALSO, AS MUCH AS REASONABLY POSSIBLE, BE SCHEDULED TO OCCUR DURING THE NON-BREEDING SEASON FROM JULY 16 DECEMBER 14. WORK IS NOT PERMITTED WITHIN THE 330' BUFFER ZONE DURING THE BREEDING SEASON.
- 5. ANY STAGING OF EQUIPMENT, FACILITIES OR MATERIALS ON THE SITE IS RESTRICTED TO THOSE AREAS OUTSIDE OF THE PROTECTIVE 660' BALD EAGLE BUFFERS ASSOCIATED WITH PONDS E AND D.

 GEOTECHNICAL NOTE:
- 1. A GEOTECHNICAL REPORT IS NOT REQUIRED FOR THE PRINCE WILLIAM COUNTY SITE PLAN SUBMITTAL.. A GEOTECHNICAL EXPLORATION AND TESTING PROGRAM HAS BEEN COMPLETED AND A GEOTECHNICAL REPORT HAS BEEN PREPARED FOR SUBMISSION TO OTHER AGENCIES, AS REQUIRED.

| PROPOSE | D EROSION AND SEDIMENT CONTROL LEGEND | LIST OF ABBRE | EVIATIONS |
|---------|--|---------------|---|
| | | ABBREVIATION | DEFINITION |
| SF | SILT FENCE ——————————————————————————————————— | CCR | COAL COMBUSTION RESIDUALS |
| SSF | SUPER SILT FENCE ——————————————————————————————————— | V.P.D.E.S. | VIRGINIA POLLUTANT DISCHARGE ELIMINATION SYSTEM |
| (IP) | STORM DRAIN INLET PROTECTION | ВМР | BEST MANAGEMENT PRACTICE |
| CIP | CULVERT INLET PROTECTION | V.E.S.C.H. | VIRGINIA EROSION & SEDIMENT CONTROL HANDBOOK |
| ST | TEMPORARY SEDIMENT TRAP | SSD | SUBSURFACE DRAIN |
| SB | TEMPORARY SEDIMENT BASIN | QC | QUALITY CONTROL |
| SCC | STORMWATER CONVEYANCE CHANNEL | UD | UNDERDRAIN |
| OP | OUTLET PROTECTION | AR | ACCESS ROAD |
| B/M | SOIL STABILIZATION BLANKETS AND MATTING | VDOT | VIRGINIA DEPARTMENT OF TRANSPORTATION |
| TO | TOPSOILING | CQC | CONSTRUCTION QUALITY CONTROL |
| TS | TEMPORARY SEEDING | ADS | ADVANCED DRAINAGE SYSTEMS |
| PS | PERMANENT SEEDING | SDR | STANDARD DIMENSION RATIO |
| MU | MULCHING | HDPE | HIGH-DENSITY POLYETHYLENE |
| CD | ROCK CHECK DAM | LLDPE | LOW LINEAR-DENSITY POLYETHYLENE |
| DD | TEMPORARY DIVERSION DIKE | GCL | GEOSYNTHETIC CLAY LINER |
| RR | RIPRAP | GDN | GEOSYNTHETIC DRAINAGE NET |
| SAF | SAFETY FENCE —— CF —— CF —— | ССМ | CELLULAR CONCRETE MAT |
| CE | CONSTRUCTION ENTRANCE | | |
| | LIMITS OF DISTURBANCE ———LOD——LOD—— | | |


PLAN REVIEW MINIMUM STANDARD CHECKLIST


YES NO NA

MS-1 Have temporary and permanent stabilization been addressed in narrative? Are practices shown on the plan? SEE SHEET 11 THROUGH SHEET45 Seed specifications? SEE SHEET 002 IN E&SC NARRATIVE SECTION VEGETATIVE PRACTICE Mulching? SEE SHEET 002 IN E&SC NARRATIVE SECTION VEGETATIVE PRACTICE SEE SHEET 11 THROUGH 45 ROADS, INLET PROTECTION, OUTLET PROTECTION, AND RIPRAP MS-2 Has stabilization of soil stockpiles been addressed in narrative? Are sediment trapping measures provided? SEE SHEET 002 IN GENERAL E&SC NOTES, NOTE 17 SEE SHEET 002 IN GEÑÊRĂL E&SC NÔTES, NOTES 10.d, 12, AND 13 MS-3 Has maintenance of permanent stabilization been addressed? SEE SHEET 002 IN GENERAL E&SC NOTES, NOTE10.g MS-4 Are sediment trapping facilities to be constructed as a first step in LDA? Has maintenance of practices been addressed? (i.e. repair of structures and removal accumulated sediment) SEE SHEET 002 IN GENERAL E&SC NOTES, NOTES 10 AND 12 MS-5 Has stabilization of earthen structures been addressed? SEE SHEET 002 IN GENERAL E&SC NOTES, NOTE 19 MS-6 Are sediment basins required where needed? SEE SHEET 002 IN GENERAL E&SC NOTES, NOTE 12 [] MS-7 Has stabilization of cut and fill slopes been adequately addressed? SEE SHEET 002 IN GENERAL E&SC NOTES, NOTE 20 [] MS-8 Are paved flumes, channels, or slope drains required where necessary? SEE SHEET 002 IN GENERAL E&SC NOTES, NOTE 21 MS-9 Have water seeps from slope face, adequate drainage or other protection addressed? SEE SHEET 002 IN GENERAL E&SC NOTES, NOTE 22 MS-10 Is adequate inlet protection required on all operational storm sewer inlets? SEE SHEET 002 IN GENERAL E&SC NOTES, NOTE 23 MS-11 Are channel lining and/or outlet protection required on stormwater conveyance channels? SEE SHEET 002 IN GENERAL E&SC NOTES, NOTE 24 MS-12 Are in-stream construction measures required so that channel damage is minimized? SEE SHEET 002 IN GENERAL E&SC NOTES, NOTE 25 MS-13 Are temporary stream crossings of non-erodible material required where necessary? SEE SHEET 002 IN GENERAL E&SC NOTES, NOTE 25 MS-14 Are all applicable federal, state and local regulations pertaining to working in or crossing live watercourses being met? SEE SHEET 002 IN GENERAL E&SC NOTES, NOTE 27 MS-15 Has re-stabilization of areas subject to in-stream construction been adequately addressed? SEE SHEET 002 IN GENERAL E&SC NOTES, NOTE 28 MS-16 Has stabilization of utility trenches been addressed? SEE SHEET 002 IN GENERAL E&SC NOTES, NOTE 29 [] MS-17 Has the prevention of transporting of soil and mud onto public roadways been adequately addressed? (i.e. Construction Entrances, Wash Racks, daily cleaning of roadways, transport of sediment to a trapping facility)
SEE SHEET 002 IN GENERAL E&SC NOTES, NOTE 33 MS-18 Has the removal of temporary practices been addressed? SEE SHEET 002 IN GENERAL E&SC NOTES, NOTE 16 MS-19 Are properties and waterways downstream from the development adequately protected from

erosion and sediment deposition due to increases in peak stormwater runoff?


SEE SHEET 002 IN GENERAL Ê&SC NOTES, NOTE 30








GAI DRAWING NUMBER:


003

















PHASE 1


SANITARY SEWER FORCEMAIN RELOCATION GENERAL NOTES:


- A. PRIOR TO COMMENCING WORK ACTIVITIES:
- APPROVED EROSION AND SEDIMENT CONTROLS ARE TO BE INSTALLED AND MAINTAINED IN ACCORDANCE WITH THE PLANS AND SPECIFICATIONS.
- 2. CONTRACTOR SHALL FIELD LOCATE ALL UNDERGROUND UTILITIES IN ADVANCE OF CONSTRUCTION AND TAKE MEASURES TO PROTECT THEM FROM DAMAGE DURING CONSTRUCTION.
- CONTRACTOR SHALL STAKE OUT ALL UTILITIES AND LIMITS OF WORK AREAS.
- 4. PROVIDE THE OWNER WITH A PLANNED CONSTRUCTION SCHEDULE/SEQUENCE AND TESTING PLAN
- 5. CONTRACTOR SHALL FIELD VERIFY THE FORCEMAIN SIZE AND MATERIAL AT THE TIE-IN POINTS PRIOR TO ORDERING PIPING, FITTINGS, COUPLINGS AND JOINT RESTRAINTS. IN THE EVENT AN UNEXPECTED PIPE SIZE OR MATERIAL IS IDENTIFIED, NOTIFY THE OWNER AND ENGINEER IMMEDIATELY.
- B. PRIOR TO PERFORMING THE CUT-INS TO THE EXISTING FORCEMAIN:
- 1. NOTIFY THE STATION AT LEAST TWO WEEKS IN ADVANCE OF INTENT TO PERFORM THE CUT-INS AND TO COORDINATE THE TIME OF THE REQUIRED SHUTDOWN.
- 2. VERIFY THAT THE OWNER'S SANITARY SEWAGE TRANSFER PUMPS HAVE BEEN DE-ENERGIZED AND LOCK-OUT/TAG-OUT ('LOTO') PROCEDURES HAVE BEEN IMPLEMENTED.
- 3. INSTALL VALVE CUT-IN TO ISOLATE DOWNSTREAM USERS DURING FORCEMAIN RELOCATION WORK. SEE "PROPOSED VALVE CUT-IN LOCATION PLAN", THIS SHEET.
- 4. THE SECTION OF FORCEMAIN AFFECTED BY THE TIE-INS SHALL BE PUMPED DRY TO A TANKER TRUCK OR OTHER APPROVED LOCATION AND DISPOSED AS ACCEPTABLE TO THE OWNER AND JURISDICTIONAL AGENCY. THIS SHALL BE ACCOMPLISHED USING A WATERTIGHT TAPPING SLEEVE AND VALVE ON A SECTION OF PIPE THAT IS TO BE ABANDONED, AND INSTALLING WATERTIGHT PIPING TO THE PUMP AND TANKER TRUCK OR OTHER APPROVED LOCATION.

- C. <u>FORCEMAIN INSTALLATION:</u>
- 1. ALL BENDS/FITTINGS SHALL INCLUDE THRUST BLOCKING OR RESTRAINTS AT EACH PIPE AND FITTING JOINT AS REQUIRED IN THE THRUST BLOCK DETAILS AND RESTRAINED JOINT SCHEDULES. HOWEVER, RESTRAINTS AT EXISTING FORCEMAIN PIPE AND FITTING JOINTS (THAT ARE TO REMAIN AFTER PIPE ABANDONMENT) ARE REQUIRED PER THE RESTRAINED JOINT SCHEDULES TO BRACE THE FORCEMAIN DURING REMOVAL OF THE SECTION TO BE ABANDONED.
- 2. THE CONTRACTOR SHALL PERFORM AN APPROVED HYDROSTATIC PRESSURE TEST ON THE NEWLY INSTALLED FORCEMAIN IN ACCORDANCE WITH THE CONTRACT SPECIFICATIONS.
- 3. THE CONTRACTOR SHALL CORRECT ANY LEAKS IN THE NEWLY INSTALLED FORCEMAIN AND RE-TEST, AS NECESSARY, UNTIL AN ACCEPTABLE HYDROSTATIC PRESSURE TEST RESULT IS ATTAINED.
- 4. UPON COMPLETION OF AN ACCEPTABLE HYDROSTATIC PRESSURE TEST, THE CONTRACTOR SHALL COORDINATE WITH THE OWNER TO RETURN THE SANITARY FORCEMAIN SYSTEM INTO OPERATION AND REMOVE ALL 'LOTO' DEVICES.
- 5. THE CONTRACTOR SHALL PLAN AND MAKE EVERY EFFORT TO COMPLETE THE FORCEMAIN TIE-INS AND MINIMIZE DOWNTIME TO 4 HOURS OR AS OTHERWISE AGREED IN ADVANCE WITH THE OWNER.
- 6. DETAILS ASSOCIATED WITH THE SANITARY SEWER FORCEMAIN RELOCATION ARE SHOWN ON SHEETS 53 AND 54.
- D. <u>FORCEMAIN MATERIALS:</u>
- 1. PIPE SHALL BE GASKETED, PUSH-ON JOINT PVC PRESSURE PIPE IN ACCORDANCE WITH THE CONTRACT SPECIFICATIONS.
- 2. FITTINGS SHALL BE GASKETED, PUSH-ON JOINT PVC WITH RESTRAINT HARNESSES OR MECHANICAL JOINT DUCTILE IRON WITH WEDGE ACTION RETAINER GLANDS IN ACCORDANCE WITH THE CONTRACT

SPECIFICATIONS. IN LIEU OF RETAINER GLANDS THRUST BLOCKS ARE ALSO ACCEPTABLE. 45-DEG VERTICAL - 45-DEG VERTICAL BENDS (TYP. OF 2) BENDS (TYP. OF 2) EX. GROUND __ EX. 30" PIPF FX 30" PIPF -_INV. 23.7 1' CLR. (MIN.) 1' CLR. (MIN.) - PROP. ∣4" PVC FORCEMA[N 1+00 2+00 2+50 3+50 1+50 3+00


PROPOSED RELOCATED FORCEMAIN SEWERLINE PROFILE





- 1. LOCATION OF FORCEMAIN APPROXIMATED FROM AS-BUILT DRAWING FOR "POSSUM POINT POWER STATION SANITARY SEWER PUMP STA./FORCEMAIN". DRAWING NO. 9158A-BC-006, REV 1, DATED 05-SEPT-2002.
- 2. CONTRACTOR TO VERIFY LOCATION OF EXISTING FORCEMAIN SEWER AND AIR RELEASE
- 3. CONTRACTOR SHALL INSTALL SILT FENCING AND OTHER EROSION AND SEDIMENT CONTROL BMPS AS NECESSARY DOWNGRADIENT OF THE WORK AREA PRIOR TO ANY EARTH DISTURBING ACTIVITIES.
- 4. PROP. 4" VALVE CUT-IN TO BE LOCATED 15' DOWNSTREAM OF THE EXISTING AIR RELEASE VALVE. LOCATION OF PROPOSED VALVE TO BE APPROVED BY OWNER'S REPRESENTATIVE PRIOR TO INSTALLATION.

PROPOSED VALVE CUT-IN LOCATION PLAN



ROW AND BOUNDARY SURVEY INFORMATION SHOWN BY GAI CONSULTANTS DATED, 7-27-2015

VA-N NAD83 (2011) NAVD88 (GEOID 12A) 1 FT. CONTOUR INTERVALS

EXISTING TOPOGRAPHY PREPARED BY KEDDAL AERIAL MAPPING. PHOTOGRAPHY DATED 02-13-2015.

SUPPLEMENTED BY GROUND SURVEY PERFORMED BY GAI CONSULTANTS, INC. AND FROM INFORMATION

MAPPING REFERENCE:

PROVIDED BY DOMINION.

