VPDES PERMIT PROGRAM FACT SHEET

This document gives pertinent information concerning the VPDES Permit listed below. This permit is being processed as a MAJOR, MUNICIPAL permit.

VA0081281 D 1. PERMIT NO.: VA0081941 EXPIRATION DATE: 1/27/2013 FACILITY NAME AND LOCAL MAILING FACILITY LOCATION ADDRESS (IF DIFFERENT) 2. ADDRESS Hampton Roads Sanitation District Virginia Initiative STP 4201 Powhatan Ave 1436 Air Rail Ave Norfolk, VA 23508 Virginia Beach, VA 23455 CONTACT AT FACILITY: CONTACT AT LOCATION ADDRESS NAME: Jamie Heisig-Mitchell NAME: N/A TITLE: Chief of Technical Services TITLE: PHONE: (757) 460-4220 PHONE: З. OWNER CONTACT: (TO RECEIVE PERMIT) CONSULTANT CONTACT: NAME: Mr. Edward G. Henifin NAME: N/A TITLE: General Manager FIRM NAME: COMPANY NAME: HRSD ADDRESS: ADDRESS: 1436 Air Rail Ave Virginia Beach, VA 23455 **PHONE:** (757) 460-2261 PHONE: (PERMIT DRAFTED BY: DEQ, Water Permits, Regional Office Permit Writer(s): Deanna Austin () Date(s): 3/20/12-4/3/12Date(s): 4/10/12 Reviewed By: Mark Sauer 5. PERMIT ACTION: (X) Reissuance () Revoke & Reissue () Owner Modification () Issuance () Change of Ownership/Name [Effective Date: () Board Modification SUMMARY OF SPECIFIC ATTACHMENTS LABELED AS: 6. Site Inspection Report/Memorandum' Attachment 1 Attachment 2 Discharge Location/Topographic Map Attachment 3 Schematic/Plans & Specs/Site Map/Water Balance Attachment TABLE I - Discharge/Outfall Description 4 Attachment __ 5 TABLE II - Effluent Monitoring/Limitations 6 _ Effluent Limitations/Monitoring Rationale/Suitable Attachment Data/Antidegradation/Antibacksliding Special Conditions Rationale Attachment 7 Attachment 8 Toxics Monitoring/Toxics Reduction/WET Limit Rationale Attachment Material Stored Attachment Receiving Waters Info./Tier Determination/STORET Data/Stream Modeling Attachment_9 303(d) Listed Segments Attachment 10 TABLE III(a) and TABLE III(b) - Change Sheets NPDES Industrial Permit Rating Worksheet and EPA Permit Checklist Attachment 11 Attachment 12 Chronology Sheet Attachment Public Participation

PERMIT CHARACTERIZATION: (Check as many as appropriate) (X) Effluent Limited (X) Existing Discharge () Proposed Discharge (X) Water Quality Limited () WET Limit (X) Municipal SIC Code #4952 () Interim Limits in Permit () Industrial () Interim Limits in Other Document SIC Code(s) () Compliance Schedule Required (X) POTW () Site Specific WQ Criteria () PVOTW () Variance to WQ Standards () Private () Water Effects Ratio () Federal (X) Discharge to 303(d) Listed Segment () State (X) Toxics Management Program Required () Publicly-Owned Industrial () Toxics Reduction Evaluation () Storm Water Management Plan (X) Pretreatment Program Required () Possible Interstate Effect (X) CBP Significant Dischargers List RECEIVING WATERS CLASSIFICATION: River basin information. 8. Outfall No: 001 Receiving Stream: Elizabeth River River Mile: 2-ELI0037.37 Basin: James River (Lower) Subbasin: NA Section: 1 Class: II Special Standard(s): a, z, bb Tidal: YES 7-Day/10-Year Low Flow: N/A 1-Day/10-Year Low Flow: N/A 30-Day/5-Year Low Flow: N/A Harmonic Mean Flow: N/A Outfall No(s): 002, 004-014 Receiving Stream: Unnamed Tributary to Elizabeth River River Mile: 2-ELI003.37 (002, 003, 010-014) 2-ELI003.42 (004-009) Basin: James River (Lower) Subbasin: N/A Section: 1 Class: II Special Standard(s): a, z, bb Tidal: YES 7-Day/10-Year Low Flow: N/A ,1-Day/10-Year Low Flow: N/A 30-Day/5-Year Low Flow: N/A Harmonic Mean Flow: N/AFACILITY DESCRIPTION: Describe the type facility from which the discharges originate. Existing municipal discharge resulting from the discharge of treated domestic sewage. LICENSED OPERATOR REQUIREMENTS: () No (X) Yes Class: I RELIABILITY CLASS: I

9.

10.

11.

	Performed By: Steven Long
	SEE ATTACHMENT 1
.3.	<u>DISCHARGE(S)</u> LOCATION DESCRIPTION: Provide USGS Topo which indicates the discharge location, significant (large) discharger(s) to the receiving stream, water intakes, and other items of interest.
•	Name of Topo: Norfolk, North Quadrant No.: 36A SEE ATTACHMENT 2
4.	ATTACH A SCHEMATIC OF THE WASTEWATER TREATMENT SYSTEM(S) [IND. & MUN.]. FOR INDUSTRIAL FACILITIES, PROVIDE A GENERAL DESCRIPTION OF THE PRODUCTION CYCLE(S) AND ACTIVITIES. FOR MUNICIPAL FACILITIES, PROVIDE A GENERAL DESCRIPTION OF THE TREATMENT PROVIDED.
	Narrative: Treatment at this facility includes raw influent pumps, flow measurement, screening, grit removal, primary and secondary clarification activated sludge aeration including biological nutrient removal, phosphorous removal chlorination and prior to discharge into the main stem of the Elizabeth River via gravity. Solids handling consists of centrifuge dewatering and incineration. SEE ATTACHMENT 3
5.	<u>DISCHARGE DESCRIPTION</u> : Describe each discharge originating from this facility.
	SEE ATTACHMENT 4
6.	COMBINED TOTAL FLOW:
-	TOTAL: 40.04 MGD (for public notice)
• -	PROCESS FLOW: MGD (IND.)
	NONPROCESS/RAINFALL DEPENDENT FLOW: 0.041 (Est.)
	DESIGN FLOW: 40 MGD (MUN.)
7.	STATUTORY OR REGULATORY BASIS FOR EFFLUENT LIMITATIONS AND SPECIAL CONDITIONS: (Check all which are appropriate)
. •	X State Water Control Law Clean Water Act VPDES Permit Regulation (9 VAC 25-31-10 et seq.) X EPA NPDES Regulation (Federal Register) EPA Effluent Guidelines (40 CFR 133 or 400 - 471) X Water Quality Standards (9 VAC 25-260-5 et seq.) Wasteload Allocation from a TMDL or River Basin Plan
8.	EFFLUENT LIMITATIONS/MONITORING: Provide all limitations and monitoring requirements being placed on each outfall.
	SEE TABLE II - ATTACHMENT 5

REPORT DATE: 2/25/10

SITE INSPECTION DATE: 2/11/10

12.

19. EFFLUENT LIMITATIONS/MONITORING RATIONALE: Attach any analyses of an outfall by individual toxic parameter. As a minimum, it will include: statistics summary (number of data values, quantification level, expected value, variance, covariance, 97th percentile, and statistical method); wasteload allocation (acute, chronic and human health); effluent limitations determination; input data listing. Include all calculations used for each outfall and set of effluent limits and those used in any model(s). Include all calculations/documentation of any antidegradation or antibacksliding issues in the development of any limitations; complete the review statements below. Provide a rationale for limiting internal waste streams and indicator pollutants. Attach chlorine mass balance calculations, if performed. Attach any additional information used to develop the limitations, including any applicable water quality standards calculations (acute, chronic and human health).

OTHER CONSIDERATIONS IN LIMITATIONS DEVELOPMENT:

VARIANCES/ALTERNATE LIMITATIONS: Provide justification or refutation rationale for requested variances or alternatives to required permit conditions/limitations. This includes, but is not limited to: waivers from testing requirements; variances from technology guidelines or water quality standards; WER/translator study consideration; variances from standard permit limits/conditions.

No variances were given during this permit reissuance.

SUITABLE DATA: In what, if any, effluent data were considered in the establishment of effluent limitations and provide all appropriate information/calculations.

All suitable effluent data were reviewed.

ANTIDEGRADATION REVIEW: Provide all appropriate information/calculations for the antidegradation review.

The receiving stream has been classified as tier 1; therefore, no further review is needed. Permit limits have been established by determining wasteload allocations which will result in attaining and/or maintaining all water quality criteria which apply to the receiving stream, including narrative criteria. These wasteload allocations will provide for the protection and maintenance of all existing uses.

ANTIBACKSLIDING REVIEW: Indicate if antibacksliding applies to this permit and, if so, provide all appropriate information.

There are no backsliding issues to address in this permit (i.e., limits as stringent or more stringent when compared to the previous permit).

SEE ATTACHMENT 6

20. SPECIAL CONDITIONS RATIONALE: Provide a rationale for each of the permit's special conditions.

SEE ATTACHMENT 7

21. TOXICS MONITORING/TOXICS REDUCTION AND WET LIMIT SPECIAL CONDITIONS RATIONALE:

Provide the justification for any toxics monitoring program and/or toxics reduction program and WET limit.

SEE ATTACHMENT 8

22. SLUDGE DISPOSAL PLAN: Provide a description of the sludge disposal plan (e.g., type sludge, treatment provided and disposal method). Indicate if any of the plan elements are included within the permit.

Sludge from this facility are incinerated in one of two onsite multiple hearth incinerators. Alternative disposal plans include transport to another HRSD incinerator or hauling to an approved landfill for disposal.

23. <u>MATERIAL STORED</u>: List the type and quantity of wastes, fluids, or pollutants being stored at this facility. Briefly describe the storage facilities and list, if any, measures taken to prevent the stored material from reaching State waters.

The materials stored on site include sodium hypochlorite, sodium bisulfate, sodium hydroxide, ferric chloride, polymer, muriatic acid, fuel oil, ammonia, gasoline and diesel fuel. The materials are either stored in buildings with drains connected to the treatment system or are in contained areas. Fuel tanks are double walled.

24. RECEIVING WATERS INFORMATION: Refer to the State Water Control Board's Water Quality Standards [e.g., River Basin Section Tables (9 VAC 25-260-5 et seq.). Use 9 VAC 25-260-140 C (introduction and numbered paragraph) to address tidal waters where fresh water standards would be applied or transitional waters where the most stringent of fresh or salt water standards would be applied. Attach any memoranda or other information which helped to develop permit conditions (i.e. tier determinations, PReP complaints, special water quality studies, STORET data and other biological and/or chemical data, etc.

SEE ATTACHMENT 9

25 <u>305(b)/303(d) Listed Segments</u>: Indicate if the facility discharges to a segment that is listed on the current 303(d) list and, if so, provide all appropriate information/calculations.

This facility discharges directly to the Elizabeth River. This receiving stream segment has been listed in Category 5 of the 305(b)/303(d) list for non-attainment of DO, PCB in Fish Tissue, and Aquatic Life, . EPA approved the Chesapeake Bay TMDL on 12/29/10: for this segment for nitrogen, phosphorus and TSS. Because an aggregated WLA exists, the permit did not receive an individual WLA. The aggregated WLA is presented as a delivered load for each of the impaired 92 Bay segments.

The Water Quality Management Plan covered under regulation 9 VAC25-720-120C provides the WLAs for which the Nutrient GP are based from.

26. CHANGES TO PERMIT: Use TABLE III(a) to record any changes from the previous permit and the rationale for those changes. Use TABLE III(b) to record any changes made to the permit during the permit processing period and the rationale for those changes [i.e., use for comments from the applicant, VDH, EPA, other agencies and/or the public where comments resulted in changes to the permit limitations or any other changes associated with the special conditions or reporting requirements].

SEE ATTACHMENT 10

- 27. NPDES INDUSTRIAL PERMIT RATING WORKSHEET: N/A This is a municipal facility.
- 28. DEQ PLANNING COMMENTS RECEIVED ON DRAFT PERMIT: Document any comments received from DEQ planning.

The discharge is addressed in the water quality management plan and appears to be in conformance.

29. <u>PUBLIC PARTICIPATION</u>: Document comments/responses received during the public participation process. If comments/responses provided, especially if they result in changes to the permit, place in the attachment.

<u>VDH/DSS COMMENTS RECEIVED ON DRAFT PERMIT</u>: Document any comments received from the Virginia Dept. of Health and the Div. of Shellfish Sanitation and noted how resolved.

The VDH reviewed the application and waived their right to comment and/or object on the adequacy of the draft permit. Memo received 3/9/12.

The DSS has no comments on the application/draft permit. Memo received 4/18/12.

EPA COMMENTS RECEIVED ON DRAFT PERMIT: Document any comments received from the U.S. Environmental Protection Agency and noted how resolved.

EPA has no objections to the adequacy of the draft permit. Email received 5/8/12.

ADJACENT STATE COMMENTS RECEIVED ON DRAFT PERMIT: Document any comments received from an adjacent state and noted how resolved.

Not Applicable.

OTHER AGENCY COMMENTS RECEIVED ON DRAFT PERMIT: Document any comments received from any other agencies (e.g., VIMS, VMRC, DGIF, etc.) and noted how resolved.

Not Applicable.

OTHER COMMENTS RECEIVED FROM RIPARIAN OWNERS/CITIZENS ON DRAFT PERMIT: Document any comments received from other sources and note how resolved.

The application and draft permit have received public notice in accordance with the VPDES Permit Regulation, and no comments were received.

DESCRIBE PN COMMENTS AND RESOLUTIONS. PROVIDE PUBLIC HEARING DATE AND REFERENCE BACKGROUND MEMORANDUM, IF APPROPRIATE.

PUBLIC NOTICE INFORMATION: Comment Period: Start Date 4/22/12 End Date 5/22/12

Persons may comment in writing or by e-mail to the DEQ on the proposed issuance/ reissuance/modification of the permit within 30 days from the date of the first notice. Address all comments to the contact person listed below. Written or e-mail comments shall include the name, address, and telephone number of the writer, and shall contain a complete, concise statement of the factual basis for comments. Only those comments received within this period will be considered. The Director of the DEQ may decide to hold a public hearing if public response is significant. Requests for public hearings shall state the reason why a hearing is requested, the nature of the issues proposed to be raised in the public hearing and a brief explanation of how the requestor's interests would be directly and adversely affected by the proposed permit action.

All pertinent information is on file and may be inspected, and arrangements made for copying by contacting Deanna Austin at: Department of Environmental Quality (DEQ), Tidewater Regional Office, 5636 Southern Boulevard, Virginia Beach, VA 23462. Telephone: 757-518-2008 E-mail:deanna.austin@deq.virginia.gov

Following the comment period, the Board will make a determination regarding the proposed issuance/reissuance/modification. This determination will become effective, unless the Director grants a public hearing. Due notice of any public hearing will be given.

30. ADDITIONAL FACT SHEET COMMENTS/PERTINENT INFORMATION:

ATTACHMENT 1

SITE INSPECTION REPORT/MEMORANDUM

Facility:	HRSD – Virginia Initiative Plant WWTP
Gounty/city:	Norfolk



DEPARTMENT OF ENVIRONMENTAL QUALITY WASTEWATER FACILITY INSPECTION REPORT PART 1

Inspection date:	Fel	oruary 11	, 2010	Date form	completed:		February 25,	2010		
Inspection by:	Ste	even J.E.	Long	Inspection	n agency:		DEQ/TRO	5		
Time spent:		4 hour	s	Announce	ed Inspection:	[]	/es [√]N	4o		
Reviewed by: Kenneth T. Rau	ım			Photo	ographs taken a	t site? [√] Yes []	No		
Present at inspection:			uperintend , P.E. – Pla		er					
FACILITY TYPE:			·	FACII	LITY CLASS:		,			
(√) Municipal	•			(1)	Мајог	•				
() Industrial				() N	linor					
() Federal				() 8	Small	•				
() VPA/NDC .	() VPA/NDC () High Priority () Low Priority									
TYPE OF INSPECTION:					SECTION OF THE SECTIO					
Routine √	Re	einspectior T	n		<u> </u>	e/assistance/cor	mplaint DEQ/TRO			
Date of previous inspection: Population Served:	~150,0	200	Connection		Agency:	~	46,000			
Last Month Average Influent: January 2010	BOD 5 (mg/l)	137	T.SS (mg/l)	92	Flow (MGD)	37.91	TP (mg/l)	3.6		
	Other:	pH 6.5-€	5.9 s.u. TK	N = 236 mg	g/L	•				
Last Month Average Effluent: January 2010	BOD 5 (mg/l)	10	TSS (mg/l)	7.7	Flow (MGD)	37.91	TP (mg/l)	0.36		
	Other:	pH 6.1-7	7.0 s.u.							
Last Quarter Average Effluent	BOD 5 (mg/l)		TSS (mg/l)		Flow (MGD)		NH ₃ (mg/l)			
	Other:						,			
Data verified in preface:		Upo	dated?		NO	CHANGES?		. 1		
Has there been any new constr	uction?		· <u></u> · -		YES	5	NO	1		
If yes, were the plans and spec	ifications	approve	ed?		YES	5	NO	V		
DEQ approval date:		•						./		
COPIES TO: (√) DEQ/TRO; (√) DEQ/	OWPP; ((√) OWNER	R; () OPER	RATOR; () EPA	-Region III; () Other:			

FACILITY: HRSD-VIP WWTP

VA0081281

	PLANTOP	ERAT	ON A	ND MAI	NTE	NANCE			Lenishi Ba			
1.	Class/number of licensed operators:	1	13	II]	п	IV	-1	1 Trainee		
2.	Hours per day plant manned?		_	24 hours/day, 7					lays/week			
3.	Describe adequacy of staffing			GOO	D	1	√ AVERAGE			PO	OR	
4.	Does the plant have an established program for training personnel								YES	1	NO	
5.	Describe the adequacy of training GOOD √ AVERA						RAGE		РО	OR		
6.	Are preventative maintenance tasks scheduled								YES	1	NO	
7.	Describe the adequacy of maintenance GOOD √ AVERAGE						RAGE		РО	OR		
, and the second	Does the plant experience any organic/hydra	ulic ov	erload	ing?					YES		NO	1
8.	If yes, identify cause/impact on plant na											
9.	Any bypassing since last inspection?								YES	1	NO	
10.	Is the standby electrical generator operational? YES √						٧	NO		NA		
	How often is the standby generator exercises	1?					Mon	thly and	d under load			
11.	Power transfer switch?	Mo	nthly		AL/	ARM SY	/STEM?	?	Weekly			
12.	When was the cross connection last tested o	n the p	ootable	supply	?					_		
13.	Is the STP alarm system operational?						YES	. 1	NO		NA	
14.	Is sludge disposed in accordance with an ap	oroved	SMP				YES	4	NO	,	NA	
	Is septage received by the facility?			.:				,	YES	1	NO	
	Is septage loading controlled? YES √						4	NO		NA		
15.	Are records maintained? YES					YES	4	NO		NA		
				000			A) "	DAGE			NOD	
	OVERALL APPEARANCE OF FACIL	LITY		GOO	עי	1	AVE	RAGE		PC	OR	L l

0014445450		•	·
COMMENTS:			

VA0081281

FACILITY: HRSD-VIP WWTP

				PLANT	RECORDS							
	WHIC	CH OF	THE FOLLO	WING F	RECORDS DOES	S THE	PLAN	MAIN1	TAIN?			
	Operational logs for each p	rocess	unit				YES	. 1	NO		NA	
	Instrument maintenance a	nd calib	ration		,		YES	√ .	NO	-	NA	
	Mechanical equipment ma	intenan	ce				YES	4	МО		NA	
1.	Industrial waste contribution	n (mun	icipal faciliti	ies)			YES	4	NO		NA	
		١	WHAT DOE	S THE (DPERATIONAL L	.og c	ONTAI	N				
	Visual Observations	1	/ F	low Mea	asurement	4	Laboratory Results					1
2.	Process Adjustments		<i>I</i> 0	ontrol C	alculations				Other?			
COMN	MENTS:	•	•						-			
	WHAT DO THE MECHANICAL EQUIPMENT RECORDS CONTAIN? NA										-	
	MFG. Instructions	,	/ A	s Built P	lans/specs	√	Spare Parts Inventory					1
3.	Lube Schedules		1	Other? Equipment/parts Supplie							rs	1
COMMENTS:												
	WHAT DO INDUS	TRIAL I	NASTE CO	NTRIBU	ITION RECORDS	CON	ITAIN?	(MUNIC	CIPAL)		NA	
	Wa	ste Ch	aracteristics	5		1	Impact on Plant					1
4	Locatio	n and [Discharge T	ypes		√	Other?					
COMN	MENTS:											
	WHICH OF THE FOLLS	OWING	RECORDS	ARE A	T THE PLANT &	AVAÏI	LABLE	TO PER	RSONNE	L?	NA	
	Equipment Maintena	nce Re	cords	√ ,	In	dustri	al Cont	ributor R	Records	,		√
5.	Operational Log	1	Samp	ling/testi	ng Records		l,	nstrume	ntation F	Record	s	√
6.	Records not normally avail	able to	personnel a	at their lo	ocation:				ntral Lal tment p			
7.	Were the records reviewed	d during	the inspec	tion					YES	1	NO	
8.	Are records adequate and	the O8	M manual o	current?					YES	. 1	NO	
9.	Are the records maintained	d for the	e required 3	-year tin	ne period				YES	1	· NO	
СОМ	MENTS:								•			

FACILITY: HRSD-VIP WWTP VA0081281

		SA	MPLING									
1.	Are sampling locations capable of prov	/iding represen	tative san	ples?	•			YES	√	N	2	
2.	Do sample types correspond to VPDE	S permit requir	ements?					YES	1	N	$\neg \top$	
3.	Do sampling frequencies correspond to	o VPDES perm	nit requirer	ments?	•			YES	√	N	o	-
4.	Does plant maintain required records of	of sampling?						YES	1	N	5	
5.	Are composite samples collected in pr	oportion to flow	v?			YES	1	NO		N/	4	ı
6.	Are composite samples refrigerated during collection? YES √							NO		N/	A	
7.	Does the plant run operational control	tests?			,	YES	1	NO		N,	A	
COMMENTS. Composite samples are collected in separate aliquots, stored in the laboratory refrigerator and combined, proportionally to flow, by the lab technicians.												
4 9			ESTING				2					
	Who performs the testing?	Who performs the testing? Plant √ Central Lab √						Comme	ercial l	_ab	ļ	
1.	Name:											
	IF THE PLANT PERFORMS ANY TESTING, PLEASE COMPLETE QUESTIONS 2-4											
2.	Which total residual chlorine method is	s used?				Ha	ch Poc	ket Co	lorime	eter		<u> </u>
3.	Does plant appear to have sufficient e	quipment to pe	erform requ	uired tests?	?				YES	√.	NO	
4.	Does testing equipment appear to be	clean and/or op	erable?						YES.	. 1	NO	
сомі	MENTS:			,								
	FOR INDUSTRIAL FA	ACILITIES WIT	TH TECHN	OLOGY E	BASE	D LIM	ITS ON	ILY.				
1.	Is the production process as described changes in comments section.	d in permit app	lication? I	f no, descr	ibe		YES		NO		NA	1
2.	Are products/production rates as described in the permit application? If no list differences in comments section.						YES		.NO		NA	1
3.	Has the Agency been notified of the cl Date agency notified:	Has the Agency been notified of the changes and their impact on plant effluent? Date agency notified:									NA	1
СОМІ	MENTS:						_	•				

FACILITY: HRSD-VIP WWTP

VA0081281

PROBLEMS IDEN	TIFIED ATLAST INSPECTION:	CORRECTED	NOT/ CORRECTED
None noted.			

SUMMARY

INSPECTION COMMENTS:

Arrived at the facility at approximately 1015 and initially met with Kelly Lamp, Plant Superintendent. Discussed the inspection routine and some of the items that were to be covered and started with the site review. Followed the wastewater pathways for the plant and then reviewed the solids handling, the incinerator, wastewater from the Norfolk water treatment plant and the nitrification enhancement facility. The site visit ended with the laboratory review with Plant Operator, Earl Ott. By the end of the site visit, Plant Manager Sami Ghosn was in attendance.

Overall the facility appeared to be clean and well maintained. Several of the treatment units appeared to be in better condition than previously observed. This included the aeration chambers with significantly less foam observed than previous visits and the secondary clarifiers appeared to be much clearer without noticeable solids bulking up in the units. There were no problems noted during the site visit.

During the review of the facility files a couple events were noted and then reviewed in depth with facility personnel. Both of the events occurred during heavy rainfall, one on August 12, 2009 and the other during a sustained, stalled Nor'easter over November 12-14, 2009. Each of these events is discussed below.

The August 12, 2009 event was noted due to the reported bypass of 1.5 MG of raw wastewater. Chlorine addition was reported with the wastewater discharged from junction box #3 into the canal leading to the Elizabeth River at the NW corner of the facility.

A report was provided for the bypass stating the cause was due to the drastically increased flow rate due to extremely heavy rain in the area. The rainfall was reported as being measured at 4.5". Seven temporary pumps were reported to be installed due to the ongoing rehabilitation of the wet well with the influent pumps taken off line. The report further provides that the influent junction box increased from 55" to 146" in minutes with a manhole on Bluestone Ave. overflowing as the flow backed up in the plant.

Corrective actions "to minimize the offsite overflow" included the use of bypass pumps that were on hand to pump the raw effluent into the canal. A chlorination system was installed to chlorinate the wastewater prior to discharge. The report stated that all five temporary bypass pumps were placed in operation. The start of this event was at 1845 and ended the same night at 2310.

Flows for this period are found below.

Au	igust 12							<u> </u>	
Time	15:00	16:00	17:00	18:00	、19:00	20:00	21:00	22:00	23:00
Flow (MGD)	33.36	31.44	32.64	46.56	67.68	58.32	50.4	62.16	62.16
Aι	igust 13							_	
Time	0:00	1:00	2:00	3:00	4:00	5:00	6:00	7:00	8:00
Flow (MGD)	61.68	59.76	57.6	55.68	53.76	48.72	45.84	53.28	50.16
									T.

Several questions were asked during the site visit that concerned the temporary pumps, their flow rating, hourly flows for the plant, weather information, the piping used, location of the discharge for the temporary pipes, the location of junction box #3 and the pumps used for the bypass. Several of the questions were answered during the site visit. A list of the questions was provided for those that remained unanswered. Answers were then provided by Ms. Sharon Nicklas via email.

FACILITY: HRSD-VIP WWTP

INSPECTION COMMENTS (continued): 🚮 📒

The additional information obtained during the site visit and via email included that the pumps were tested as sets of two with the pump rating determined to be 29.5 MGD for the pair. A final, combined total was reported to be of close to 89 MGD. The exact number of pumps used was not provided though from the pump rating and total estimated flows, there appears to be a total of six pumps on hand for the influent pumping. The original report provided that seven pumps had been in place. Two 24 " pipes were set up for delivering the wastewater from the influent junction boxes, bypassing the screens and delivering the wastewater to the grit chambers.

The rainfall from area weather stations was reviewed and found to be varied, ranging from a low of 1.41" at Norfolk Naval Air Station to 4.23" in the Craddock section of Portsmouth. When asked about where the 4.5" was measured it was provided this was anecdotal information likely provided by facility personnel. Rainfall at the facility was reported as 2.5"

The number of bypass pumps used at junction box #3 was originally reported as five though emailed information provided that only those needed to drop the levels in the manhole were operated. The actual number of pumps was not reported in the email. The flow rate for the pumps used was reported to be 1500 gpm. When asked about pumping the wastewater from the junction box to the plant, it was reported that hoses of sufficient length were not available at the time.

Additional questions have come up concerning this event concerning the use of the temporary pumps during the wet well rehabilitation and the estimated volume of the bypass. In response to this report please provide information concerning the design of the temporary pumping system to include:

- Bypass pump design criteria (gallons per minute [gpm] versus Total Dynamic Head [TDH]) for individual pump operation and combined pump operation.
- Basis for the design TDH and the designed gpm.
- Install pump capacity (gpm versus TDH) for individual pump operations and combined pump operations.
- Pump curve(s)
- How the volume of the actual bypass was determined.


The second event reviewed occurred in November during a sustained Nor'easter. Rainfall at the plant was recorded for November 11th, 12th, and 13th at 2.00", 6.90" and 2.00" respectively. Facility personnel reported that there were no overflows of manholes in the local area and a bypass of the plant did not occur. Average flows for these days are reported as 44.19, 84.47, 91.60, 84.17, 72.33, and 64.13 MGD from November 11-16, 2009.


The file review noted that at 80 MGD there would be the passive overflow of the weir that discharged to Outfall 002. When asked about this, facility personnel provided that a discharge to this Outfall did not occur. This calls to question the flow amount that a discharge to Outfall 002 would actually occur.

Reviewing the hourly flows reported from the 12th to the 16th did show a wide variation in flows from hour to hour. Data provided for the flows is shown on two charts on the following page. The first charts the hourly flows for November 8-19, 2009. A diurnal pattern is shown for the 8th to the 11th with the subsequent increase as rainfall is received from the storm event. At approximately 1100 on the 11/12/09 the flow starts to show the wide variation that continues until the 16th. The hourly flow chart shows a pattern of the flow bouncing back and forth from high to low for these days. The amount of the fluctuations between hours is then shown on the second chart. This chart shows the hourly difference in flow with significant differences reported from the 12th to the 16th.

Hourly flow rates on 11/13/09 from 0300, 0400, 0500 and 0600 are shown as of 93.36, 106.8, 73.68, and 95.52 MGD. The hourly differences for these flows are shown as an increase of 13.44 MGD, a drop of 33.12 MGD, and an increase of 21.84 MGD. The greatest variation is shown on Monday, 11/16/09, from Midnight to 0200. Flow increased at Midnight by 18.48 MGD, dropped by 37.44 MGD at 0100 and then increased by 20.64 at 0200.

The hourly flow variation shown for this period in November does not appear to be realistic without causing significant problems within the treatment process for the facility. As part of the response to this inspection report, please provide information concerning the last date of calibration of the effluent flow meter, the calibration range, the calibration results and the maximum flows that can be accurately measured. Please provide any additional information concerning the validity of the flow data for the November 12-16 event. Finally, review what the flow would be expected for Outfall 002 to have a discharge and provide the reasoning for the determination of this flow.





VA0081281

FACILITY: HRSD-VIP WWTP

1.3	COMPLIANCE RECOMMENDATIONS FOR ACTION
	For all reports concerning bypasses, please provide factual information. This should include the number of pumps used, flow rates, design flows (temporary piping), rainfall amounts, and the determination of any bypass volumes.
	Provide the requested information concerning the flow data from November, the validity of the flow data and the requested information concerning discharges to Outfall 002.
	Provide the requested information concerning the design and set up for the temporary pumping system during the wet well rehabilitation project. Provide how the bypass was estimated.
,	

	E UN	IT PROCESS:	Screenii	ngs/Co	mminution					
								YES	NO	NA
1.	Number of manual units			1						
2.	Number of mechanical unit	s		3						
3.	Number manual units in op	eration		0						
4.	Number of mechanical unit	s in operation		2						
	Bypass channel provided							۱ √		
5.	Bypass channel in use	ass channel in use							1	
6.	Area adequately ventilated						4			
7.	Alarm system for equipmen	nt failure and/or overloads						1	·	
8.	Proper flow distribution bet	ween units				·				N
9.	How often are units checke		Cleaned automatically, routinely checked ~ every other hour.							
10.	Cycle of operation		~ every 5 minutes					F V		
11.	Volume of screenings removed 42 ft³/day Average, January 2010									
GENE	ERAL CONDITION:	GOOD	1		FAIR		F	OOR		
			<u> </u>			ı			<u></u>	

COMMENTS:		, "

		· UNIT	PROCESS		Frit Rem	oval		,		
	-					•		YES	NO	NA
1.	Numbe	er of units			3					
2.	Numbe	er units in operation			3					
	Opera	tion of grit collection e	quipment:							
3.	۸.	Manual	Time Cle	ock	4	Continuou			9 - 5 T - 1X 9 - 5 Z - 5	
4.	Area a	dequately ventilated				· · · · · ·	•	4		
5.	Proper	r flow distribution betw	een units							1
6	Daily v	volume of grit removed	3			60 ft ³ January 2	2010		74	
7.	All equ	uipment operable					•	√ _	,	
GENI	ERAL C	CONDITION:	GOOD	1		FAIR	Р	OOR		

COMMENTS:

Sent to grit classifier, 3 units/pumps available with all in operation. Increased grit amounts were noted with subsequent wear and tear on the pumps noted. Refurbishing ongoing with one pump already replaced. Grit removed and volume obtained on seven days within the month.

		UNIT	PROCESS.	Se	edimentation	n				
	PRIMARY	1	SECONDARY		TERTIARY		,	YES	NO	NA
1.	Number of units	•				2			4 . 	
2.	Number units in ope	ration				and about				
3.	Proper flow distribut	ion between	units					4		
4.	Sludge collection sy	stem working	g properly?	<u>-</u>				4		
5.	Signs of short circuit	ting and/or o	verloads				· ·		1	
6.	Effluent weirs level							4		
7.	Effluent weirs clean							1		
8	Scum collection syst	tem working	properly				•	4		
9	Influent/effluent baffl	le system wo	orking properly		,			4		
10.	Chemical Used					Chemical A	Addition			
11.	Effluent characterist	ics								
GENER	RAL CONDITION:		GOOD	4	FAI	R		POOR		

COMMENTS:

Effluent flow is observable for these units with the scum collection observed. Unit #3 was drained at the time of the site visit. No problems noted for the flows observed. Effluent from the Primary Clarifiers is discharged into the Biological Nutrient Removal Tanks. Four treatment trains are available with 4 anaerobic and 2 anoxic stages. Three trains were in use on the day of the site visit. Effluent from the BNR tanks is discharged to the Activated Sludge units.

WNIT PROCESS Biological Nutrient Removal

	`.	<u> </u>									
11			_					,	YES	NO	NA
1.	Number	of aeration units	3			4		y dist			7.5/10
2.		units in operatio	n			3					
	Mode of	operation:			Anaerobic s						7.1
3.	5			<u></u>	4 Anoxic sta	iges					數。如
4.		ow distribution b							٧		
5.	Foam co	ntrol operationa	ı l								1
6.	Scum co	ntrol present									. √
7.	Dead spo	ots									1
8.	Excessiv	e foam									√
9.	Poor aer	ation			-						√
10.	Excessiv	e scum				4					
11.	Aeration	equipment mal	function				•				-√
12.	Other pro	oblem(s):				· · -	•				4
13.	Effluent of	control devices	working proper	ly (oxidatioi	N DITCHES)						√,
14.		MIXED LIG	UOR CHARA	CTERISTICS		ABLE: <mark>Janu</mark> a			14.71		抗學
	рН		MLSS	1189	DO		SVI				i i Agili
. `	(s.u.)		(mg/l)	Anaerobi	, , ,		1				ųžŽ.
			<u> </u>	c Effluent	;	<u> </u>	051		A FARM		
	Odor	<u> </u>	Settleabi	lity (mi/i)			SDI				
15.			RETURI	VWASTE S	LUDGE RAT	ES:		•••			L
	Return	29.53 MGD	Return	35.84 MG					1.7.7	a tan	
,	Rate	Anaerobic	Rate	Anoxid							
GENE	RAL CON	IDITION:	GOOD	'	√]	FAIR		P(DOR		
			,						-		

Units are covered.

COMMENTS:

UNIT PROCESS	Activated Sludge

•				· .						YES	NO	NA
1.	Number	of aeratio	on units				4					
. 2.	Number	units in c	peratio	n	,		4					
3.	Mode of	operatio	n:			Plug flow						
4.	Proper flo	ow distrib	oution b	etween units						7		
5.	Foam co	ntrol ope	rationa	l:						7		
6.	Scum co	ntrol pre	sent					-		-	1	
7.	Dead spo	ots				•					4	
8.	Excessiv	e foam									4	
9.	Poor aera	or aeration										
10.	Excessiv	xcessive scum										
11.	Aeration	Aeration equipment malfunction										
12.	Other pro	oblem(s)	Signi	ficantly less fo	oam noted d	luring this \	isit as compa	red to t	ne last.		1	
13.	Effluent o	control de	evices v	working properl	y (OXIDATION	DITCHES)				-		1
14.		MIX	ŒD LIÇ	UOR CHARAC	CTERISTICS	AS AVAILA	BLE: January	2010				
	pH (s.u.)	6.2-	7.0	MLSS (mg/l)	2902	DO (mg/l)		SVI				
	Odor	กดเ	ne	Settleabil	ity (ml/l)			SDI				
	Color	Brow	n foan	n, crisp bubble	es							
15.				RETURN	INVASTE SL	UDGE RAT	ES:	,				
	Return Rate	11.17	MGD	Waste Rate			Vaste quency					
16.				AERAT	ION SYSTE	M CONTRO	L:					
	Time (Clock		Manual Fee	d	Contin	uous Feed		1			
	Other:											

GENERAL CON	IDITION:	GOOD		FAIR	1	POOR	
COMMENTS:	Less foam n	oted from previous vis	its.	,			

	UNIT PROCESS Sedimentation											
·	PRIMARY		SECONDARY	V	/ т	ERTIARY			·	YES	NO	NA
1.	Number of units				- 1	5			# 1 2 1 A			
2.	Number units in ope	ration				5						
3.	Proper flow distribut	ion be	tween units							1		
4.	Sludge collection sy	stem v	working properly?							1		
5.	Signs of short circuit	ting ar	nd/or overloads [,]								4	
6.	Effluent weirs level									1		
7.	Effluent weirs clean									4		
8.	Scum collection sys	tem w	orking properly							1		
9.	Influent/effluent baff	le syst	tem working prope	rly								
	Chemical Used		Z-75					on: 150 l		1		
_10.			Ammonium	Hy				on: 48 lb				<u> </u>
11.	Effluent characterist	ics			Clear	and colories	s no noti	ceable s	olids.	Culture of		4
GENE	RAL CONDITION:	,	GOOD		۷.	FAIF	₹ .		Р	OOR		

COMMENTS:

Polymer application performed only on five days.

Ammonium hydroxide added to the effluent.

Waste activated sludge average rate for January 2010 is 0.208 MGD.

	. UN	UNIT PROCESS Chlorination											
	· .							YES	NO	NA			
1.	Number of chlorine pur	nps?		3) () () () () () () () () () (
2.	Number pumps in opera	ation?		1				1000000 600000	· · · · · · · · · · · · · · · · · · ·	ant. St			
3.	Number of evaporators	?	·	na									
4 *	Number of evaporators	in operation		na									
5.	Number chlorine contact	t tanks		2									
6.	Number chlorine contact				2								
7.	Proper flow distribution	oper flow distribution between units?											
	HOW IS	CHLORINE INTRO	DUCED INT	TO THE WA	ASTE ST	REAM?							
8.	Perforated Diffuser	Injecto	or w/single e	ntry point	4	Tablet Fee	der		• 0.1				
9	Chlorine residual in con	tact basin effluent ((mg/l)			@1305							
10.	Applied chlorine dosage	(lbs/day)		,	110	2 lbs/day, 1/2	2010						
11.	Contact basin adequate	ely baffled?						1					
12.	Adequate ventilation in	chlorine cylinder sto	rage area?							1			
14.	Adequate ventilation in	dequate ventilation in chlorine equipment room?											
15.	Proper safety precautio	ns used?						1					
GENE	RAL CONDITION:	GOOD	. 1	F	AIR		P	OOR					

	MONET FROM	Dennialier 200					r		
							YES	NO	NA
	Dechlorination chemical used?	 					1 F 5 影響。		
. 1.		sulfite √	T	Other:	senders' trafficioled	the state of the s	֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓		
2.	Number of bisulfite pumps?			4	7.452		7.5	Ny ara-	
3.	Number pumps in operation?		<u> </u>	1			\$ 1 \$ \$ \$ \$ \$		
4.	Number of evaporators?	-		na					
5.	Number of evaporators in operation	on	_	na					
6.	Number contact tanks?			1					
7.	Number contact tanks in operatio	n?		1					
8.	Proper flow distribution between a	units?				··			√
	HOW IS CHEMIC	AL INTRODUC	ED INTO	THE WASTE	STREAM?				100 000 10000
9.	Perforated Diffuser √	Injector w/				t Feeder	7.00		. 44
10.	Chlorine residual in basin effluent			<0.	1 mg/L. 2/1	1/10 @ 1314			
11.	Applied dechlorination dosage (lb				216 lbs/da				
12.	Control system operational?		.,	h_ _	 -	-	1		
13.	Control system adjusted?	Automatic	- I J I	Manual	Other:	<u> </u>	12. 《		
	Residual analyzer?		<u> </u>				(*) 40 min (*)		
14.	Contact basin adequately baffled					<u> </u>	- V		
15.							1 1		├
16.	Adequate ventilation in cylinder s						ļ	Ļ	√
17.	Adequate ventilation in equipmen	it room?				<u> </u>	√		
18.	Proper safety precautions used?						_ √		
GENE	ERAL CONDITION:	GOOD	√.	FAIR		F	POOR		
				·					
COM	MENTS:								
	· ·				,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,				-
	·	•							
	JUNIT PROC	ESS#	Flow	<u>Measuremer</u>	nt				
_	 	RMEDIATE		EFFLUENT	_		YES	NO	NA
1_	Type of measuring device			I Flume with ul		sor			
2.	Present reading? Bypass channel		62	2.91 MGD, 2/11/	10 @1109			i i i i i i i i i i i i i i i i i i i	├
		* "					1	<u> </u>	
4.	Bypass channel metered?	U						1	
_	Return flow discharged upstream of	ine meter/					5 * 4 ; # 1000 miss	1 V	—
5. C	Identify: Device operating properly?	<u> </u>				· · · · · · · · · · · · · · · · · · ·			
6. 7.	Date of last calibration?	·	Not	obtained durit	na eita vieit		z. (, , , , , , , , , , , , , , , , , , ,		
<u> </u>	Date Of last calibration?	EVIDENCE		FOLLOWING F			10.000000	grafiat -g	
	Obstruction?		<u>.</u>	<u> </u>					٦ √
	Grease?						 		1
8.					<u> </u>	_		<u> </u>	
GENE	RAL CONDITION:	GOOD	1	FAIR	<u> </u>	· \	POOR	l"	
OL/VL	TOTAL DOTTON		4	17.013		<u> </u>			
COM	MENTS: Large parshall flume ju	st after dechlori	nation.						
	1 1								

UNIT PROCESS:	Influent Pump Station

							_				YES	NO	NA
1.	Number of pumps			-		-	4						
2.	Number pumps in op	erat	ion				4						
			TYPE	OF W	ASTEP	JMPED): (***)						
	Primary		Waste A	ctivated			Oth	er: Plant i	influent	1		, , E	
3,	Secondary	Secondary Return					Co	ombination	1				
	TYPE OF PUMP:	YPE OF PUMP: Plunger			Diaphra	agm					が ま なかり等 11. 47. 12.53		
4.	Centrifugal:	4	Screwlift		Prog. C	g. Cavity		0	Other:				
5	MODE OF OPERATION:	Manual		Autom	atic	. 1	0	ther;					
6.	Volume pumped:	37.9	91 MGD	avera	ge Janua	ary 2010 (effluent	flow)		- Q.			
7.	Alarm system for equ	erloads	operatio	nal?					1				
GENE	RAL CONDITION:	GOOD		V	√ FAIR P				POOR				

COMMENTS: Influent flow comes in through two junctions boxes, to the bar screens and then to the influent pump wet well. Pumps are rated at 20 MGD each for an approximate flow rate of 80 MGD.

UNIT PROCESS. Primary Sludge to Solids Handling

											YES	NO	NA
1.	Number of pumps						12	2 (2) 14 (2) 14 (2)					7/2 7/2
2.	Number pumps in op	erati	on			Not	determin	ned					
·			TYPI	OF W	STEP	UMPEC). D:						
	Primary	1	Waste A	ctivated				Other:	,			- 11	
3.	Secondary	Return Activated					Co	ombinatio	n				
	TYPE OF PUMP:		Plunger	unger Diaphra				1					
4	Centrifugal:		Screwlift		Prog. 0	Cavity		C	Other:				
5	MODE OF OPERATION:		Manual		Auton	natic	1	C	Other:				
6.	Effluent volume pum	iffluent volume pumped: 0.31						o centrif	uge, 1/2	010			
7.	Alarm system for equ	Alarm system for equipment failures/overloads op						-			1		
GENE	RAL CONDITION:	ONDITION: GOOD					FAIR			P	OOR		

COMMENTS:

UNIT PROCESS:

Waste Activated Sludge Pumping Return Activated Sludge Pumping

							-	•		YES	NO	NA
1.	Number of pumps			_			4				1 1	7
2.	Number pumps in or						h RAS/V					
			TYPE	OFISE	UDGE F	UMPE	D: '.		i Šatašti i			
	Primary	Primary / Waste A			,	√ Other:					*	
3.	<u> </u>			Activated	d -	1	Co	ombination				Ş.
	TYPE OF PUMP:		Plunger		Diaphr	agm						
	Centrifugal:				•							
4.	_	1	Screwlift		Prog. C	Cavity		Other:				
	MODE OF											
5.	OPERATION:		Manual		Auton		√	Other:			ីស្រែក	
	Sludge volume pump	oed:					208 MG					
6.			11.17 MGD RAS									K
7.	Alarm system for equ	uipme	ent failures/ov	erloads	operation	nal?				1		
GENE	GENERAL CONDITION: GOOD				√ √		FAIR		P	OOR		

COMMENTS:	
-----------	--

UNIT PROCESS:	Flow Equalization:
	Norfolk Water Solids Holding Tank

	•																
															YES	NO	NA
1.	Type syst	em:	In-	ine		Side	-line	√	S	Spill I	Pond						
2.	Number o	ells:		1							1462	2 (2.0					
3.	What unit	What unit process does this unit precede? Norfolk Water Plant (solids)															
4.	Is volume	Is volume adequate:															
	Mixing?	N	lone		Diffu	used Air	,			Fixe	ed Mec	hani	cal	1			
5.	Flo	ating Med	chanical			Other									100		
6.	Condition	of mixing	equipn	nent	10	GOOD	1	ΑV	ERAG	ΞE		P	OOR	,			
		HOW DRAWN OFF?												7 4			
	Pumped from? Surface Sub-surface √ Adjustable																
7.	Weir?		Surfac	e		Sub	-surfac	e	18 10 CC 60 60								
8.	Is contain	ment stru	icture in	good c	ondit	ion?									√ √		
9.	Are the fa	cilities to	flush so	olids/gre	ase f	from bas	sin wall	s ade	quate	?							√
10.	Are there	facilities	for with	drawing	floati	ing mate	erial an	d foai	m?						1	ļ	
			-	Н	OW /	ARE SC	LIDS F	REMO	OVED:	?					F. ITE		
11.	Drain (down	-√	Dr	ag lir	ne				, (Öther:						
12.	Is solids r	emoval a	dequate	?											1		
13.	Is the em	ergency o	verflow	in good	con	dition?									1		
14.	Are the de	epth gaug	jes in g	ood con	dition	1?									<u> </u>		1
GENE	ERAL CONDITION: GOOD √ FAIR											F	OOR				
COMI	COMMENTS: Discharges from 38 th Street Water Treatment Plant received and stored in this tank use to keep solids suspended. Water and solids are combined with solids from the and the NEF.																

UNIT PROCESS:

Activated Sludge Nitrification Enhancement Facility

									YES	NO	NA	
1	Number	of aeration units	·			1					10 30 °	
2.		units in operatio	n			1			4 🛎			
3.		operation:		Con	tinuous ae	ration	1				I. Fr	
4.	Proper fl	ow distribution b	etween units								lacksquare	
5.	Foam co	ntrol operationa	<u> </u>								1	
6.	Scum co	ntrol present	-								1	
7.	Dead sp	ots								V		
8.	Excessiv	e foam							·	 ✓		
9.	Poor aer	ation								_ √		
10.	Excessiv	e scum			· · · · · · · · · · · · · · · · · · ·			` '		1		
11.	Aeration	Aeration equipment malfunction										
12.	Other pro	Other problem(s):										
13.	Effluent of	control devices v	working proper	v (OXIDATION	DITCHES)			 	1			
14.			QUOR CHARA	<u> </u>		ABLE: March	2006 .					
	рН	5.4-6.4	MLSS	3418	DO	0.5-1.5	SVI	61		4 . *		
	(s.u.)		(mg/l)		(mg/l)		<u> </u>			- 1		
	Odor	None	Settleabil	ity (ml/l)		210	SDI	,				
	Color	Grey-			<u></u>		<u></u>	<u> </u>				
15.		ı	RETURI	IWASTE SL	JDGE RAT	ES:	_			Marija (a. s.) G		
,	Return	0.707 MGD		0231 MGD to	l ,	Vaste	JA/iei	n solids		i ya		
	Rate	(recycled)	Waste Rate		•	quency		ndling				
16.	AERATION SYSTEM CONTROL:											
	Time (Clock	Manual Fee		T	uous Feed	Τ	1				
	Other:				L							
GENE	RAL CON	IDITION:	GOOD	√		FAIR		F	OOR			
СОМ	MENTS:	NEF plant de the nitrifying			found in th	e incinerator	scrubbe	r water th	at then i	nhibite)d	

			10 2	NIT PROCESS	Ni	itrifica	Sediment ition Enhan		acility				
	PRIMA	RY	•	SECONDARY	4		TERTIARY				YES	NO	NA
1.	Number of	units		·	•		1	•					T
2.	Number uni	ts in opera	ation				1			f Belt ije			
3.	Proper flow	Proper flow distribution between units											4
4.	Sludge colle	Sludge collection system working properly?											
5.	Signs of she	igns of short circuiting and/or overloads											
6.	Effluent wei	rs level									4		
7.	Effluent wei	irs clean						,			4		
 8.	Scum collec	ction syste	m working	properly									1
9.	Influent/efflu	uent baffle	system wo	rking properly							4		
10.	Chemical U	sed						Chemica	al Addition				\ \
11.	Effluent cha	racteristic	.s				Clea	r, colories	s			100	
GEN	GENERAL CONDITION: GOOD		GOOD		1	√ FAIR I				OOR			
COM	MENTS:		nt sent to ntrifuge.	the head of the	plant	. Soli	ds are eithe	r recycle	d to the aer	ation (R	AS) or a	re ser	it to

UNIT PROCESS:	Centrifugation

									YES	NO	NA
1.	Number of units		·			5				4.44	77 / + .
2.	Number units in	operation	on .	•	1	2					
			PURP	OSE OF	CENTRI	-UGE					
3.	Thickening		Dewate	ring	1	Other:					
			OPER/	ATION OI	EQUIP	MENT	=				AND THE TOTAL TOTA
4.	Manual	7	Automa	atic		Other:		-		3 34	
5.	Centrifuge run tir	me	·	23.5	nrs/day	average, 1/2010		a al s	Yaran		iar art
6.	Volume of influe	nt sludg	e flow: (gal/min))							
7.	Amount of cake	produce	d: (lbs/day)							42812	
8.			;	SLUDGE	SOLIDS			,			BRE STATE
	Influent (%)		1.59	Efflu	ent (%)	24	.8	A. Esta	Ž.		
9.	Conditioning che	emical fe	ed:		C	-341				3	
10.	Conditioning che	emical d	ose:		284	bs/ton					
11.	Centrate return I	ocation:		hea	ad of plant (0.315 MGD)						
12.	Signs of centrate	e return	problems?			-		·		4	
GENE	RAL CONDITION	J;	GOOD		√	FAIR		PC	OOR		
СОМІ	MENTS:	•						•			

UNITIPROCESS:		
•••	• • • • • • • • • • • • • • • • • • • •	

										YES	NO	NA	
1.	Method:	M	ultiple Hea	rth Furnace		√.	Fluidized Bed I	ncinerator					
2.	Number of units				2								
3.	Number units in	operatio	n		1 *************************************								
4.				Тур	es of s	ludge	e incinerated:		-				
	Primary	,	/ Wa	aste Activate	ed	√	Other:			THE TANK	プログライン 1975年 マンスの発		
5.	Loading rate (we)		42,	Reg.	01/12							
6.	Range of operat	Range of operating temperature					388-1408 ⁰	F				The state of the s	
7.	Fuel used	(Gas/Oil	A	Amount Gas: 99,000ft ³ /day				010	,	\$ 100 1 - 6 - 100		
8.	Amount of ash g	Amount of ash generated			day, 10	D	isposal of ash	land	fill .			The state of the s	
9.	Average number	r of hour	s of operati	on per day				23.4 hr/da	у				
GEN	ERAL CONDITION			OOD	1		FAIR			POOR			
COM	MENTS:	1			· ·		-	I					

UNIT PROCESS: EFFLUENT/PLANT OUTFALL

			· .		*				YES	NO	NA
1.	Type of outfall			Sho	ore Based		Submerged	1			
			TYPE	IF SHO	RE BASED:				Ž.		
2.	Wingwall [*]		Headwall		Rip Rap		Pipe				√
3.	Flapper valve p	resent?		,							4
4.	Erosion of bank	area?									1
5.	Effluent plume	visible?								1	
	Condition of out	fall and	the supporting str	ucture?	·						131
6.	GOOD	٧	FAIR	•	POOR						
		FINAL	EFFLUENT, EVIL	DENCE (OF FOLLOW!	NG PROB	LEMS?		2		7
	Oil sheen?				·				•		1
	Grease?										1
	Sludge bar?								`		1
	Turbid effluent?										1
	Visible foam?										1
7.	Unusual color?										1
	<u> </u>				:		•		1	·	J
 GENI	ERAL CONDITIO	N.	GOOD		1	FAIR	.]]	 Р	OOR		

GENERAL CON	IDITION:	GOOD	1	FAIR	POOR	
					 •	
COMMENTS:	Shore side f	facilities look good.				



HRSD

P.O. BOX 5911, VIRGINIA BEACH, VIRGINIA 23471-0911 • (757) 460-7004 • FAX: (757) 318-6452

www.hrsd.com

March 29, 2010

Commissioners

R. Tyler Bland, III Chair

Vishnu K. Lakdawala, PhD Vice-Chair

Parris D. Carson

B. Anoc Davis

Douglas E. Miller

Frederick N. Elofson, CPA, PFS

Gerald S. Johnson

Michael E. Glean

Serving the Cities of

Chesapeake

Hampten

Newport News

Norfolk

Pognoson

Portsmouth

Suffolk

Virginia Beach

Williamsburg

Serving the Counties of

Gloucester

Isic of Wight

James City

King & Queen

King William

Mathows

Middlesex

Vori

Steven J.E. Long Dept of Environmental Quality 5636 Southern Blvd Virginia Beach, VA 23462

RE: Virginia Initiative STP VA0081281 Inspection Report

Dear Mr. Long:

Hampton Roads Sanitation District (HRSD) has reviewed your report of the technical and laboratory inspection conducted at the Virginia Initiative STP on February 11, 2010. The information requested in your report has been collected and is attached to this correspondence.

The attachments include the demonstration of capability for the plant operator who conducted the pH and chlorine residual analyses during your visit. HRSD has an extensive, well documented training program which meets the demonstration of capability requirements as defined in the 2008 DEQ Laboratory Stakeholders Workgroup meetings summary. A copy of the DEQ Laboratory Stakeholders Workgroup meetings summary has been included for your reference. The plant operators' proficiency test records are maintained at plant site. The calibration verification for chlorine residual analysis has also included in the attachments. This record is kept at the plant in the daily plant operations report.

After reading the inspection report, HRSD is unsure whether DEQ completely understood the pumping setup that was in operation during the headworks rehabilitation that occurred in August 2009. The report referred to "temporary pumps" which made it unclear as to which set of pumps it was addressing. There were two sets of pumps at the plant. The first set was a group of seven pumps that were installed to pump the influent flow directly to the grit removal process while the headworks area was undergoing a planned rehabilitation project. The HRSD plant personnel referred to these pumps during the inspection as "pumparound" pumps. The second set of pumps was five pumps that were installed at junction box #3. These pumps were to be used in an emergency situation if part of the influent flow had to be diverted to outfall 003. The HRSD plant personnel referred to these pumps as the "bypass" pumps. The DEQ report requested information on the "temporary" pumps but then specifically asked for information on the "bypass" pumps. Since it is unclear which set of pumps piqued DEQ's interest, HRSD has included information for both sets of pumps,

The original HRSD report cited in your report was correct. There were seven pumps on site for pumping the influent instead of the six noted in the inspection report. The pumps were tested in pairs to determine capacity. The pump-around system had been designed for 90 MGD and six pumps provided 89 MGD so HRSD had a seventh pump installed as a safety factor which would boost system capacity above 90 MGD. The capacity for each of pumps 1 through 6 was 14.8 MGD. Pump 7 had a capacity of approximately 7 MGD. The system was field tested and provided more than 90 MGD capacity. The pumps were model DV-400 pumps. The Total Dynamic Head (TDH) for the pumps 1 and 2 were 93 feet. The TDH for pump 3 was 101 feet and pump 5 was 106 feet. The TDH for pumps 4 and 6 was 114 feet. The company which installed the pumps did not provide the specific TDH for pump 7 but it was comparable to the others and it was installed with separate piping. The pump curves for the DV-400 pumps are included in the attachments.

The 5-pump bypass system was designed based on best engineering judgment using the available space. Five pumps, each with a capacity of 2 MGD were set up near the junction box. The entire system was designed for 10 MGD with negligible TDH since the pumps only had to pump the water over the wall of the junction box into outfall 003. The pumps were model DV-150i. The pump curves for these pumps are included in this correspondence.

DEQ requested more information regarding how the estimated volume of the bypass into 003 was determined. As previously reported, all five bypass pumps were initially pumping to pull the level down and to stop the manhole on Bluestone Avenue from overflowing. The peak capacity of each pump is 1800 gpm and the design capacity is 1,500 gpm. HRSD operated all five pumps from 6:45 pm to 9:30 pm. Using the peak flow rate as a conservative measure, this calculates to 5 pumps X 1800 gpm X 165 minutes which results in 1,485,000 gallons. HRSD then dropped the pump rate down to a combined 200 gpm from 9:30 pm to 10:45 pm which calculates to an additional 15,000 gallons. A flow rate of 150 gpm was estimated for fifteen more minutes which calculates to 2250 gallons. The pumping rate was then slowed to 50 gpm until the pumping ceased at 11:10 pm. This brings the total to 1,502,750 gallons (this is a conservative estimate as it was based on 1,800 gpm and not 1,500 gpm).

The DEQ report also requested more information concerning a nor'easter which occurred on November 11-13th. HRSD disputes the observation in the inspection report that there did not appear to be any significant

problems within the treatment process for the facility despite the extraordinarily high flows. The inspector was provided with the complete monthly plant operations report for this event. The inspector's review focused on the hourly flow reading sheet but the entire monthly report reflected the considerable impact of the nor'easter on plant performance. Daily average turbidities spiked from 5 NTU to 30 NTU. Additional barscreens, grit tanks, primary clarifiers and secondary clarifiers had to be placed into service. Chemical feed was initiated at the secondary clarifiers to improve settling. BOD, TSS, and nutrient removal efficiencies dropped significantly during this time period. Contrary to the report's assessment, the storm created significant treatment problems which were addressed admirably by the professionals at this facility.

The inspection report guestioned the validity of the plant flow data. Please find attached the most recent record of calibration for the plant flow meter. The effluent meter is calibrated for a range up to 80 MGD. The flow meter data can be recorded using two different methods. During typical plant operations, the flow data is routed to the plant distributive control system (DCS). However, this system only accepts flow readings up to 80 MGD. Therefore, during the storm the operators were taking readings from the totalizer. The operator records the number of gallons that have flowed into the plant since the last reading. These numbers are multiplied by 24 to produce a daily flow rate. Please be advised that there is some error involved as the readings are not taken exactly 60 minutes apart. The operator has multiple duties that must be accomplished during an hourly round and therefore totalizer readings are not taken at exact intervals. However, this mode of flow recording is the approved method when calculating flows above 80 MGD. Based on experience, it is HRSD's position that the hourly flow figures provide the best possible data for determining the daily average flow. The street flooding which occurred during this storm contributed to the wide fluctuations in the hourly flow rates. Flows spiked during periods of flooding but dropped quickly as the water cleared from the streets.

The short outfall 002 is not necessarily utilized every time the plant flow reaches 80 MGD. The plant discharges via gravity so the flow will follow the path of least resistance. The primary and easiest route for the plant flow is to drop into outfall 001. If there are mitigating factors such as high tide or strong wind, the flow will have a hard time discharging through the diffuser ports. The level in the contact tank will then rise as flow backs up. If it rises high enough, the flow will spill over the weir and out the short outfall. If this occurs, there is a bubbler system which will alert the plant operator that water has been discharged to the short outfall in addition to

March 29, 2010 Page 4 of 4

the operator being able to observe whether flow is going over the weir. There is no exact flow rate that can be determined when the short outfall will be utilized. Each scenario contains its own unique set of circumstances.

HRSD hopes that this information clarifies the plant operation of the Virginia Initiative STP. Please contact me if you have any further questions.

Sincerely,

Sharon Nicklas

Permits Manager

Enclosures



PROFICIENCY TEST FOR THE MEASUREMENT OF TOTAL RESIDUAL CHLORINE (HACH COLORIMETRIC METHOD) PART B: DEMONSTRATION

ivame:		FARL	WHEREN OF	7 be Position:	•	PLANT	aper of
Locatio	n:	VIP		Work Cente	Work Center:		
Issue Date:		7.7-2009		Reexamine	Date:		
·						****	
	Instruct Operat	or	Sampling and Te shift.	all conduct a total res sting SOP. Assume	that you are	at the begi	nning of the day
Instructions for E x a m i n e			is being performe For certification of questions #1-22 a solution. If an ind procedures as ne	er for each question, d. The green highlig f proficiency, the ind and the "analyzed va lividual is deficient or cessary after the test, amiliar with the test, s hedule.	thted responsividual must live" of the earn any quest at is finished	nses reflect to tobtain a sco acceptable re ion, review to the fit is clear	he correct answer. ore of 100 for ange for the known he proper ily evident that the
*		•	(P	nalyze a "blank" of t TRC), to correct of p esidual is detected, t om the TRC value o perator completes th	ossible TRO palculate the of the QA/QC	C, in the high a ma/L TRC.	purity water. If a then subtract this
[Von	No						
Yes	No	<u> </u>	· · · · · · · · · · · · · · · · · · ·	<u> </u>			
M	П	1. Was tr	Was the expiration date verified on the Spec Check standards kit?				
M		2. Were the Spec Check standards checked to assure they were clean and the glass was not scratched?					
M		3. Could the operator explain the appropriate action to take if a standard was not within the acceptable range?					
M		4. Was the expiration date verified on the DPD Powder Pillow?					
闽		5. Were the sample cells checked to verify they were clean and in good condition?					
义		6. Was the meter set on the Low Range?					
M		7. Was the outside of the sample cell containing the untreated sample wiped dry with a Kimwipe prior to zeroing the meter?					
M		8. Was the sample cell placed in the cell holder with the diamond facing forward?					
M		9. Was the meter zeroed using the untreated sample as a blank?					
M		10. Was the 10 mL sample volume measured correctly?					

JPD Powder Pillow mixed with the sample by capping and shaking the sample
outside of the sample cell wiped dry with a Kimwipe before placing it in the
of three minutes, was a reading taken on the sample?
nstrument cap placed correctly on the meter when blank and sample were
ollowing information recorded on the proficiency test worksheet?
tal Residual Chlorine (2 decimal places)
erators initials
ne analysis began (when sample was added to cell)
otal Residual Chlorine greater than 2.20 mg/L?
operator explain the procedure if the residual was greater than 2.20 mg/L? ion of the sample and blank)
lassware washed with soap and water?
lassware rinsed with high purity water after washing?
lassware clean after it was rinsed?
erator understand that the high range on the instrument, 0-4.5 mg/l must?
hlorine value of the known solution within the acceptable range?
of QA/QC Solution
/alue
zed Value 1.72
zed Value

Tested By:f	COK 2/1/0
Date;	7 77

Comments:

TOTAL RESIDUAL CHLORINE PROFICIENCY TEST WORKSHEET

HACH POCKET COLORIMETER TRC VERIFICATION (CONDUCTED BY OPERATOR)

Hach Spec Check STD Lot#	ABZ46		
Expiration Date	9/30/10		
Time Verified	8:47	•	
Operator's Initials	60		¥
	True Value	Accept. Range	Meter Reading
	mg/L TRC	mg/L TRC	mg/L TRC
Blank	0.00	NA .	0
STD 1	0.2	112-130	. 20
STD 2	0.92	.82-1.02	, 41
STD 3	1.64	1.50-1.78	1.63

SOLUTION ANALYSIS (CONDUCTED BY OPERATOR)

Date of Analysis	7.7.09
Time analysis began (time sample poured in cell)	8:54
Total Residual Chlorine, mg/L	1.72
Operator's Initials	60

HIGH PURITY WATER ANALYSIS (CONDUCTED BY SUPERINTENDENT)

Total Residual Chlorine, mg/L	0.00
Superintendent's Initials	ROK

PROFICIENCY TEST FOR pH ANALYSIS (ELECTROMETRIC METHOD)

PART B: DEMONSTRATION

NAME: EARL WALROW OTT)R	POSITION: RANT Operator
LOCATION: VIP	WORK CENTER: VIP
ISSUE DATE: 7.7.2009	REEXAMINATION DATE:

1990E DATE. 7	7 2804 REEAWINATION DATE:
Test Instructions	The individual shall conduct a pH analysis test as outlined by the Sampling and Testing SOP. Assume you are starting the beginning of the day shift.
· .	Select one answer for each question, based on your observations while the test is being performed. The highlighted response reflects the correct answer. For certification of proficiency, the individual must obtain a score of 100 for questions #1-11, and the "analyzed value" of the known QA/QC solution must fall within the acceptable range for the QA/QC solution.
	NOTE: The QA/QC solution used for testing <u>MUST</u> be analyzed and reported to two (2) places following the decimal point
·.	If an individual is deficient on any question, review the proper procedures as necessary after the test is finished. If it is clearly evident that the individual is not familiar with the test, stop the test and set up the necessary training and reexamination schedule.

YES	NO	N/A	QUESTIONS
	,		Did the operator verify that the:
M			a. pH electrode fill hole was open?
			 b. Electrolyte was at the proper level? (no more than 1/2" from the top of the fill hole)
M			(1) If not, was the electrolyte added?
X			c. pH electrode was free of <u>discolored</u> electrolyte or crystals?
M			d. pH electrode tip had less than 1/2 inch of crystalline build-up?
M			e. Holding time for the buffer solutions had not expired.
×			Were the pH buffer solutions and electrode soaking solution changed by discarding the solution in each small container, rinsing with high purity water, followed by a rinse with the proper buffer solution, then refilling each small container with the proper buffer solution?
			3. During the meter calibration with the first buffer solution:
A			a. Was pH 7 standardized buffer solution used?
Ø			b. Was the buffer stirred gently?
M			 Was the instrument display cleared prior to beginning the meter calibration?
M			d. Did the operator wait until the display "Eye" stopped flashing before removing the electrode from the buffer solution?

YES	NO	N/A	QUESTIONS	
D			e.	Were the electrodes rinsed with high purity water and blotted dry?
			f.	Were the electrodes wiped?
			4. Durin	g the meter calibration with the second buffer solution:
M			a.	Was pH 4 buffer solution was used?
X			b.	Did the operator wait until the display "Eye" stopped flashing before removing the electrode from the buffer solution?
			Ċ.	Were the electrodes rinsed with high purity water and blotted dry?
	X		d.	Were the electrodes wiped?
.4			5. Durin	g the meter calibration with the third buffer solution:
N N			a.	Was pH 10 buffer solution was used?
M			b.	Did the operator wait until the display "Eye" stopped flashing before removing the electrode from the buffer solution?
M			C,	Were the electrodes rinsed with high purity water and blotted dry?
	X		d.	Were the electrodes wiped?
A				the buffer solutions capped after the meter calibration was leted?
X			7. Were	the electrodes returned to the soaking solution?
			8. Was t	he following recorded on the worksheet:
M			a.	Time of calibration
M			b.	Operators initials
			C.	Actual value of the buffer solutions used
X.			d.	Temperature of the buffer solutions
		,	e.	Time the soaking and buffer solutions were changed.
翼			9. Was	oH 7 buffer solution analyzed as a "check sample"?
			a.	Did the operator understand that he should check the "Variation of pH with Temperature Chart" to verify that the meter reading was within +/- 0.1 unit of the appropriate reading?
			10. During	Ine pH analysis of the QA/QC solution:
M			a.	Was the operator aware that samples should be mixed thoroughly prior to beginning the analysis?
X			b.	Were the electrodes rinsed with high purity water and blotted dry after removal from the soaking solution?
	図		G.	Were the electrodes wiped?
×			d.	Was the sample stirred gently?
×			e.	Did the operator wait until the display "Eye stopped flashing before recording the pH of the QA/QC solution?
M			f.	Were the electrodes rinsed with high purity water and blotted dry?
M			g,	Were the electrodes returned to the soaking solution for storage between measurements?

YES	NO	N/A	QUESTIONS	
N			h.	Was the magnetic stirplate turned off when the analysis was completed?
M			1.	Did the operator know to record his initials in the appropriate place when recording the final effluent data?
M			j,	Was the operator aware that the analysis of the final effluent sample must be completed within 15 minutes?
A			k. range?	Was the pH value of the QA/QC solution within the acceptable
		,		Code # of QA/QC Solution
				Analyzed Value 8.06 S.U Acceptable Range 8.05-8.33 S.U.
			-	
Comr	nents;			
	·			
Teste	d By:		LO)	Date: 7/2/09

TREATMENT PLANT SAMPLING AND TESTING PROCEDURES HAMPTON ROADS SANITATION DISTRICT

PH PROFICIENCY TEST WORKSHEET

pH METER CALIBRATION

OPERATORS INITIALS	EO	
TIME BUFFER AND SOAKING SOLUTIONS CHANGED	7:40	
CALIBRATION TIME	8:40	
	pH Reading, S.U.	Temperature, degrees C
Meter Reading, pH 7 Buffer	7.01 - 22.	22.3
Meter Reading, pH 4 Buffer	4.00	22.1
Meter Reading, pH 10 Buffer	10.04	22.3

CHECK SAMPLE	n/	
pH Buffer "Check sample" meter reading _	7.04	s.u.
QC SAMPLE		
Time of analysis 8:4/		
QC Sample Meter Reading 8.06	s.u,	

Turbidi	ty Meter Ver	fication		1000		Assigned	VaksAccept Range	Meder Value	建设设施 证
Assigned		Moler	Coerato	Herr Spee On		inge i	RC MOLTRO	regil TRC	Check
				CON CHES	0072010			0.00	
5	4-5	5	JRF	On Price Life		Harold Haron	国政政政政	0.21	OK
45	41-47	45	JRF	JRF	4:51			0.91	ОК
477	453-501	479	JRF		-6,0.1	3031 238		1,64	ĐK

Nutrient pH					
	notes:				
abioposida	MAKA TIP				
iantasilan					

Алило	nia Meter Verifi	cation
Meter	Acceptable	
Resoliq	Figure 10 and 10	Manager 1
POSTROPIO TONA	STREET,	negretani del

ľ	LAB	VERMICATI	ONS				:\$T p∺	METER CAL	BRATION								ADDITIONAL pl	METER CALL	RATION		
	FNE ph Taken	HIGH Posty Water	TIME of Case		d 7 Buffer				10 Buffer	Sol Chgđ	19. TEN 19.		TIME of Carb.		rd 7 Buller		rd 4 Buffec		d 10 Bullar	TME Buil/Electr Sol Clogd	Calb Performed By
ŀ	s de Maria O Como Santo	200 A 100 A		Meler Rdg	Temp							Meler Rdo	A STATE OF THE STA	Meter Roc	Temp	Meter Ros	Temp	Molet Roo	Temp		
_	PINIT	CRNRED		12/19/24/51/1	Desc		Deg C	200	Deg C	0.00	inles	遊響權	0.00	新新港市	Deg C	排門	Deg C		Deg C	9.00	hatels
•	·		27.12	7 1 2 2 2 2 2		}									ļ	Fall of the	* 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1		* # * * * * * * * * * * * * * * * * * *		
•			177.4 177.7 J.J									ļ					eranjando)	Li .	11 2-15		ļ
0	11.00						1 1	<u> </u>			14 14 15		1 777						100000	ļ	<u> </u>
ó		1 1 2 1	. 2 ' . 2 '	indicipas)						an addition and		<u> </u>		<u> </u>	"TO HELL MINES	25144	Fernick discourse	11110000000	Professional Control	Acres 1	
0	: · · · · ·					1 1 1 1 1		100 to 100	1		Marray)		`			endage ta	ar sankija	All Johnson	e langue e		
0		GRN	449	7,02	16.5	4.00	18.8	10,07	18.9	4:48	JRF .	7.08	<u> </u>	1	Englished	rei y la	MARKET	History HS	arthreaf []		
ō			ļ	<u> </u>	ļ.,			<u> </u>	<u> </u>				ļ	ļ			ļ		<u></u>		
ō		- A -		ta sejárat			<u> </u>				[<u> </u>		·	[a struktive e		** yd ",	1810		
				3.65								<u> </u>	<u> </u>			Brand M	0.0048	Professional Contract			<u> </u>
ő			200	hereta se		and an ord											and street for				
	EO	1124	0 0 . 7 1		<u> </u>						profess.		<u> </u>			111777	duter study	marketeti;	4.74.4		
Ų,		GRH	11949	7,02	19.7	4,00	19,1	10.07	15,2		EO	7:05			1	1 [144:213	Agg strike	,	for a PN		
ÿ	111111		:	Futtri Minis			. 171,000				- # Kilo	30.	1			不知的性		Park District	System 1		,
<u>:</u>				1,220,140,4												3,,,,	Alasamiy.	1100			ľ
,					1											l				•	
																	7,24 17				
	1.			7 (1 m) 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1						****						37.7.1		oper from	1 11 11		
			12.25	22.545.00			,		1		100	17.	1.		H 7552		- errigerije	HELE PAR	\$10 eve 21		
3	-			Mark H											2001 12	Patient (ym (ann	a-Author	180 14		
		1707		at estab	4.4		1			10000	raga i		1000		1 2 1 1 2 1	1900	5,315,517	aret arris	A155	1	· · ·
6.1	2.2.5	Gra	2024	7.01	21,8	4.00	21.2	10,09	21.7	1,2,10,12	yww.	· 7:05	7	J	1.4 (1.11	19 [247:12		00000000	44411		1 .25 11
	H	10 mg 15 mg		7.5	1 11 11 11	3.7	-		***	111-12-2	1 12 × 12 ×	1.3	1000	1 1	A11 47 (17 17 17 17 17 17 17 17 17 17 17 17 17 1	rikeret.	O. Art.	out intilize	ryl art.	1	
	·**			 	 	1				1	1	<u> </u>	<u> </u>	<u> </u>	†			 	<u> </u>	†	
		11,71,711	5.15.	7 (1.5)		1			7.7.7		1			1	1 7 2 7 7 7	rumiglio	Altric II.,	that byit	aller Trains		
4	EO Operato		1.5.2.2.5	L	1	ļ		<u> </u>		<u> </u>	<u> </u>		<u> </u>	L	<u> </u>			1	<u> </u>	1	1

Laboratory Stakeholders Workgroup

Summary of May 12, June 16, July 14, and August 18, September 29 and December 8, 2008 Meetings

Attendance: Organizations represented were Virginia Municipal Wastewater Association, Virginia Manufacturing Association, Virginia Rural Water Association, Virginia Water Environment Association Laboratory Practices Committee, commercial laboratories, and DEQ.

The following laboratory related recommendations were agreed upon by members of the workgroup. DEQ will consider these recommendations when developing further guidance.

TOPICS

1. Standard Methods (SM) Part 1000

VPDES permits require proper operation and maintenance which includes "adequate laboratory controls and appropriate quality assurance procedures." The work group agreed that following SM Part 1020, with modifications, along with QC components recommended by EPA would fulfill the permit QA/QC requirements for compliance analyses. The components given below are the minimum QC to be applied to all testing procedures where applicable, not just SM methods. A laboratory is to follow the frequency and acceptance criteria given in the approved edition of SM cited by the laboratory.

a. Initial Demonstration of Capability (IDC)

- A facility/laboratory training program that is accepted by DEQ may be used as an alternative to analyzing four replicates of an independent check sample. This will allow facilities that already have an extensive well documented training program in place to continue using them without incurring additional costs.

Components of an alternate training program to be presented to DEQ

must include the following:

Demonstrated knowledge of the method
Demonstrated ability to conduct all aspects of the method the
analyst will perform
Analysis of at least two replicates of an independently
prepared check sample

b. Matrix spikes

- Matrix is defined as wastewater.

- Captive labs are expected to rotate outfalls when selecting samples

for spiking.

Commercial labs are to randomly select samples for spiking. When a
client requests that a specific sample be spiked, this sample may
occasionally be used in place of a randomly selected sample;

- c. Analysis of externally supplied standards
 - -Recovery must meet method/SM/DEQ established acceptance criterion.
 - DEQ's established criteria of 80 -120% recovery is to be used in place of control charts when a method requires the laboratory to establish the acceptable limits.
 - Manufacturers' established acceptance criteria may not be used because they are parameter specific, not method specific.
- d. Analysis of reagent blanks
 - -Glassware used in the analysis of blanks must be randomly selected, unless specified otherwise in the method.
- e. Calibrations with standards no modifications were suggested.
- f. Analysis of analytical duplicates

Analytical duplicates should be split from the sample container received by the laboratory.

Field measurements, defined as "required analysis within 15 minutes of collection" (i.e., pH, DO, TRC, and temperature), will not require analytical duplicates. Removal of this requirement for these parameters is based on problems associated with reporting min/max limits in permits and the possibility of a rapidly changing concentration in a given sample.

- g. Positive and negative controls for microbiological pollutants
 - -Positive control may be a dilute influent from a source within the wastewater treatment process containing the microorganism(s) of interest.
 - -Negative control may be a sterile-water blank for laboratories using manufacturer-prepared media; laboratories preparing their own media (i.e., using media other than unit-dose-media such as Colilert) must also inoculate the prepared media with a culture known to produce a negative response.
- h. Corrective action for failed QC
 - -Laboratory/facility must appropriately address failed QC and provide adequate documentation of corrective actions taken,

2. Ortho-phosphate requirement in Watershed Nutrient Trading General Permit The Chesapeake Bay Watershed Nutrient Trading General Permit requires monitoring of ortho-phosphate using approved methods and holding times given in 40 CFR Part 136. This data is required in the general permit for the Chesapeake Bay Program modeling. For several years prior to the issuance of the general permit, some permittees from Maryland, Virginia, Pennsylvania, and DC have voluntarily submitted phosphorus results to the Bay Program for samples that were either filtered or not filtered.

DEQ Chesapeake Bay Program has indicated that there is no EPA guidance identifying the type of reactive phosphorus analysis that should be performed (filtered or unfiltered). The Watershed Nutrient Trading General Permit requires ortho-phosphorus monitoring and filtering of the sample within 15 minutes of sample collection. Since either filtered or unfiltered are acceptable for the Chesapeake Bay program modeling, DEQ Inspection Program will be provided guidance to also accept unfiltered sample as meeting this general permit requirement.

3. Thermistor temperature calibration

Verification of thermistors used in pH meters and dissolved oxygen meters for automatic temperature correction (ATC) was discussed. The Work Group agreed that the Virginia Environmental Accreditation Program (1VAC30-45-860 and 1VAC30-46-210) requirements for annual calibration/verification annual over the entire range of use should be utilized. For a thermistor or thermometer that is used to measure one target temperature a one point calibration at the target temperature meets this requirement.

4. Field duplicates vs. lab duplicates

See Section 1.f. above.

5. QL's listed in permits

When developing limitations for VPDES permits DEQ utilizes site specific discharge and receiving stream information to evaluate if there is a potential to violate water quality criteria. To determine if permit limitations are required DEQ identifies site specific target values (SSTV) for parameters of concern associated with the individual discharge. These SSTVs are used to establish the QLs for parameters of concern required as part of the VPDES application for reissuance.

The work group reviewed "worst case" (hardness, pH, stream flow) SSTV scenarios for number of parameters. As listed below there are a number of parameters for which there is not an achievable QL under the "worst case" scenario for a site specific target value.

Parameter	Worst Case for Site Specific Target Value (ug/l)	Achievable QL
Antimony	1.4	YES
Arsenic	1.0	YES
Cadmium	0.057	YES
Chromium III	3.6	YES
Chromium VI.	1.6	NO
Copper	0.36	NO
Lead	0.35	YES
Mercury	0.005	YES
Nickel	0.94	YES
Selenium	0.75	YES
Silver	0.0032	NO
Zinc	. 3.6	YES

Pentachiorophenol	0.0015 (1)	NO
Hydrogen sulfide (2)	0.05 (1)	NO NO
Cyanide	1.3 (1)	NO

DEQ should insure that permit writers are utilizing existing guidance for requiring QLs to address specific permit requirements. This includes clarification that QLs should only be established to a level that is necessary to determine compliance with individual permit site specific target values. DEQ will continue to advise permittees to use clean sampling protocols for low level analysis.

DEQ should include stakeholder participation as part of the process to revise guidance associated with QL requirements in VPDES permits.

6. Clarification of DEQ's definitions associated with lab work

- Laboratory Control Sample (LCS), Laboratory Intercomparison
 Samples (LIS), and Proficiency Evaluation Sample (PES) are quality
 control samples of known concentration prepared from a source
 different from the one used to prepare standards.
 - LCS is required for VPDES. It is equivalent to the laboratory fortified blank (LFB) which also is from an alternate source and may be prepared by the laboratory.
 - LIS is not required for VPDES.
 - o PES is required only for permittees participating in the Discharge Monitoring Report Quality Assurance Program (DMRQA). This sample must be purchased from an approved PT Provider. The concentration must not be known by the laboratory or permittee.
- Annual once per calendar year

- Quarterly—once within the calendar quarter
- BOD5 final reading must be taken on the fifth day of incubation unless the edition of Standard Methods used by the laboratory establishes a more stringent requirement. (Previously the lab was instructed to take the final reading within plus or minus three hours of the initial reading.)
- Externally Supplied Standard sample of known concentration prepared using a different source than was used to prepare the calibration standards.

7. DEQ Inspection Consistency:

DEQ need to have a process for providing changes to the program to DEQ Inspectors and the regulated community so that there is a clear understanding of the new requirements and that DEQ consistently applies the requirements throughout the state. (example: calibration requirements for thermistor or thermometer)

DEQ should ensure that present guidance requiring a final inspection response letter from DEQ indicating that deficiencies noted in the inspection "have been addressed" is being followed.

Before sending an inspection report DEQ should call the inspected facility/laboratory to clarify report exceptions (to extent possible) identified during review of the facility/laboratory records that were not discussed during the closing interview at the time of the inspection. This approach may allow for clarification and verification of issues prior to the report or help the facility more fully understand the issue when the inspection report is received.

DEQ should classify inspection report exceptions as "comments" or "required actions."

DEQ will examine the use of unannounced inspection to the extent possible recognizing the mandate by the General Assembly to conduct unannounced inspections.

DEQ should continue this workgroup on an annual/semiannual basis to discuss emerging issues as well as to provide a forum to stakeholders to discuss concerns.


8. Composite Requirements for VPDES Permit Application Attachment A Sampling


Certain parameters in Attachment A (base /neutral/acid extractable organic compounds, pesticides and PCBs) are currently required to be monitored via "special composite" or grab samples. The "special composite" sample was initiated by DEQ to address concerns of inaccurate results if a normal composite sample were used for those

pollutants. Based on further DEQ review, DEQ is not aware of any other states that have a similar requirement. Discussions with EPA Region III confirm that Regional III also utilizes standard composite procedures to sample for these parameters. Consequently, DEQ should no longer require the use of "special composite" samples. Attachment A should be revised to reflect the use of "standard" composite or grab samples. For existing permits with the "special composite" requirements DEQ should allow permittees to use the "standard" composite in place of the "special composite" sample.

Other points of discussion:

- Laboratory inspection check sheets and Frequently Asked Questions document will be updated to reflect QA/QC requirement modifications in Topic 1. This Work Group and the Good Laboratory Practices Committee should be provided an opportunity to comment on the draft laboratory inspection check sheets.
- Labs may establish criteria for acceptable relative percent differences (RPD) of duplicates when the concentration of analyte is too low to allow reasonable statistical evaluation.
- The Laboratory Work Group should continue to meet on a semiannual basis to discuss emerging issues.







CERTIFICATE OF CALIBRATION – Effluent Flow Meter

Calibration Date : <u>01-28-10</u> Calibrated By: <u>Pope/Flythe</u>

Location: Virginia Initiative Plant – Effluent Flow Meter

E.I.D. Number: VIP-INST-ST-K-0311-01

Manufacturer: Milltronics

Model Number: Multiranger Plus

Serial Number: 050643

Test Equipment Used:	Milltronics Keypad; Multimeter; Screwdriver; Tape Measure; Parshall Flu	me
Chart		

	Sec.	
Calibration Data:	·	

%	Eng. Units MGD	Before Cal Output (mA)	After Cal. Output (mA)	Error
0	0	4.01	4.01	
100	80	20.01	20.01	


Additional Notes: No Adjustments Made

Pope 01-28-10

Signature of Calibration Technician / Date

ATTACHMENT 2

DISCHARGE LOCATION/TOPOGRAPHIC MAP




Location Map for Virginia Initiative Plant

Scale: 1*=2000'


ATTACHMENT 3

SCHEMATIC/PLANS & SPECS/SITE MAP/ WATER BALANCE



VIRGINIA INITIATIVE PLANT


Solids Handling Flow Diagram






VIRGINIA INITIATIVE PLANT

Sewage Treatment Flow Diagram





VIRGINIA INITIATIVE PLANT- OUTFALL LOCATIONS



ATTACHMENT 4

TABLE I - DISCHARGE/OUTFALL DESCRIPTION

TABLE I

NUMBER AND DESCRIPTION OF OUTFALLS

OUTFALL	DISCHARGE	DISCHARGE SOURCE	TREATMENT (2)	FLOW
NO.	LOCATION	等量達得等等(1)。特別是學家	(2)	(3)
001	36°52′ 57″N	POTW, primary treated	Secondary treatment provided	40 MGD
	076°19′20″W	wastewater effluent	by screening, grit removal, primary and secondary	
	ļ	discharge		design
	İ		clarification, activated	flow
	ļ		sludge including enhanced	
			biological nutrient removal	· ·
		-	chlorination, and	
			dechlorination.	
002	36°56′ 18″N	POTW, alternate for fully	Same as above	
	076°61′032″W	treated waste	·	Same as
				above
003	36°52′58″N	POTW, emergency bypass	No treatment except Chlorine	
	076°19′16″W	point	- not included in the permit	N/A
	·		-	_
004	·36°52′55″N	Storm Water	No treatment provided, best	
•	076°18′58″W	·	management practices used.	0.006 MG
				_
005	36°52′52″N	Storm Water	No treatment provided, best	
•	076°18′59″W	,	management practices used.	0.009 MG
006	36°52′55″N	Storm Water	No treatment provided, best	
	076°19′05″W		management practices used.	0.003 MG
			•	
007	36°52′59″N	Storm Water	No treatment provided, best	-
007	076°19′07″W	5551 772552	management practices used.	0.002 MG

008	36°52′53″N	Storm Water	No treatment provided, best	-
000	076°19'`14"W	BCOTIL WALCET	management practices used.	0 0000 MG
	0,01) 11 "	·	management practices about	0.0009 MG
009	36°52′51″N	Storm Water	No treatment provided, best	-
009	076°19′15″W	Scorm water	management practices used.	
	070 19 13 W		management practices asca.	0.005 MG
010	36°53′01″N	Charm Nahar	No treatment provided, best	1
010	076°19′13″W	Storm Water	management practices used.	
	0 10 13 13 W		management practices used.	0.003 MG
10.0.0	252701 55 "17		1	<u> </u>
011	36°52′59″N	Storm Water	No treatment provided, best	
	076°19′10″W		management practices used.	0.0009 MG
	0.63701 == ":"		37	ļ
012	36°52′57″N	Storm Water	No treatment provided, best	
	076°19′07″W	·	management practices used.	0.001 MG
013	36°52′ 58″N	Storm Water	No treatment provided, best	
	076°19′05″W		management practices used.	0.008 MG
	·			
014	36°53′01″N	Storm Water	No treatment provided best	
	076°18′57″W		management practices used.	0.002 MG
	1	1	•	
	1			'

⁽¹⁾ List operations contributing to flow

SEE ATTACHED SHEET

⁽²⁾ Give brief description, unit by unit

⁽³⁾ Give maximum 30-day average flow for industry and design flow for municipal

Virginia Initiative STP VA0081281

IV.A. Drainage Area of Outfalls

	Area of Impervious	Total Area Drained]
Outfall	Surface (ft ²)	(ft ²)	
004	12800	127000	0.006 MGD
005	59661	168300	.009 mG
006	21672	64000	, 003
007	5600	35000	.002
008	3400	18300	.0009
009	19882	102400	,005
010	25854	62100	,003
011	5600	18160].∞૦૧
012	14778	22300	.001
013	52812	148200	. DO8
014	6400	32000	, <i>00</i> 2

Total = 0.041

ATTACHMENT 5

TABLE II - EFFLUENT MONITORING/LIMITATIONS

TABLE II - INDUSTRIAL EFFLUENT LIMITATIONS/MONITORING

OUTFALL # 001 and 002[i]

DESIGN FLOW: 40 MGD

Outfall Description: Municipal Discharge

SIC CODE: 4952

(X) Final Limits () Interim Limits Effective Dates - From: Reissuance To: Expiration

				EFFLUENT I	MONITORING REQUIREMENTS			
PARAMETER & UNITS	BASIS FOR LIMITS	DESIGN FLOW MULTIPLIER	MONTHLY AVERAGE	WEEKLY AVERAGE	MINIMUM	MAXIMUM	FREQUENCY	SAMPLE TYPE
Flow (MGD)[a]	3		NL	NA	NA .	NL	Continuous	TI & RE**
pH (S.U.)	1		NA	NA	6.0	9.0	1/Day	Grab
BOD5 (mg/1)[c][d]	. 1	40	30	45	NA	NA	3/Week	24-Hr. Comp
BOD5 (kg/d) [d]	1	40	4542	6813	NA	NA	3/Week	24-Hr. Comp
TSS (mg/l)[c][d]	1	40	30	45	NA . ·	NA	3/Week	24-Hr. Comp
TSS (kg/d)[d]	1	40	4542	6813	NA	` NA	3/Week	24-Hr. Comp
TRC (mg/l)[b][c]	2		0.20	2.4	· NA	NA	1/Day	Grab
Total Phosphorus (mg/l)	3		NL	NA	NA	NA	1/Month	24-Hr. Comp
Total Phosphorus (mg/l) Year to date [f]	3		NL	NA	NA	NA	1/Month	Calc
Total Phosphorus (mg/l) Calendar Year [e][f]	3		2.0	NA	NA	NA	1/Year	Calc
Fecal Coliform (n/cml)[d] [g]	2		200	NA	NA	NA 	1/Week (Between 10 am & 4 pm)	Grab
Enterococci (n/cml) [d] [h]	2 .		35	AN	NA	NA	2/Month (Between 10 am & 4 pm)	Grab

^{**}Totalizing, Indicating & Recording Equipment

NA = NOT APPLICABLE; NL = NO LIMIT, MONITORING REQUIREMENT ONLY

1 Year= January 1-December 31; reported for each full calendar year

Upon issuance of the permit, Discharge Monitoring Reports (DMRs) shall be submitted to the regional office at the frequency required by the permit regardless of whether an actual discharge occurs. In the event that there is no discharge for the monitoring period, then "no discharge" shall be reported on the DMR.

In addition to any Total Nitrogen or Total Phosphorus concentration limits listed above, this facility has Total Nitrogen and Total Phosphorus calendar year load limits associated with this outfall included in the current Registration List under registration number VAN040090, enforceable under the General VPDES Watershed Permit Regulation for Total Nitrogen and Total Phosphorus Discharges and Nutrient Trading in the Chesapeake Watershed in Virginia.

- [a] The design flow of this treatment facility is 40 MGD. See Part I.C.5 for additional flow requirements.
- [b] See Part I.B. for additional chlorine monitoring instructions.
- [c] See Parts I.C.7 and I.C.8 for quantification levels and reporting requirements, respectively.
- [d] See Part I.C.9 for additional instructions regarding effluent monitoring frequencies.
- [e] Annual average limitation, based on a calculation of all samples collected during the calendar year.
- [f] See Part I.C.12.for additional instructions regarding Total Phosphorus
- [g] Fecal Coliform monthly average is calculated as a geometric mean.
- [h] Enterococci monthly average is calculated as a geometric mean. Samples must be taken at least 7 days apart.
- [i] Monitoring for Outfall 001 represents Outfall 002. There is no Part I.A. reporting for Outfall 002. See Part I.C.6. for additional requirements for Outfall 002.
 - 2. There shall be no discharge of floating solids or visible foam in other than trace amounts.
 - 3. At least 85% removal for BOD and TSS must be attained for this effluent.

The basis for the limitations codes are:

- 1. Technology (e.g., Federal Effluent Guidelines)
- 2. Water Quality Standards (9 VAC 25-260 et. seq.)
- 3. Best Professional Judgment

TABLE II - STORM WATER EFFLUENT LIMITATIONS/MONITORING

OUTFALLS # 004-014

Outfall Description: Stormwater Not Associated With Regulated Industrial Activity

SIC CODE: 4952

THESE OUTFALLS SHALL CONTAIN STORM WATER RUNOFF NOT ASSOCIATED WITH A REGULATED INDUSTRIAL ACTIVITY WHERE NO MONITORING IS REQUIRED. THERE SHALL BE NO DISCHARGE OF PROCESS WASTEWATER FROM THESE OUTFALLS.

No exposure status has been given to these outfalls.

TABLE II - MUNICIPAL MINOR EFFLUENT LIMITATIONS Attachment 5 continued

Final Chlorine Limitations Effective Dates - From: Permit Issuance

To: Permit Expiration

TRC **	AFTER CL2 CONTACT TANK (Dechlor. Required)			TER RINATION	AFTER CL2 CONTACT TANK (Dechlor. Not Required)					
	MIN.	EXC.	INST. MIN.	WKLY AVG.	INST. MAX.	PERMIT RANGE	EXC.	REPORT- ING RANGE	EXC.	TECH. MAX.
a) Non- Detect. Dechlor. Required		 ·			· <u></u>	NA	NA	NA	NA ·	NA
b) Detect. Dechlor. Required	0.30 mg/l	36	0.30 mg/l*	2.4 mg/l		`.NA	NA	ŅA	NA	NA
c) No Dechlor.	NA	NA	NA	NA	ŅA					

^{*} Reporting is required when 3 or more consecutive readings are <0.30 mg/l or when the TRC is <0.1 mg/l.

** -- Chlorine mass balance Cw (W for Tidal systems): check one

a) C_w < 0.1 mg/l [dechlor. required, non-detectable format]

X b) 0.1 mg/l $\leq C_w \leq$ 2.0 mg/l (2.5 mg/l for PWS, Shellfish waters) [dechlor, required, detectable format]

The design flow of this treatment facility is 40 MGD.

NA = NOT APPLICABLE; NL = NO LIMIT, MONITORING REQUIREMENT ONLY

See Part I.B. for additional TRC limitations.

c) C_w > 2.0 mg/l (2.5 mg/l for PWS, Shellfish waters) [dechlor. not required, include a restrictive technology max. value]

ATTACHMENT 6

EFFLUENT LIMITATIONS/MONITORING RATIONALE/SUITABLE DATA/
ANTIDEGRADATION/ANTIBACKSLIDING

HRSD Virginia Initiative STP Rationale For Parameters, Limitations, And Sampling Requirements Outfall 001/002

Flow:

No limit, monitoring is required with continuous, totalizing, indicating or recording equipment. This based on the VPDES Permit Manual, and is standard for sanitary wastewater plants with discharges greater than 2 MGD. The design flow of 40 MGD is the baseline for the 95% design flow capacity notification.

: Hq

Minimum limit of 6.0 and maximum of 9.0 S.U. These limits are based on Federal Effluent Guidelines (40 CFR 133.102) and Water Quality Standards in 9 VAC 25-260-50, which limits pH to the range above for coastal waters of the State. Monitoring is a daily grab sample and is standard for sanitary WW plants with discharges greater than 2 MGD.

Biochemical Oxygen Demand:

Monthly average of 30 mg/l and 4542 kg/day and a weekly average of 45 mg/l and 6813 kg/day. This is based on Federal Effluent Guidelines (40 CFR 133.102) which sets the limits for secondary WW plants. Loading limits are in whole numbers based upon the latest DEQ significant figures guidance (06-2016). Monitoring required is a 24 hour composite, 3 days a week. The frequency is based upon previous permit reissuances where DEQ guidance document 98-2005 was used to decrease the monitoring frequency to 3 days/week. This will be carried forward for this reissuance.

Total Suspended Solids:

Monthly average of 30 mg/l and 4542 kg/day and a weekly average of 45 mg/l and 6813 kg/day. This is based on Federal Effluent Guidelines (40 CFR 133.102) which sets the limits for secondary WW plants. Loading limits are in whole numbers based upon the latest DEQ significant figures guidance (06-2016). Monitoring required is a 24 hour composite, 3 days a week. The frequency is based upon previous permit reissuances where DEQ guidance document 98-2005 was used to decrease the monitoring frequency to 3 days/week. This will be carried forward for this reissuance.

Total Residual Contact Chlorine:

Minimum limit after contact time is 0.30 mg/l with 36 exceptions. This value was determined from the HRSD Chlorine Reduction Test which was approved by DEQ in February 1997. In addition, it follows the requirements of the VPDES permit manual. These process monitoring limits are believed necessary to ensure proper disinfection. Monitoring required is a grab sample once every two hours. This is based on the VPDES Permit Manual and is standard for municipal discharges of > 2.0 MGD to nutrient enriched waters.

A special condition requires reporting if the chlorine concentration falls below 0.30~mg/l or chlorination is lost(<0.10 mg/l).

Final Total Residual Chlorine:

A weekly average of 2.4 mg/l. A monthly average of 0.20 mg/l. This is a technology based limit following guidance document 00-2011 and is carried forward from the current permit. Monitoring is required once/day by grab sample. The frequency is based on the VPDES permit manual and is standard for municipal discharges of >2.0 MGD.

Fecal Coliform:

Monthly average of 200 n/cml. This is based on Water Quality Standards (9 VAC 25-260-160) and is believed protective of instream standards. Monitoring required is a grab sample once a week. The VPDES Manual allows reduction to this frequency based on long term average discharge values in relation to the monthly average limit. Current guidance requires fecal coliform monitoring in salt or transition waters if the discharge is to shellfish waters. BPJ determines that this frequency is adequate to determine compliance with the standard.

Enterococci:

A monthly average limit of 35 n/cml is included per water quality standards. Sampling is required 2/Month to be calculated as a geometric mean. Samples must be taken at least 7 days apart. This is carried forward from the current permit. Enterococci was added at the time of the last permit reissuance due to Enterococci monitoring becoming an issue that EPA addressed in late 2007/early 2008.

Total Phosphorus Calendar Year

An annual average concentration limit of 2.0 mg/l is placed in the permit with monitoring on an annual basis. Additional nutrient monitoring and reporting is covered under the General VPDES Watershed Permit for Total Nitrogen and Total Phosphorus. The Virginia Initiative Plant HRSD facility is covered under VAN040090. On 5/16/07 guidance document 07-2008 was released by DEQ Central Office for the implementation of the nutrient general permit in relation to the individual permit. The 2.0 mg/l limit is carried forward to the reissued permit.

Total Phosphorus Year-to-Date

There is no limit for the monthly average TP Year-to-date parameter. This parameter was added to the permit in accordance with guidance document 07-2008. Reporting is 1/M and is a calculation. Data for this parameter is collected in accordance with the VPDES permit VAN040090 for the James River Watershed held by HRSD.

Total Phosphorus

There is no limit for the monthly average phosphorus parameter. This parameter was added to the permit in accordance with guidance document 07-2008. Reporting is 1/M. Data for this parameter is collected in accordance with the VPDES permit VAN040090 for the James River Watershed. Reporting for this parameter is required in the individual permit (IP) because the annual concentration limits is contained in the IP. All data used to calculate and determine compliance with the limit in the IP needs to be in the same document and reported on the same form as the limit.

Water Quality Standards Reasonable Potential

Nickel, Zinc, Ammonia, Bromoform, Chlorodibromomethane, and Cyanide all had a quantifiable concentration for the data gathered for the 2012 application. However, these data points were significantly below the most limiting wasteload allocations found in the attached wasteload allocation analysis. No limits were needed for these parameters.

All other water quality parameters reported on Form 2A were below the quantification levels. No additional limits are needed at this time.

Mixing Zone Analysis

A dilution study was submitted for this facility in 1998. The dilution study was approved by central office at the time of submittal. The acute dilution ratio is 41:1 and the chronic ratio is 113:1.

Stormwater

Outfalls 004-014 are discharges of stormwater from the plant (industrial) area. HRSD submitted stormwater sample data from one outfall located at the VIP HRSD plant. It is HRSD's position that this data represents all the stormwater outfall discharges for this plant site.

HRSD has met the requirements for industrial "no exposure", thereby only discharging stormwater <u>not associated</u> with an industrial activity. The Stormwater Management Condition has been removed from the permit. The "no exposure" certification form is attached to the section.

Outfall 003

Outfall 003 is described in the permit application as an outfall that received no treatment and is therefore considered a bypass. As such, it will not be included in the permit under part I Limitations or Special Conditions. Discharges from Outfall 003 must meet requirements in the Part U and other appropriate parts of the Standard Conditions found in Part II of the permit.

VIRGINIA DEQ NO EXPOSURE CERTIFICATION FOR EXCLUSION FROM VPDES STORM WATER PERMITTING

Submission of this No Exposure Certification constitutes notice that the entity identified below does not require permit authorization for its storm water discharges associated with industrial activity under the VPDES Permit Program due to the existence of a condition of No Exposure.

A condition of No Exposure exists at an industrial facility when all industrial materials and activities are protected by a storm resistant shelter to prevent exposure to rain, snow, snowmelt, and/or runoff. Industrial materials or activities include, but are not limited to, material handling equipment or activities, industrial machinery, raw materials, intermediate products, byproducts, final products, or waste products. Material handling activities include the storage, loading and unloading, transportation, or conveyance of any raw material, intermediate product, final product or waste product. A storm resistant shelter is not required for the following industrial materials and activities:

- drums, barrels, tanks, and similar containers that are tightly sealed, provided those containers are not deteriorated and do not leak. "Sealed" means banded or otherwise secured and without operational taps or valves;
- adequately maintained vehicles used in material handling; and
- final products, other than products that would be mobilized in storm water discharges (e.g., rock salt).

A No Exposure Certification must be provided for each facility qualifying for the No Exposure exclusion. In addition, the exclusion from VPDES permitting is available on a facility-wide basis only, not for individual outfalls. If any industrial activities or materials are or will be exposed to precipitation, the facility is not eligible for the No Exposure exclusion.

	Please Type or Print All Information. ALL INFORMATION ON THIS FORM MUST BE PROVIDED.	_
1.	. Facility Operator Information	
	Name: Hampton Roads Sanitation District	
	Mailing Address: 1436 Air Rail Avenue	
	City: Virginia Beach State: VA Zip: 23455 Phone: 757-460-2261	
2.	. Facility/Site Location Information Facility Name: Virginia Initiative STP Address: 4201 Powhatan Avenue	
	Address: 4201 Powhatan Avenue	DEQ
	Address: 4201 Powhatan Avenue City: Norfolk County Name: State: VA State: VA Zip: 23508 TicleWater Region Office	
	County Name:	al /
	Latitude: 36 53' 00" Longitude: 76 19' 00"	
3.	. Was the facility or site previously covered under a VPDES storm water permit? Yes 🗹 No 🗌	
	If "Yes", enter the VPDES permit number: VA0081281	
4.	SIC/Activity Codes: Primary: 4952 Secondary (if applicable):	
5.	. Total size of facility/site associated with industrial activity: 24.3 acres	
6.	. Have you paved or roofed over a formerly exposed pervious area in order to qualify for the No Expension? Yes No V	osure
	If "Yes", please indicate approximately how much area was paved or roofed. Completing this question not disqualify you for the No Exposure exclusion. However, DEQ may use this information in considerable whether storm water discharges from your site are likely to have an adverse impact on water quality, in case you could be required to obtain permit coverage.	dering

7.	Exp	osure Ch	ecklist		
	che	ck either "`	e following materials or activities exposed to precipitation, now or in the foreseeable Yes" or "No" in the appropriate box.) If you answer "Yes" to any of these questing eligible for the No Exposure exclusion.		
		· · · · · ·		Yes	No
	(1)	-	oring or cleaning industrial machinery or equipment, and areas where residuals g, storing or cleaning industrial machinery or equipment remain and are exposed water		\checkmark
	(2).	Materials	or residuals on the ground or in storm water inlets from spill/leaks		\checkmark
	(3)	Materials of	or products from past industrial activity		$\overline{\checkmark}$
	(4)	Material h	andling equipment (except adequately maintained vehicles)		$\overline{\checkmark}$
	(5)	Materials	or products during loading/unloading or transporting activities		
	(6)		or products stored outdoors (except final products intended for outside use [e.g., where exposure to storm water does not result in the discharge of pollutants)		<u></u>
	(7)	Materials o	contained in open, deteriorated or leaking storage drums, barrels, tanks, and ntainers		✓
	(8)	Materials discharge	or products handled/stored on roads or railways owned or maintained by the		✓
	(9)	Waste ma	aterial (except waste in covered, non-leaking containers [e.g., dumpsters])		\checkmark
4	(10)	Application	n or disposal of process wastewater (unless otherwise permitted)		\overline{V}
((11)		e matter or visible deposits of residuals from roof stacks and/or vents not otherwise (i.e., under an air quality control permit) and evident in the storm water outflow		$\overline{\checkmark}$
8.	Cer	tification	Statement		
exp wat	osui er c	re and obtoniate	nalty of law that I have read and understand the eligibility requirements for claiming taining an exclusion from VPDES storm water permitting; and that there are no disceed by exposure to industrial activities or materials from the industrial facility identified d under 9 VAC 25-31-120 E 2).	charges	of storm
env app pen req	riron lical form uest	mental Quole). I unde inspection . I unders	I am obligated to submit a No Exposure Certification form once every five years to the pality and, if requested, to the operator of the local MS4 into which this facility discretand that I must allow the Department, or MS4 operator where the discharge is into us to confirm the condition of no exposure and to make such inspection reports publicated that I must obtain coverage under a VPDES permit prior to any point source diswith industrial activity from the facility.	ischarge: the local ly availa	s (where I MS4, to ble upon
acc sub in g	orda mitte pathe plet	nce with a ed. Based ering the internal te. I am a	halty of law that this document and all attachments were prepared under my direction a system designed to assure that qualified personnel properly gathered and evaluated upon my inquiry of the person or persons who manage the system, or those persons information, the information submitted is to the best of my knowledge and belief to ware that there are significant penalties for submitting false information, including the for knowing violations.	ed the inf s directly ue, accu	ormation involved rate and
	Prir	nt Name:	Edward G. Henifin, P.E.		_
	Prin	it Title:	General Manager		
	Sigi	nature:	MMBM		-
	Dat	e:	3/15/2012		
			For Department of Environmental Quality Use Only		*****

Accepted/Not Accepted by: _

Date :

Permit No.	Parameter Description	E QTYAVO	3. [™] QTYMA	XIXCONCM	IN CONCAV	G CONCMA	X Start Date	攤後End Date
VA0081281	FLOW	25.01	29.13	Control of the Contro	S - Marie Billion Company		01-Feb-2008	29-Feb-2008
VA0081281	PH			6.9		7,1	01-Feb-2008	29-Feb-2008
VA0081281	BOD5	488	527	 ``	5	6	01-Feb-2008	29-Feb-2008
VA0081281	TSS	698	895		7.3	10	01-Feb-2008	29-Feb-2008
VA0081281	COLIFORM, FECAL	1070			2		01-Feb-2008	29-Feb-2008
VA0081281	TP				0.39		01-Feb-2008	29-Feb-2008
VA0081281	CL2, TOTAL CONTACT			0.35	0.39		01-Feb-2008	29-Feb-2008
VA0081281	CL2, TOTAL FINAL			0,35	0.061	0.11	01-Feb-2008	29-Feb-2008
VA0081281	<u> </u>				0.84	0.11		29-Feb-2008
	TP (YEAR-TO-DATE)	20.42	124 70	 	0.84		01-Feb-2008	
VA0081281	FLOW	28.42	36.70				01-Mar-2008	31-Mar-2008
VA0081281	PH	1	1001	6.8		7.2	01-Mar-2008	31-Mar-2008
VA0081281	BOD5	674	1036		6	9	01-Mar-2008	31-Mar-2008
VA0081281	TSS	760	1151		7.0	10	01-Mar-2008	31-Mar-2008
VA0081281	COLIFORM, FECAL	ļ			3		01-Mar-2008	31-Mar-2008
VA0081281	TP				0.38	-	01-Mar-2008	31-Mar-2008
VA0081281	CL2, TOTAL CONTACT			0.19			01-Mar-2008	31-Mar-2008
VA0081281	CL2, TOTAL FINAL				0.018	0.057	01-Mar-2008	31-Mar-2008
VA0081281	TP (YEAR-TO-DATE)				0.68		01-Mar-2008	31-Mar-2008
VA0081281	FLOW	32,10	51.54				01-Apr-2008	30-Apr-2008
VA0081281	РН			6.6		7.2	01-Apr-2008	30-Apr-2008
VA0081281	BOD5	885	1263		7	10	01-Apr-2008	30-Apr-2008
VA0081281	TSS	875	1251		· 7.0	10	01-Apr-2008	30-Apr-2008
VA0081281	COLIFORM, FECAL	1			4		01-Apr-2008	30-Apr-2008
VA0081281	TP				0.47		01-Apr-2008	30-Apr-2008
VA0081281	CL2, TOTAL CONTACT	•		0.29	i i		01-Apr-2008	30-Apr-2008
VA0081281	CL2, TOTAL FINAL				0.022	0.016	01-Apr-2008	30-Apr-2008
VA0081281	TP (YEAR-TO-DATE)				0.63		01-Apr-2008	30-Apr-2008
VA0081281	FLOW	29.27	33.44				01-May-2008	31-May-2008
VA0081281	PH		100	6.9		7.2	01-May-2008	31-May-2008
VA0081281	BOD5	401	455		4	4	01-May-2008	31-May-2008
VA0081281	TSS	646	819	•	5.8	7.1	01-May-2008	31-May-2008
VA0081281	COLIFORM, FECAL	10-10	1019		87	7.3	01-May-2008	31-May-2008
VA0081281	TP TP			+	0.37		01-May-2008	31-May-2008
VA0081281	CL2, TOTAL CONTACT			0.26	0.57		01-May-2008	31-May-2008
VA0081281	CL2, TOTAL FINAL			0.20	0.067	0.096	01-May-2008	31-May-2008
-	TP (YEAR-TO-DATE)	+	_			0.096	<u> </u>	31-May-2008
VA0081281	 	2/ 22	20.00		0.58		01-May-2008	
VA0081281	FLOW	26.33	29.90			7.0	01-Jun-2008	30-Jun-2008
VA0081281	PH	1244		6.8		7.2	01-Jun-2008	30-Jun-2008
VA0081281	BOD5	344	511		3	5 .	01-Jun-2008	30-Jun-2008
VA0081281	TSS	441	597		4.4	5.8	01-Jun-2008	30-Jun-2008
VA0081281	COLIFORM, FECAL			·	3		01-Jun-2008	30-Jun-2008
VA0081281	TP ·				0.46		01-Jun-2008	30-Jun-2008
VA0081281	CL2, TOTAL CONTACT			0.44			01-Jun-2008	30-Jun-2008
VA0081281	CL2, TOTAL FINAL				0.049	0.10	01-Jun-2008	30-Jun-2008
VA0081281	TP (YEAR-TO-DATE)				0.56		01-Jun-2008	30-Jun-2008
VA0081281	FLOW	27.52	36.28				01-Jul-2008	31-Jul-2008
VA0081281	PH			6.8		7.2	01-Jul-2008	31-Jul-2008
VA0081281	BOD5	433	557		4	5	01-Jul-2008	31-Jul-2008
VA0081281	TSS	637	975		5.9	8.1	01-Jul-2008	31-Jul-2008
VA0081281	COLIFORM, FECAL				4		01-Jul-2008	31-Jul-2008
VA0081281	ТР				0.80		01-Jul-2008	31-Jul-2008
VA0081281	ENTEROCOCCI				1		01-Jul-2008	31-Júl-2008
VA0081281	CL2, TOTAL CONTACT			0.17			01-Jul-2008	31-Jul-2008
VA0081281	CL2, TOTAL FINAL	1			0.037.	0.071	01-Jul-2008	31-Jul-2008

Permit No	Parameter Description	QTYAVG	QTYMAX	CONCMIN	CONCAVG	CONCMAX	Start Date	End Date
VA0081281	TP (YEAR-TO-DATE)		1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	1	0.59		01-Jul-2008	31-Jul-2008
VA0081281	FLOW	26.35	30.12				01-Aug-2008	31-Aug-2008
VA0081281	PH	-0.00	1	7.0		7.2	01-Aug-2008	31-Aug-2008
VA0081281	BOD5	253	438	17.0	3	5	01-Aug-2008	31-Aug-2008
VA0081281	TSS	450	831		4.6	8.7	01-Aug-2008	31-Aug-2008
VA0081281	COLIFORM, FECAL	1730	031	 	3	0.7	01-Aug-2008	31-Aug-2008
VA0081281	TP			-	0.64			31-Aug-2008
VA0081281	ENTEROCOCCI				1		01-Aug-2008	
VA0081281				0.22			01-Aug-2008	31-Aug-2008
	CL2, TOTAL CONTACT			0.23	10004	0.054	01-Aug-2008	31-Aug-2008
VA0081281	CL2, TOTAL FINAL				0.024	0.051	01-Aug-2008	31-Aug-2008
VA0081281	TP (YEAR-TO-DATE)	05.04	10.50	<u> </u>	0.60		01-Aug-2008	31-Aug-2008
VA0081281	FLOW	25.84	42.52	1	<u> </u>	1	01-Sep-2008	30-Sep-2008
VA0081281	PH			6.9		7.2	01-Sep-2008	30-Sep-2008
VA0081281	BOD5	285	420		3	4	01-Sep-2008	30-Sep-2008
VA0081281	TSS	429	626	<u> </u>	4.3	6.6	01-Sep-2008	30-Sep-2008
VA0081281	COLIFORM, FECAL				2		01-5ep-2008	30-Sep-2008
VA0081281	TP				0.65		01-Sep-2008	30-Sep-2008
VA0081281	ENTEROCOCCI				1		01-Sep-2008	30-Sep-2008
VA0081281	CL2, TOTAL CONTACT			0.19			01-Sep-2008	30-Sep-2008
VA0081281	CL2, TOTAL FINAL_		,		0.054	0.12	01-5ep-2008	30-Sep-2008
VA0081281	TP (YEAR-TO-DATE)				0.60		01-5ep-2008	30-5ep-2008
VA0081281	FLOW	25,00	27.94				01-Oct-2008	31-Oct-2008
VA0081281	PH			6.4		7.2	01-Oct-2008	31-Oct-2008
VA0081281	BOD5	121	207		1	2	01-Oct-2008	31-Oct-2008
VA0081281	T55	240	284		2.5	2.9	01-Oct-2008.	31-Oct-2008
VA0081281	COLIFORM, FECAL				3		01-Oct-2008	31-Oct-2008
VA0081281	TP				0.31		01-Oct-2008	31-Oct-2008
VA0081281	ENTEROCOCCI				1		01-Oct-2008	31-Oct-2008
VA0081281	CL2; TOTAL CONTACT			0,25			01-Oct-2008	31-Oct-2008
VA0081281	CL2, TOTAL FINAL		<u> </u>		0.035	0.049	01-Oct-2008	31-Oct-2008
VA0081281	TP (YEAR-TO-DATE)				0.57		01-Oct-2008	31-Oct-2008
VA0081281	FLOW	27.30	32.87		1	1	01-Nov-2008	30-Nov-2008
VA0081281	PH			6.6	•	7.1	01-Nov-2008	30-Nov-2008
VA0081281	BOD5	394	471		4	5	01-Nov-2008	30-Nov-2008
VA0081281	TSS	456	482		4.3	4.8	01-Nov-2008	30-Nov-2008
VA0081281	COLIFORM, FECAL	130	1702		18	1,0	01-Nov-2008	30-Nov-2008
VA0081281	TP				0.48		01-Nov-2008	30-Nov-2008
VA0081281	ENTEROCOCCI				5		01-Nov-2008	30-Nov-2008
VA0081281	CL2, TOTAL CONTACT	<u> </u>	<u> </u>	0.22	1	1	01-Nov-2008	30-Nov-2008
VA0081281	CL2, TOTAL FINAL			0.22	0.040	0.070	01-Nov-2008	30-Nov-2008
VA0081281					0.57	0.070	01-Nov-2008	30-Nov-2008
	TP (YEAR-TO-DATE)	21 24	40.02		0,57			
VA0081281	FLOW	31.34	48.02			7 2	01-Dec-2008	31-Dec-2008
VA0081281	PH	450	1003	6.6	-	7.3	01-Dec-2008	31-Dec-2008
VA0081281	BOD5	659	902	<u> </u>	6	7	01-Dec-2008	31-Dec-2008
VA0081281	TSS FEET	614	693		5.2	6.0	01-Dec-2008	31-Dec-2008
VA0081281	COLIFORM, FECAL	ļ			11		01-Dec-2008	31-Dec-2008
VA0081281	TP	ļ		+	0.32		01-Dec-2008	31-Dec-2008
VA0081281	ENTEROCOCCI				1		01-Dec-2008	31-Dec-2008
VA0081281	CL2, TOTAL CONTACT		•	0.29			01-Dec-2008	31-Dec-2008
VA0081281	CL2, TOTAL FINAL			<u> </u>	0.023	0.057	01-Dec-2008	31-Dec-2008
VA0081281	TP (YEAR-TO-DATE)				0.55		01-Dec-2008	31-Dec-2008
VA0081281	TP - ANNUAL AVERAGE (MO	, 			0.55		01-Dec-2008	31-Dec-2008
VA0081281	FLOW	28.88	31.48				01-Jan-2009	31-Jan-2009
VA0081281	PH			6.8		7.3	01-Jan-2009	31-Jan-2009
					*			

Permit No學激	Parameter Description -	QTYAVO	3 ≣ <u></u>	X CONCM	IN CONCAV	GHECONEMA	X Stärt Däte	End Date
VA0081281	BOD5	588	662		5	6	01-Jan-2009	31-Jan-2009
VA0081281	TSS .	487	534		4.4	4.8	01-Jan-2009	31-Jan-2009
VA0081281	COLIFORM, FECAL				2		01-Jan-2009	31-Jan-2009
VA0081281	TP				0.28		01-Jan-2009	31-Jan-2009
VA0081281	ENTEROCOCCI				1		01-Jan-2009	31-Jan-2009
VA0081281	CL2, TOTAL CONTACT			0.23			01-Jan-2009	31-Jan-2009
VA0081281	CL2, TOTAL FINAL				√QL	√QL	01-Jan-2009	31-Jan-2009
VA0081281	TP (YEAR-TO-DATE)				0.28		01-Jan-2009	31-Jan-2009
VA0081281	FLOW	27.74	30,52				01-Feb-2009	28-Feb-2009
VA0081281	PH			6.8		7.2	01-Feb-2009	28-Feb-2009
VA0081281	BOD5	798	896		8	9	01-Feb-2009	28-Feb-2009
VA0081281	TSS	765	859		7.3	8.1	01-Feb-2009	28-Feb-2009
VA0081281	COLIFORM, FECAL				6		01-Feb-2009	28-Feb-2009
VA0081281	ТР	· · · · · · · · · · · · · · · · · · ·			0.40		01-Feb-2009	28-Feb-2009
VA0081281	ENTEROCOCCI			,	1		01-Feb-2009	28-Feb-2009
VA0081281	CL2, TOTAL CONTACT	···		0.32	-		01-Feb-2009	28-Feb-2009
VA0081281	CL2, TOTAL FINAL			0.02	0.0036	0.014	01-Feb-2009	28-Feb-2009
VA0081281	TP (YEAR-TO-DATE)				0.34	0.011	01-Feb-2009	28-Feb-2009
VA0081281	FLOW	37.78	50.43		5,5 1		01-Mar-2009	31-Mar-2009
VA0081281	PH	- 37.70	30.13	6.8		7.1	01-Mar-2009	31-Mar-2009
VA0081281	BOD5	1261	2193	0.0	9	15	01-Mar-2009	31-Mar-2009
VA0081281	TSS	1490	3299		10	22	01-Mar-2009	31-Mar-2009
VA0081281	COLIFORM, FECAL	1430	3277		2		01-Mar-2009	31-Mar-2009
VA0081281	TP		<u> </u>		0.51		01-Mar-2009	31-Mar-2009
VA0081281	ENTEROCOCCI				2		01-Mar-2009	31-Mar-2009
VA0081281	CL2, TOTAL CONTACT			0.29	<u> </u>		01-Mar-2009	31-Mar-2009
VA0081281	CL2, TOTAL FINAL			0.29	0.025	0.063	01-Mar-2009	31-Mar-2009
VA0081281	TP (YEAR-TO-DATE)				0.025	0.063	01-Mar-2009	31-Mar-2009
VA0081281	FLOW	33.78	39.09		0.40		01-Apr-2009	30-Apr-2009
VA0081281	PH	33.76	37.07	6.6		7.1	01-Apr-2009	30-Apr-2009
VA0081281	BOD5	1088	1568	0.0	8	13	01-Apr-2009	30-Apr-2009
VA0081281	TSS	906	1367	<u> </u>	7.2	11	01-Apr-2009	30-Apr-2009
VA0081281		906	1307			11	01-Apr-2009	30-Apr-2009
VA0081281	COLIFORM, FECAL				0.49			
VA0081281	ENTEROCOCCI.		<u> </u>				01-Apr-2009	30-Apr-2009
	·			0.13	2		01-Apr-2009	30-Apr-2009
VA0081281	CL2, TOTAL CONTACT	<u> </u>		0.13	0.038	0.050	01-Apr-2009	30-Apr-2009
VA0081281	CL2, TOTAL FINAL				0.028	0.050	01-Apr-2009	30-Apr-2009
VA0081281	TP (YEAR-TO-DATE)	21.70	2(40	- 	0.42	- 	01-Apr-2009	30-Apr-2009
VA0081281	FLOW .	31.70	36.49	4 7		173	01-May-2009	31-May-2009
VA0081281	PH	407	F//	6.7		7.3	01-May-2009	31-May-2009
VA0081281	BOD5	486	566		4	4	01-May-2009	31-May-2009
VA0081281	TSS SECOND SECOND	748	859	-	6.1	6.8	01-May-2009	31-May-2009
VA0081281	COLIFORM, FECAL	·			6		01-May-2009	31-May-2009
VA0081281	TP COCCE				0.34	-	01-May-2009	31-May-2009
VA0081281	ENTEROCOCCI				2		01-May-2009	31-May-2009
VA0081281	CL2, TOTAL CONTACT			0.25	2 2 2 2	0.004	01-May-2009	31-May-2009
VA0081281	CL2, TOTAL FINAL				0.070	0;094	01-May-2009	31-May-2009
VA0081281	TP (YEAR-TO-DATE)	0.4.5.5	40.00		0.40		01-May-2009	31-May-2009
VA0081281	FLOW	34.99	48.28				01-Jun-2009	30-Jun-2009
VA0081281	PH · ·			6.5		7.0	01-Jun-2009	30-Jun-2009
VA0081281	BOD5	487	580		4	4	01-Jun-2009	30-Jun-2009
VA0081281	T55	773	986		6.0	6.8	01-Jun-2009	30-Jun-2009
VA0081281	COLIFORM, FECAL				_ 2		01-Jun-2009	30-Jun-2009
VA0081281	TP				0.66		01-Jun-2009	30-Jun-2009

Permit No.	Parameter Description	₩ ‡ @TYAVO	3/ QTYMA	X CONCM	IN CONCAV	G CONGMA	X Start Date	End:Date
VA0081281	ENTEROCOCCI				1		01-Jun-2009	30-Jun-2009
VA0081281	CL2, TOTAL CONTACT			0.13			01-Jun-2009	30-Jun-2009
VA0081281	CL2, TOTAL FINAL				0.11	0.12	01-Jun-2009	30-Jun-2009
VA0081281	TP (YEAR-TO-DATE)				0.45		01-Jun-2009	30-Jun-2009
VA0081281	FLOW	28.03	30.93				01-Jul-2009	31-Jul-2009
VA0081281	PH	1.0.00		6.9		7.1	01-Jul-2009	31-Jul-2009
VA0081281	BOD5	266	337	0.5	3	3	01-Jul-2009	31-Jul-2009
VA0081281	TSS	444	468		4.2	4.4	01-Jul-2009	31-Jul-2009
VA0081281	COLIFORM, FECAL	1111	100		10	7.4	01-Jul-2009	31-Jul-2009
VA0081281	TP				0.35		01-Jul-2009	31-Jul-2009
VA0081281	ENTEROCOCCI				2		01-Jul-2009	31-Jul-2009
VA0081281	CL2, TOTAL CONTACT			0.30	١٤		01-Jul-2009	31-Jul-2009
		·		0.30	0.043	0.051		31-Jul-2009
VA0081281	CL2, TOTAL FINAL	-				0.051	01-Jul-2009	
VA0081281	TP (YEAR-TO-DATE)	122 (2	F4.50		0.43		01-Jul-2009	31-Jul-2009
VA0081281	FLOW	33.63	54.59				01-Aug-2009	31-Aug-2009
VA0081281	PH '		<u> </u>	6.6		7.1	01-Aug-2009	31-Aug-2009
VA0081281	BOD5	260	557		2	3	01-Aug-2009	31-Aug-2009
VA0081281	TSS	476 ·	758		3.5	4.8	01-Aug-2009	31-Aug-2009
VA0081281	COLIFORM, FECAL				9		01-Aug-2009	31-Aug-2009
VA0081281	TP				0.29		01-Aug-2009	31-Aug-2009
VA0081281	ENTEROCOCCI		<u>' </u>		1		01-Aug-2009	31-Aug-2009
VA0081281	CL2, TOTAL CONTACT			0.27			01-Aug-2009	31-Aug-2009
VA0081281	CL2, TOTAL FINAL	·			0.045	0.070	01-Aug-2009	31-Aug-2009
VA0081281	TP (YEAR-TO-DATE)				0.41		01-Aug-2009	31-Aug-2009
VA0081281	FLOW	36.43	63.73		٠.		01-Sep-2009	30-5ep-2009
VA0081281	PH	·		6.6		7.1	01-Sep-2009	30-Sep-2009
VA0081281	BOD5	590	1083		4	5	01-Sep-2009	30-Sep-2009
VA0081281	TSS	1038	1975		6.8	9.5	01-5ep-2009	30-Sep-2009
VA0081281	COLIFORM, FECAL				9		01-Sep-2009	30-Sep-2009
VA0081281	TP				0.68		01-Sep-2009	30-5ep-2009
VA0081281	ENTEROCOCCI			- '	2		01-Sep-2009	30-Sep-2009
VA0081281	CL2, TOTAL CONTACT			0.30			01-Sep-2009	30-Sep-2009
VA0081281	CL2, TOTAL FINAL	i			0.078	0.12	01-Sep-2009	30-Sep-2009
VA0081281	TP (YEAR-TO-DATE)				0.44		01-Sep-2009	30-Sep-2009
VA0081281	FLOW	29.51	35.71				01-Oct-2009	31-Oct-2009
VA0081281	PH			6.8		7.0	01-Oct-2009	31-Oct-2009
VA0081281	BOD5	260	328		2 -	3	01-Oct-2009	31-Oct-2009
VA0081281	TSS	452	586		4.0	5.0	01-Oct-2009	31-Oct-2009
VA0081281	COLIFORM, FECAL		-		2		01-Oct-2009	31-Oct-2009
VA0081281	TP				0.17		01-Oct-2009	31-Oct-2009
VA0081281	ENTEROCOCCI				1		01-Oct-2009	31-Oct-2009
VA0081281	CL2, TOTAL CONTACT		_	0.32			01-Oct-2009	31-Oct-2009
VA0081281	CL2, TOTAL FINAL				0.047	0.086	01-Oct-2009	31-Oct-2009
VA0081281	TP (YEAR-TO-DATE)				0.42		01-Oct-2009	31-Oct-2009
VA0081281	FLOW	43.96	91.60				01-Nov-2009	30-Nov-2009
VA0081281	PH			6.4		7.0 ·	01-Nov-2009	30-Nov-2009
VA0081281	BOD5	844	1400		4	6	01-Nov-2009	30-Nov-2009
VA0081281	TSS	999	2351		5.0	9.5	01-Nov-2009	30-Nov-2009
VA0081281	COLIFORM, FECAL			•	9		01-Nov-2009	30-Nov-2009
VA0081281	TP		<u> </u>		0.21	,	01-Nov-2009	30-Nov-2009
VA0081281	ENTEROCOCCI	_	<u> </u>		1		01-Nov-2009	30-Nov-2009
VA0081281	CL2, TOTAL CONTACT			0.34			01-Nov-2009	30-Nov-2009
VA0081281	CL2, TOTAL FINAL			10.01	0.083	0.19	01-Nov-2009	30-Nov-2009
VA0081281	TP (YEAR-TO-DATE)		,		0.40	J	01-Nov-2009	30-Nov-2009
17.10001201	I (reak-to-batte)				[0.10		107 1404-2009	100 1404 2007

.

Permit No.	Rarameter Description	[QTYAVG	XAMYTO	CONCMIN	GONCAVG	CONCMAX	Start Date	S End Date
VA0081281	FLOW	46.88	66.88				01-Dec-2009	31-Dec-2009
VA0081281	РН			6.1		7.0	01-Dec-2009	31-Dec-2009
VA0081281	BOD5	1020	944	1	6	5	01-Dec-2009	31-Dec-2009
VA0081281	TSS	870	883		5.0	4.7	01-Dec-2009	31-Dec-2009
VA0081281	COLIFORM, FECAL	1	1		4	1	01-Dec-2009	31-Dec-2009
VA0081281	TP	<u> </u>	<u> </u>		0.14	 	01-Dec-2009	31-Dec-2009
VA0081281	ENTEROCOCCI	 			1 :		01-Dec-2009	31-Dec-2009
VA0081281	CL2, TOTAL CONTACT		 	0.32	+		01-Dec-2009	31-Dec-2009
VA0081281	CL2, TOTAL FINAL	 		0.32	0.078	0.13		31-Dec-2009
VA0081281 VA0081281	\ 					0.13	01-Dec-2009	31-Dec-2009
	TP (YEAR-TO-DATE)	 	0.405(446	<u> </u>	0.38		01-Dec-2009	
VA0081281	PHOSPHORUS, TOTAL - AN			(L) T	0.38		01-Jan-2009	31-Dec-2009
VA0081281	FLOW	37.91	50.44		<u> </u>		01-Jan-2010	31-Jan-2010
VA0081281	PH	1	 	6.1	1	7.0	01-Jan-2010	31-Jan-2010
VA0081281	BOD5	1419	2284	<u>.</u>	10	13	01-Jan-2010	31-Jan-2010
VA0081281	TSS	1137	1623		7.7	10	01-Jan-2010	31-Jan-2010
VA0081281	COLIFORM, FECAL	<u> </u>			2		01-Jan-2010	31-Jan-2010
VA0081281	TP				0.36		01-Jan-2010	31-Jan-2010
VA0081281	ENTEROCOCCI				2		01-Jan-2010	31-Jan-2010 -
VA0081281	CL2, TOTAL CONTACT	,		0.23			01-Jan-2010	31-Jan-2010
VA0081281	CL2, TOTAL FINAL	<u> </u>			0.030	0.046	01-Jan-2010	31-Jan-2010
VA0081281	TP (YEAR-TO-DATE)				0.36		01-Jan-2010	31-Jan-2010
VA0081281	FLOW	44.42	81.32	,			01-Feb-2010	28-Feb-2010
VA00B1281	РН			6.2		7.0	01-Feb-2010	28-Feb-2010
VA0081281	BOD5	1956	2134		12	15	01-Feb-2010	28-Feb-2010
VA0081281	TSS	1332	1513		8.1	9.9	01-Feb-2010	28-Feb-2010
VA0081281	COLIFORM, FECAL			7	4	1	01-Feb-2010	28-Feb-2010
VA0081281	TP				0.30		01-Feb-2010	28-Feb-2010
VA0081281	ENTEROCOCCI				6		01-Feb-2010	28-Feb-2010
VA0081281	CL2, TOTAL CONTACT			0.23			01-Feb-2010	28-Feb-2010
VA0081281	CL2, TOTAL FINAL	 	-		0.023	0.019	01-Feb-2010	28-Feb-2010
VA0081281	TP (YEAR-TO-DATE)	<u> </u>	:.		0.33		01-Feb-2010	28-Feb-2010
VA0081281	FLOW	39.31	63.60		0.00		01-Mar-2010	31-Mar-2010
VA0081281	PH	1	00.00	6.3	 	7.0	01-Mar-2010	31-Mar-2010
VA0081281	BOD5	1594	1300	0.5	10	9	01-Mar-2010	31-Mar-2010
VA0081281	TSS	785	839		5.0	6.2	01-Mar-2010	31-Mar-2010
VA0081281	COLIFORM, FECAL	1703	039		3	0.2	01-Mar-2010	31-Mar-2010
VA0081281	TP				0.22		01-Mar-2010	31-Mar-2010
VA0081281					2		01-Mar-2010	31-Mar-2010
VA0081281	ENTEROCOCCI	[0.34	2	1		31-Mar-2010
VA0081281	CL2, TOTAL CONTACT			0.34	0.030	0.017	01-Mar-2010	
	CL2, TOTAL FINAL	-		-	0.029	0.017	01-Mar-2010	31-Mar-2010
VA0081281	TP (YEAR-TO-DATE)	120 50	144 = 2		0.29		01-Mar-2010	31-Mar-2010
VA0081281	FLOW	32.59	44.73			17.0	01-Apr-2010	30-Apr-2010
VA0081281	PH	 		6.5		7.0	01-Apr-2010	30-Apr-2010
VA0081281	BOD5	312	410		2	3	01-Apr-2010	30-Apr-2010
VA0081281	TSS	426	405		3.5	3.0	01-Apr-2010	30-Apr-2010
VA0081281	COLIFORM, FECAL	<u> </u>			2		01-Apr-2010	30-Apr-2010
VA0081281	TP				0.56		01-Apr-2010	30-Apr-2010
VA0081281	ENTEROCOCCI				1	<u> </u>	01-Apr-2010	30-Apr-2010
VA0081281	CL2, TOTAL CONTACT			0.31			01-Apr-2010	30-Apr-2010
VA0081281	CL2, TOTAL FINAL				0.026	0.067	01-Apr-2010	30-Apr-2010
VA0081281	TP (YEAR-TO-DATE)				0.36		01-Apr-2010	30-Apr-2010
VA0081281	FLOW	29.33	46.90				01-May-2010	31-May-2010
VA0081281	PH			6.3		6.9	01-May-2010	31-May-2010
VA0081281	BOD5	438	633		4	6	01-May-2010	31-May-2010
			<u> </u>	····				

Permit No #	Rarameter Description	* FOTYAVO	STYMA	X#I#CONCM	IN-L'CONCAV	G CONCMA	X Start Date.	End Date
VA0081281	TSS	642	914		5.7	8.7	01-May-2010	31-May-2010
VA0081281	COLIFORM, FECAL			<u> </u>	4		01-May-2010	31-May-2010
VA0081281	TP		 		0.44		01-May-2010	31-May-2010
VA0081281	ENTEROCOCCI				1		01-May-2010	31-May-2010
VA0081281	CL2, TOTAL CONTACT			0.33	-		01-May-2010	31-May-2010
VA0081281	CL2, TOTAL FINAL	•		0.33	0.011	0.033	01-May-2010	31-May-2010
VA0081281	TP (YEAR-TO-DATE)				0.011	0.033	01-May-2010	31-May-2010
VA0081281	FLOW	26.76	28.64		0.37		01-Jun-2010	30-Jun-2010
VA0081281	PH	20.70	20.04	6.5		7.0	01-Jun-2010	30-Jun-2010
VA0081281	BOD5	256	482	6.5		5		30-Jun-2010
					2		01-Jun-2010	
VA0081281	TSS FSCAL	541	755		5.2	7.2	01-Jun-2010	30-Jun-2010
VA0081281	COLIFORM, FECAL				6		01-Jun-2010	30-Jun-2010
VA0081281	TP				0.41		01-Jun-2010	30-Jun-2010
VA0081281	ENTEROCOCCI				1	_	01-Jun-2010	30-Jun-2010
VA0081281	CL2, TOTAL CONTACT			0.27			01-Jun-2010	30-Jun-2010
VA0081281	CL2, TOTAL FINAL				0.0067	0.014	01-Jun-2010	30-Jun-2010
VA0081281	TP (YEAR-TO-DATE)				0.38		01-Jun-2010	30-Jun-2010
VA0081281	FLOW	23.66	29.94				01-Jul-2010	31-Jul-2010
VA0081281	PH			6.7		7.1	01-Jul-2010	31-Jul-2010
VA0081281	BOD5	107	150		1	2	01-Jul-2010	31-Jul-2010
VA0081281	TSS	243	256		2.7	2.8	01-Jul-2010	31-Jul-2010
VA0081281	COLIFORM, FECAL				6		01-Jul-2010	31-Jul-2010
VA0081281	TP			•	0.34		01-Jul-2010	31-Jul-2010
VA0081281	ENTEROCOCCI				1		01-Jul-2010	31-Jul-2010
VA0081281	CL2, TOTAL CONTACT			0.22			01-Jul-2010	31-Jul-2010
VA0081281	CL2, TOTAL FINAL				0.010	0.016	01-Jul-2010	31-Jul-2010
VA0081281	TP (YEAR-TO-DATE)				0.37		01-Jul-2010	31-Jul-2010
VA0081281	FLOW	24,80	27,70				01-Aug-2010	31-Aug-2010
VA0081281	PH			6.8		7.1	01-Aug-2010	31-Aug-2010
VA0081281	BOD5	√QL	√QL		√QL	√QL	01-Aug-2010	31-Aug-2010
VA0081281	TSS	191	238		2.0	2.5	01-Aug-2010	31-Aug-2010
VA0081281	COLIFORM, FECAL				4		01-Aug-2010	31-Aug-2010
VA0081281	TP			-	0.26		01-Aug-2010	31-Aug-2010
VA0081281	ENTEROCOCCI			1	1		01-Aug-2010	31-Aug-2010
VA0081281	CL2, TOTAL CONTACT	· ·		0.24			01-Aug-2010	31-Aug-2010
VA0081281	CL2, TOTAL FINAL			U.L.T	0.0097	0.043	01-Aug-2010	31-Aug-2010
VA0081281	TP (YEAR-TO-DATE)			<u> </u>	0.36	0.043	01-Aug-2010	31-Aug-2010
VA0081281	FLOW	25.33	72.43		0.30		01-Sep-2010	30-Sep-2010
VA0081281	PH	25.55	72.43	6.7		7.2	01-Sep-2010	30-Sep-2010
VA0081281	BOD5	131	1.01	0.7	0			30-Sep-2010
	 		√QL			2.7	01-Sep-2010	
VA0081281	TSS	349	233		2.7	_ 2./	01-Sep-2010	30-Sep-2010
VA0081281	COLIFORM, FECAL		_	<u> </u>	2		01-Sep-2010	30-5ep-2010
VA0081281	TP				0.37		01-Sep-2010	30-Sep-2010
VA0081281	ENTEROCOCCI	<u> </u>			2		01-Sep-2010	30-Sep-2010
VA0081281	CL2, TOTAL CONTACT			0.25			01-Sep-2010	30-Sep-2010
VA0081281	CL2, TOTAL FINAL				0.026	0.059	01-Sep-2010	30-Sep-2010
VA0081281	TP (YEAR-TO-DATE)		<u> </u>		0.36		01-5ep-2010	30-Sep-2010
VA0081281	FLOW	36.48	81.98				01-Oct-2010	31-Oct-2010
VA0081281	PH			6.3		7.0	01-Oct-2010	31-Oct-2010
VA0081281	BOD5	176	329		1	3	01-Oct-2010	31-Oct-2010
VA0081281	TSS	470	725		3.6	4.8	01-Oct-2010	31-Oct-2010
VA0081281	COLIFORM, FECAL				3		01-Oct-2010	31-Oct-2010
VA0081281	TP				0.21		01-Oct-2010	31-Oct-2010
VA0081281	ENTEROCOCCI				1		01-Oct-2010	31-Oct-2010
	7.00			-		-	•	

Permit No	Parameter Description	OTYAVO	G QTYMA	x*I:concm	IN CONCAV	G CONCMA	XI Start Date	End Date
VA0081281	CL2, TOTAL CONTACT			0.31	THE THE THE PARTY SHOWN AND ADDRESS OF THE PARTY SHOWN AND ADD		01-Oct-2010	31-Oct-2010
VA0081281	CL2, TOTAL FINAL				0.040	0.066	01-Oct-2010	31-Oct-2010
VA0081281	TP (YEAR-TO-DATE)		 - -	1	0.35		01-Oct-2010	31-Oct-2010
VA0081281	FLOW	27.54	30.99				01-Nov-2010	30-Nov-2010
VA0081281	PH			6.6		6.9	01-Nov-2010	30-Nov-2010
VA0081281	BOD5	221	327	-	2	3	01-Nov-2010	30-Nov-2010
VA0081281	TSS	471	558		4.5	5.1	01-Nov-2010	30-Nov-2010
VA0081281	COLIFORM, FECAL	***************************************			4		01-Nov-2010	30-Nov-2010
VA0081281	TP		_	1	0.42	- 	01-Nov-2010	30-Nov-2010
VA0081281	ENTEROCOCCI				1		01-Nov-2010	30-Nov-2010
VA0081281	CL2, TOTAL CONTACT			0.36			01-Nov-2010	30-Nov-2010
VA0081281	CL2, TOTAL FINAL				0.033	0.030	01-Nov-2010	30-Nov-2010
VA0081281	TP (YEAR-TO-DATE)				0.35	10.000	01-Nov-2010	30-Nov-2010
VA0081281	FLOW	26.55	28.59		0.00		01-Dec-2010	31-Dec-2010
VA0081281	PH	40.00	20.07	6.3		6.9	01-Dec-2010	31-Dec-2010
VA0081281	BOD5	617	878	 	6	8	01-Dec-2010	31-Dec-2010
VA0081281	TSS	753	911		7.4	8.7	01-Dec-2010	31-Dec-2010
VA0081281	COLIFORM, FECAL	1.00			6		01-Dec-2010	31-Dec-2010
VA0081281	TP	1			0.46		01-Dec-2010	31-Dec-2010
VA0081281	ENTEROCOCCI				2		01-Dec-2010	31-Dec-2010
VA0081281	CL2, TOTAL CONTACT		 	0.35			01-Dec-2010	31-Dec-2010
VA0081281	CL2, TOTAL FINAL		-	10.55	0.014	0.017	01-Dec-2010	31-Dec-2010
VA0081281	TP (YEAR-TO-DATE)				0.36	0.017	01-Dec-2010	31-Dec-2010
VA0081281	TP - ANNUAL AVERAGE (N	16/1)		+	0.36	-	01-Jan-2010	31-Dec-2010
VA0081281	FLOW	31,38	44.67		- 0.30		01-Jan-2011	31-Jan-2011
VA0081281	PH	31,36	17.07	6.2		6.9	01-Jan-2011	31-Jan-2011
VA0081281	BOD5	849	1508	0.2	7	12	01-Jan-2011	31-Jan-2011
VA0081281	T55	1056	1903		8.7	15	01-Jun-2011	31-Jan-2011
VA0081281	COLIFORM, FECAL	1030	1903	1	24	15	01-Jan-2011	31-Jan-2011
VA0081281	TP			+	0.35	_	01-Jan-2011	31-Jan-2011
VA0081281	ENTEROCOCCI				4		01-Jan-2011	31-Jan-2011
VA0081281	CL2, TOTAL CONTACT			0.38	T		01-Jan-2011	31-Jan-2011
VA0081281	CL2, TOTAL FINAL		- 	- 10.30	0.0032	0.014	01-Jan-2011	31-Jan-2011
VA0081281	TP (YEAR-TO-DATE)				0.35	0.014	01-Jan-2011	31-Jan-2011
VA0081281	FLOW .	31.59	35.92		0.55		01-Feb-2011	28-Feb-2011
VA0081281	PH	31,39	33.72	6.3		6.8	01-Feb-2011	28-Feb-2011
VA0081281	BOD5	603	721		5	6	01-Feb-2011	28-Feb-2011
VA0081281	T55	727	858		6.1	6.5	01-Feb-2011	28-Feb-2011
VA0081281	COLIFORM, FECAL	1/6/	1030		4	- 10.5	01-Feb-2011	28-Feb-2011
VA0081281	TP				0.36	•	01-Feb-2011	28-Feb-2011
VA0081281	ENTEROCOCCI				1		01-Feb-2011	28-Feb-2011
VA0081281	CL2, TOTAL CONTACT			0.31			01-Feb-2011	28-Feb-2011
VA0081281	CL2, TOTAL FINAL			- 0.31	0.042	0.060	01-Feb-2011	28-Feb-2011
VA0081281					0.35	0.000	01-Feb-2011	28-Feb-2011
VA0081281	TP (YEAR-TO-DATE) FLOW	30.99	37.71	_	0.35		01-Peb-2011 01-Mar-2011	31-Mar-2011
VA0081281	PH PH	30.55	37./1	6.3	- 	6.9	01-Mar-2011	31-Mar-2011
VA0081281	BOD5	289	413	10.3	2	3	01-Mar-2011	31-Mar-2011
VA0081281	TSS	489	663		4.1	5.4	01-Mar-2011	31-Mar-2011
VA0081281	COLIFORM, FECAL	1709	1003		2		01-Mar-2011	31-Mar-2011
VA0081281	TP				0.18		01-Mar-2011	31-Mar-2011
VA0081281	ENTEROCOCCI			_	1	_	01-Mar-2011	31-Mar-2011
VA0081281		-	+	0.37	<u> </u>		01-Mar-2011	31-Mar-2011
VA0081281	CL2, TOTAL CONTACT		 :	0.37	0.033	0.047	01-Mar-2011	31-Mar-2011
VA0081281	 				0.29	0.047	01-Mar-2011	31-Mar-2011
AVOODIEDI	TP (YEAR-TO-DATE)		-		10.47		101-Mai 25011	121-Mai -2011

Permit No.	Parameter Description	QTYAVG	OTYMAX	CONCMI	N CONCAVO	CONGMA	Start Date	End Date
VA0081281	FLOW	29.24	34.59	2.00 BM			01-Apr-2011	30-Apr-2011
VA0081281	PH			6.3		6.9	01-Apr-2011	30-Apr-2011
VA0081281	BOD5	347	468	10.0	3	4	01-Apr-2011	30-Apr-2011
VA0081281	TSS	480	641		4.4	6.0	01-Apr-2011	30-Apr-2011
VA0081281	COLIFORM, FECAL	1.00	1011		4	10.0	01-Apr-2011	30-Apr-2011
VA0081281	TP			 	0.25	-	01-Apr-2011	30-Apr-2011
VA0081281	ENTEROCOCCI			<u> </u>	2		01-Apr-2011	30-Apr-2011
VA0081281	CL2, TOTAL CONTACT			0,28	2		01-Apr-2011	<u> </u>
VA0081281	CL2, TOTAL CONTACT			0.28	0.042	0.054		30-Apr-2011
					0.042	0.054	01-Apr-2011	30-Apr-2011
VA0081281	TP (YEAR-TO-DATE)	24.00	0045		0.28		01-Apr-2011	30-Apr-2011
VA0081281	FLOW	26.08	28.15	1			01-May-2011	31-May-2011
VA0081281	PH			6.3		6.9	01-May-2011	31-May-2011
VA0081281	BOD5	200	339		2	3	01-May-2011	31-May-2011
VA0081281	TSS	432	551		4.3	5.5	01-May-2011	31-May-2011
VA0081281	COLIFORM, FECAL				7		01-May-2011	31-May-2011
VA0081281	TP				0.35		01-May-2011	31-May-2011
VA0081281	ENTEROCOCCI				4		01-May-2011	31-May-2011
VA0081281	CL2, TOTAL CONTACT			0.35			01-May-2011	31-May-2011
VA0081281	CL2, TOTAL FINAL				0.057	0.11	01-May-2011	31-May-2011
VA0081281	TP (YEAR-TO-DATE)				0.30		01-May-2011	31-May-2011
VA0081281	FLOW	26.17	31.94				01-Jun-2011	30-Jun-2011
VA0081281	PH .			6.5		7.2	01-Jun-2011	30-Jun-2011
VA0081281	BOD5	150	321		1	3	01-Jun-2011	30-Jun-2011
VA0081281	TSS	519	691		5.2	6.5	01-Jun-2011	30-Jun-2011
VA0081281	COLIFORM, FECAL				20		01-Jun-2011	30-Jun-2011 .
VA0081281	TP				1.1		01-Jun-2011	30-Jun-2011
VA0081281	ENTEROCOCCI				1		01-Jun-2011	30-Jun-2011
VA0081281	CL2, TOTAL CONTACT			0.27			01-Jun-2011	30-Jun-2011
VA0081281	CL2, TOTAL FINAL	<u> </u>		10.00	0.058	0.080	01-Jun-2011	30-Jun-2011
VA0081281	TP (YEAR-TO-DATE)	<u> </u>	-		0.44	0.303	01-Jun-2011	30-Jun-2011
VA0081281	FLOW	26.10	29.52	 			01-Jul-2011	31-Jul-2011
VA0081281	PH	-0.10	1-7.0-	6.5		7.1	01-Jul-2011	31-Jul-2011
VA0081281	BOD5	95	205	10.0	1	2	01-Jul-2011	31-Jul-2011
VA0081281	TSS	372	448		3.8	4.5	01-Jul-2011	31-Jul-2011
VA0081281	COLIFORM, FECAL	372	1770		8	17.5	01-Jul-2011	31-Jul-2011
VA0081281	TP .				1.8		01-Jul-2011	31-Jul-2011
		<u></u>						
VA0081281 VA0081281	ENTEROCOCCI	1			2		01-Jul-2011	31-Jul-2011
	CL2, TOTAL CONTACT			0.30	0.043	0.074	01-Jul-2011	31-Jul-2011
VA0081281	CL2, TOTAL FINAL				0.063	0.071	01-Jul-2011	31-Jul-2011
VA0081281	TP (YEAR-TO-DATE)	00.71	45.04		0.64		01-Jul-2011	31-Jul-2011
VA0081281	FLOW	29.76	65.34	 	····	 	01-Aug-2011	31-Aug-2011
VA0081281	PH	1	1	6.5		7.5	01-Aug-2011	31-Aug-2011
VA0081281	BOD5	71	183		- 1	2	01-Aug-2011	31-Aug-2011
VA0081281	TSS	347	417	<u> </u>	3.3	4.1	01-Aug-2011	31-Aug-2011
VA0081281	COLIFORM, FECAL			<u> </u>	5		01-Aug-2011	31-Aug-2011
VA0081281	TP	<u> </u>			1.8		01-Aug-2011	31-Aug-2011
VA0081281	ENTEROCOCCI	<u> </u>			1	1	01-Aug-2011	31-Aug-2011
VA0081281	CL2, TOTAL CONTACT			0.090			01-Aug-2011	31-Aug-2011
VA0081281	CL2, TOTAL FINAL				0.065	0.080	01-Aug-2011	31-Aug-2011
VA0081281	TP (YEAR-TO-DATE)				0.79		01-Aug-2011	31-Aug-2011
VA0081281	FLOW	36.89	59.14				01-Sep-2011	30-Sep-2011
VA0081281	PH			6.4		7.0	01-5ep-2011	30-Sep-2011
VA0081281	BOD5	190	339	1	1	2	01-5ep-2011	30-Sep-2011
VA0081281	TSS	562	741		4.1	5.3	01-Sep-2011	30-Sep-2011
•			<u> </u>				• • • • • • • • • • • • • • • • • • • •	· · · · · · · · · · · · · · · · · · ·

Permit No No	Rarameter Description:	VQTYAVG	QTYMAX	CONCMIN	ECONCAVO	CONCMAX	Start Date	End Date
VA0081281	COLIFORM, FECAL				7		01-Sep-2011	30-Sep-2011
VA0081281	ТР				0.44		01-5ep-2011	30-5ep-2011
VA0081281	ENTEROCOCCI			1	2		01-Sep-2011	30-5ep-2011
VA0081281	CL2, TOTAL CONTACT			0.21	,		01-Sep-2011	30-Sep-2011
VA0081281	CL2, TOTAL FINAL				0.098	0.13	01-Sep-2011	30-Sep-2011
VA0081281	TP (YEAR-TO-DATE)		-		0.75		01-Sep-2011	30-Sep-2011
VA0081281	FLOW	30.08	36.35			-	01-Oct-2011	31-Oct-2011
VA0081281	PH		100.00	6.4		7.0	01-Oct-2011	31-Oct-2011
VA0081281	BOD5	281	351		2	3	01-Oct-2011	31-Oct-2011
VA0081281	TSS	648	749	_	5.7	6.0	01-Oct-2011	31-Oct-2011
VA0081281	COLIFORM, FECAL	-	1,12		9		01-Oct-2011	31-Oct-2011
VA0081281	TP			1	0.42		01-Oct-2011	31-Oct-2011
VA0081281	ENTEROCOCCI				1		01-Oct-2011	31-Oct-2011
VA0081281	CL2, TOTAL CONTACT	***		0.25	<u> </u>		01-Oct-2011	31-Oct-2011
VA0081281	CL2, TOTAL FINAL		 	10.25	0.081	0,12	01-Oct-2011	31-Oct-2011
VA0081281	TP (YEAR-TO-DATE)				0.72	Ų,1E	01-Oct-2011	31-Oct-2011
VA0081281	FLOW	27.37	31.92	<u> </u>	0.72		01-Nov-2011	30-Nov-2011
VA0081281	PH	27.37	31.96	6.4		6.9	01-Nov-2011	30-Nov-2011
VA0081281	BOD5	375	402	10.4	4		01-Nov-2011	30-Nov-2011
VA0081281	TSS	697	851	<u></u>	6.6	8.2	01-Nov-2011 01-Nov-2011	30-Nov-2011
VA0081281		097	1931	 	12	0.2		+
	COLIFORM, FECAL						01-Nov-2011	30-Nov-2011
VA0081281	TP		 	<u> </u>	0.46		01-Nov-2011	30-Nov-2011
VA0081281	ENTEROCOCCI		<u> </u>	1	2	<u> </u>	01-Nov-2011	30-Nov-2011
VA0081281	CL2, TOTAL CONTACT			0.28	0.40	0.45	01-Nov-2011	30-Nov-2011
VA0081281	CL2, TOTAL FINAL				0.10	0.15	01-Nov-2011	30-Nov-2011
VA0081281	TP (YEAR-TO-DATE)		·	-	0.69		01-Nov-2011	30-Nov-2011
VA0081281	FLOW	26.27	27.35				01-Dec-2011	31-Dec-2011
VA0081281	PH	•		6.2		7.0	01-Dec-2011	31-Dec-2011
VA0081281	BOD5	381	494	<u> </u>	4	5	01-Dec-2011	31-Dec-2011
VA0081281	TSS	710	1062		7.1	11	01-Dec-2011	31-Dec-2011
VA0081281	COLIFORM, FECAL			<u> </u>	3		01-Dec-2011	31-Dec-2011
VA0081281	TP				0.53		01-Dec-2011	31-Dec-2011
VA0081281	ENTEROCOCCI				4		01-Dec-2011	31-Dec-2011
VA0081281	CL2, TOTAL CONTACT	<u> </u>		0.20		ļ	01-Dec-2011	31-Dec-2011
VA0081281	CL2, TOTAL FINAL				0.094	0.11	01-Dec-2011	31-Dec-2011
VA0081281	TP (YEAR-TO-DATE)				0.68		01-Dec-2011	31-Dec-2011
VA0081281	TP - ANNUAL AVERAGE (ME				0.68		01-Jan-2011	31-Dec-2011
VA0081281	FLOW	26.25	28.67				01-Jan-2012	31-Jan-2012
VA0081281	PH :			6.3	·	7.0	01-Jan-2012	31-Jan-2012
VA0081281	BOD5	402	502		4	5	01-Jan-2012	31-Jan-2012
VA0081281	TSS	674	820		6.8	8.2	01-Jan-2012	31-Jan-2012
VA0081281	COLIFORM, FECAL				2		01-Jan-2012	31-Jan-2012
VA0081281	TP .			<u></u>	0.34		01-Jan-2012	31-Jan-2012
VA0081281	ENTEROCOCCI	<u> </u>			3	<u> </u>	01-Jan-2012	31-Jan-2012
VA0081281	CL2, TOTAL CONTACT			0.30			01-Jan-2012	31-Jan-2012
VA0081281	CL2, TOTAL FINAL				0.094	0.11	01-Jan-2012	31-Jan-2012
VA0081281	TP (YEAR-TO-DATE)				0.34		01-Jan-2012	31-Jan-2012
VA0081281	FLOW	30.14	36.93				01-Feb-2012	29-Feb-2012
VA0081281	PH			6.3		7,0	01-Feb-2012	29-Feb-2012
VA0081281	BOD5	879	1365		7	11	01-Feb-2012	29-Feb-2012
VA0081281	TSS	1172	1809		10	14	01-Feb-2012	29-Feb-2012
VA0081281	COLIFORM, FECAL				3		01-Feb-2012	29-Feb-2012
VA0081281	TP				0.70		01-Feb-2012	29-Feb-2012
VA0081281	ENTEROCOCCI				4		01-Feb-2012	29-Feb-2012
				· · · · · · · · · · · · · · · · · · ·				

Permit No	将 Parameter Description	 ZOTYAVG⊪	EQTYMAX	CONCMIN	CONCAVG:	∦CONCMAX	Start Date	End Date End Date
VA0081281	CL2, TOTAL CONTACT			0.22			01-Feb-2012	29-Feb-2012
VA0081281	CL2, TOTAL FINAL				0.065	0.080	01-Feb-2012	29-Feb-2012
VA0081281	TP (YEAR-TO-DATE)				0.52		01-Feb-2012	29-Feb-2012

Pilled from discoverer 4/3/12. DDA

SALTWATER AND TRANSITION ZONES WATER QUALITY CRITERIA / WASTELOAD ALLOCATION ANALYSIS

Facility Name: Receiving Stream:

Mean Salinity =

Permit No.: VA0081281

Version: OWP Guidance Memo 00-2011 (8/24/00)

HRSD VIP STP

20.47 (g/kg)

Stream Information	<u> </u>	Mixing Information		Effluent Information	
Mean Hardness (as CaCO3) =	100 mg/t	Design Flow (MGD)	40.	Mean Hardness (as CaCO3) =	168 mg/L
90th % Temperature (Annual) =	25.97 (° C)	Acute WLA multiplier	41 5	90 % Temperature (Annual) =	(° C)
90th % Temperature (Winter) =	(°C)	Chronic WLA multiplier	113.	90 % Temperature (Winter) =	22 (° C)
90th % Maximum pH =	8.06	Human health WLA multiplier	113	90 % Maximum pH =	7.2 SU
10th % Maximum pH =	7.5			10 % Maximum pH =	6.3 SU
Tier Designation (1 or 2) =	1			Discharge Flow =	40 MGD
Early Life Stages Present Y/N =	Y.				
Tidal Zone =	(1 = saltwater, 2 = transition	zone)		•	

Parameter	Background	Wate	er Quality C	riteria	Wast	eload Alloca	itions	Antide	gradation Bas	eline	Antideg	radation Allo	cations	Most Li	miting Alloc	ations
(ug/I unless noted)	Conc.	Acute	Chronic	HH	Acute	Chronic	нн 🛴	Acute	Chronic	НН	Acute	Chronic	HH	Acute	Chronic	нн
Acenapthene	0	-		9.9E+02	_		1.1E+05						-			1.1E+05
Acrolein			-	9.3E+00	-		1.1E+03								••	1.1E+03
Acrylonitrile ^C				2.5E+00	- :	-	2.8E+02				-	_		-		2.8E+02
Aldrin ^C	0	1.3E+00		5.0E-04	5.3E+01	`	5.7E-02			_	-	_		5.3E+01		5.7E-02
Ammonia-N (mg/l) - Annual	4-40-0 Yes (200)	3.94E+00	5.30E-01	-	1.62E+02	5.99E+01		_	-	. –				1.62E+02	5.99E+01	
Ammonia-N (mg/l) - Winter	0	2.40E+01	3.40E+00	_	9.86E+02	3.84E+02	-			- ·		-		9.86E+02	3.84E+02	-
Anthracene	07.5	-		4.0E+04	-		4.5E+06	·		-				-	-	4.5E+06
Antimony)13.7.0	-		6.4E+02	_		7.2E+04			-		-		-		7.2E+04
Arsenic	(Ö)	6.9E+01	3.6E+01	_	'2.8E+03	4.1E+03	_		,-	. –			.	2.8E+03	4.1E+03	-
Benzene ^c	-0**		_	5.1E+02	-	-	5.8E+04	-	-	-	-	-	-	-	-	5.8E+04
Benzidine ^c				2.0E-03	-		2.3E-01	 '		-		-		-		2.3E-01
Benzo (a) anthracene ^c	0	_	_	1.8E-01	-		2.0E+01				-	_	_	-	 , '	2.0E+01
Benzo (b) fluoranthene ^C	7 0 2		·	1.8E-01	_		2.0E+01		-			-	-		-	2.0E+01
Benzo (k) fluoranthene ^c	0 -			1.8E-01			2.0E+01	_	- '	_			<u>.</u>			2.0E+01
Benzo (a) pyrene ^c	. 0			1.8E-01			2.0E+01		· . 					-		2.0E+01
Bis2-Chloroethyl Ether ^C	# ₀ * //	-	· ·	5.3E+00	-		6.0E+02		_			-	-			6.0E+02
Bis2-Chloroisopropyl Ether	0			6.5E+04	_		7.3E+06	_	_		-	<u></u> .		-		7.3E+06
Bis2-Ethylhexyl Phthalate ^C	∘ 78 T O 19 Int		-	2.2E+01			2.5E+03	_	-				_		-	2.5E+03
Bromoform ^c	- 0		-	1.4E+03	·	_	1.6E+05				-			-	-	1.6E+05
Butylbenzylphthalate	0			1.9E+03			2.1E+05	-	-			_	_			2.1E+05
Cadmium ⁻	- 0 🕾	4.0E+01	8.8E+00		1.6E+03	9.9E+02	-			 ·	-	_	_	1.6E+03	9.9E+02	
Carbon Tetrachloride ^C	0		-	1.6E+01		_	1.8E+03	-		<u>-</u>	_	-	·			1.8E+03
Chlordane ^C	· 0	9.0E-02	4.0E-03	8.1E-03	3.7E+00	4.5E-01	9.2E-01			-				3.7E+00	4.5E-01	9.2E-01

Parameter	Background	Wate	er Quality C	riteria	Wast	eload Alloca	ations	Antide	gradation Bas	eline	Antide	gradation Allo	cations	Most L	imiting Alloc	ations
(ug/l unless noted)	Conc.	Acute	Chronic	HH	Acute	Chronic	H	Acute	'Chronic	НН	Acute	·Chronic	нн	Acute	Chronic	нн
TRC	0 1			-												
Chlorine Prod. Oxidant	0	1.3E+01	7.5E+00	·	5.3E+02	8.5E+02	-				-	·		5.3E+02	8.5E+02	-
Chlorobenzene		_	_	1.6E+03			1.8E+05						· _	-	_	1.8E+05
Chlorodibromomethane ^c	0.0		_	1.3E+02		 `	1.5E+04	_	_		_					1.5E+04
Chloroform	0			1.1E+04	_	- -	1.2E+06	_	-					••		1.2E+06
2-Chloronaphthalene	0			1.6E+03	-	· 	1.8E+05			٠ _	· 	-	_	- '		1.8E+05
2-Chlorophenol	0		••	1.5E+02			1.7E+04		_		·	·		-	-	1.7E+04
Chlorpyrifos	. O =	1.1E-02	5.6E-03		4.5E-01	6.3E-01			-				-	4.5E-01	6.3E-01	,
Chromium III	. 140									- 1	_			- '		
Chromium VI	0 =	1.1E+03	5.0E+01	-	4.5E+04	5.7E+03	_	-	_		-		-	4.5E+04	5.7E+03	-
Chrysene ^c .	4,0		· _	1.8E-02			2.0E+00									2.0E+00
Copper	0	9.3E+00	6.0E+00)	3.8E+02	6.8E+02	- ,		-	-		_		3.8E+02	6.8E+02	-
Cyanide, Free	0	1.0E+00	1.0E+00	1.6E+04	4.1E+01	1.1E+02	1:8E+06	_	-				-	4.1E+01	1.1E+02	1.8E+06
° add				3.1E-03		- .	3.5E-01	,	- .		. –					3.5E-01
DDE C	0		-	2.2E-03		_	2.5E-01	_	-		-			- .	-	2.5E-01
DDT ^c	0 -	1.3E-01	1.0E-03	2.2E-03	5.3E+00	1.1E-01	2.5E-01	-	-	_	, - -			5.3E+00	1.1E-01	2.5E-01
Demeton	0	_	1.0E-01			1.1E+01			-				-	-	1.1E+01	
Diazinon	0	8.2E-01	8.2E-01	-	3.4E+01	9.3E+01	-		-	-				3.4E+01	9.3E+01	-
Dibenz(a,h)anthracene ^c	*** (O)			1.8E-01			2.0E+01		-	 .		_		-		2.0E+01
1,2-Dichlorobenzene	0			1.3E+03		_	1.5E+05	_		-	_		. -	-	-	1.5E+05
1,3-Dichlorobenzene	€ 0 ±			9.6E+02			1.1E+05			 .	- '	-		-		1.1E+05
1,4-Dichlorobenzene	hiji, 0	_	_	1.9E+02		-	2.1E+04			,				-	-	2.1E+04
3,3-Dichlorobenzidine ^c	• 0 •			2.8E-01	-	-	3.2E+01	_	<u>-</u> `	· -	_			·		3.2E+01
Dichlorobromomethane ^c	0	-		1.7E+02	_	-	1.9E+04			-			`			1. 9 E+04
1,2-Dichloroethane ^c	0	·		3.7E+02	 ,	_	4.2E+04	_	-	-			***		`	4.2E+04
1,1-Dichloroethylene	0	·		7.1E+03			8.0E+05				-	_	-	-		8.0E+05
1,2-trans-dichloroethylene	0	-	_	1.0E+04		·	1.1E+06	- .	-				-	-	-	1.1E+06
2,4-Dichlorophenol	} o	_	-	2.9E+02	-	- :	3.3E+04	-		_	-	-	- '	-		3.3E+04
1,2-Dichloropropane ^C	0	\		1.5E+02	_	·	1.7E+04	– .				-		\	-	1.7E+04
1,3-Dichloropropene ^C	0	-	-	2.1E+02	-	-	2.4E+04				_			-		2.4E+04
Dieldrin ^C	- O	7.1E-01	1.9E-03	5.4E-04	2.9E+01	2.1E-01	6.1E-02	_		. —	-	_		2.9E+01	2.1E-01	6.1E-02
Diethyl Phthalate	0.3	_	· – .	4.4E+04	Ì		5.0E+06		<i>.</i> -)				-	5.0E+06
2,4-Dimethylphenol	0	-		8.5E+02		-	9.6E+04		·		-			-		9.6E+04
Dimethyl Phthalate	0	l	-	1.1E+06			1.2E+08			-	-			_	-	1.2E+08
Di-n-Butyl Phthalate	0			4.5E+03		_	5.1E+05		· •	-	, –					5.1E+05
2.4 Dinitrophenol	0	-	. .	5.3E+03		-	6.0E+05	-			-				•• ,	6.0E+05
2-Methyl-4,6-Dinitrophenol	0			2.8E+02		. 	.3.2E+04	-	••		-	-	_		•	3.2E+04
2,4-Dinitrotoluene ^c	0		_	3.4E+01	-	· -	·3.8E+03	-	 ,	_				-		3.8E+03
DIOXIII 2,0,1,0	The last			5.1 E- 08			5.8E-06	_	,				•		_	5.8E-06
tetrachlorodibenzo-p-dioxin		-	´-	2.0E+00	\ <u> </u>	<u>-</u>	2.3E+02		_					-	· <u> </u>	2.3E+02
1,2-Diphenylhydrazine ^c Alpha-Endosulfan	0	3.4E-02	8.7E-03	8.9E+01	1.4E+00	9.8E-01	1.0E+04				_		٠	1.4E+00	9.8E-01	1.0E+04

Parameter	Background	Wate	er Quality C	riteria	Wast	teload Alloca	ations	Antide	egradation Ba	seline	Antide	gradation Allo	cations	Most Li	miting Alloc	ations
(ug/l unless noted)	Conc.	Acute	Chronic	НН	Acute	Chronic	НН	Acute	Chronic	HH	Acute	Chronic	HH	Acute	Chronic	нн
Beta-Endosulfan	1077	3.4E-02	8.7E-03	8.9E+01	1.4E+00	9.8E-01	1.0E+04							1.4E+00	9.8E-01	1.0E+04
Alpha + Beta Endosulfan	0	3.4E-02	8.7E-03	_	1.4E+00	9.8E-01		_						1.4E+00	9.8E-01	\
Endosulfan Sulfate	0			8.9E+01	_	_	1.0E+04		_	_				_	_	1.0E+04
Endrin	0.4	3.7E-02	2.3E-03	6.0E-02	1.5E+00	2.6E-01	6.8E+00		_			_ ′		1.5E+00	2.6E-01	6.8E+00
Endrin Aldehyde	This of the			3.0E-01		-	3.4E+01	_			·			<u> </u>	_	3.4E+01
Ethylbenzene	00	_	<u>.</u> .	2.1E+03	, 		2.4E+05					_		_		2.4E+05
Fluoranthene	*/Lo	-	-	1.4E+02		_	1.6E+04	_			. 		-	- .		1.6E+04
Fluorene	0	-		5.3E+03	_	_	6.0E+05									6.0E+05
Guthion	. 44 0		1.0E-02		-	1.1E+00		-	_	· -				_	1.1E+00	_
Heptachlor ^c	**************************************	5.3E-02	3.6E-03	7.9E-04	2.2E+00	4.1E-01	8.9E-02		_		_			2.2E+00	4.1E-01	8.9E-02
Heptachlor Epoxide ^C	. 0	5.3E-02	3.6E-03	3.9E-04	2.2E+00	4.1E-01	4.4E-02						_	2.2E+00	4.1E-01	4.4E-02
Hexachlorobenzene ^c	. 0		_	2.9E-03	-		3.3E-01							_		3.3E-01
Hexachlorobutadiene ^c	0.::	_	_	1.8E+02	-		2.0E+04		_					_		2.0E+04
Hexachlorocyclohexane Alpha- BHC ^C	1000-01-2008 100 100 100 100 100 100 100 100 100 100 100 100 100 100 100 100			10=00												
Hexachlorocyclohexane Beta-	. 0	_	_	4.9E-02	-	-	5.5E+00						· -		_	5.5E+00
BHC ^c	0			1.7E-01	· _	·	1.9E+01			· 						1.9E+01
Hexachlorocyclohexane	July 100				•								•		100	
Gamma-BHC ^c (Lindane)	1 7 4 9	1.6E-01	-	1.8E+00	6.6E+00	-	2.0E+02		-	- .	-			6.6E+00		2.0E+02
Hexachlorocyclopentadiene	0	-	-	1.1E+03	-	·	1.2E+05	·		-	-	-		-		1.2E+05
Hexachloroethane ^c	0	-	_	3.3E+01	_		3.7E+03	-		-						3.7E+03
Hydrogen Sulfide	0		2.0E+00	-	-	2.3E+02			-			-	_		2.3E+02	-
Indeno (1,2,3-cd) pyrene C	- 0 - 10	-	-	1.8E-01	-	-	2.0E+01		-	-	-			-	'	2.0E+01
Isophorone ^c	-0	-	_	9.6E+03		-	1.1E+06	_		. -			_	-		1.1E+06
Kepone	0		0.0€+00	-	-	0.0 E+ 00	_	_	••	-	Ŧ	· –			0.0E+00	
Lead	05.5	2.4E+02	9.3E+00	-	9.8E+03	1.1E+03		. –		-	 .		-	9.8E+03	1.1E+03	
Malathion	0	_	1.0E-01	 .		1.1E+01	'					-		-	1.1E+01	
Mercury	0.11	1.8E+00	9.4E-01		7.4E+01	1.1E+02	-	_				-		7.4E+01	1.1E+02	-
Methyl Bromide	O Training	-	-	1.5E+03		·	1.7 E+ 05									1.7E+05
Methylene Chloride ^c	0	_		5.9 E+ 03	-		6.7E+05		• ••				-		_	6.7E+05
Methoxychlor .	0	-	3.0E-02			3.4E+00		-		-			. 		3.4E+00	-
Mirex	0	-	0.0E+00		-	0.0E+00	-	-	·	· -		-	. - .	-	0.0E+00	-
Nickel	Ö.	7.4E+01	8.2E+00	4.6E+03	3.0E+03	9.3E+02	5.2E+05	_	•					3.0E+03	9.3E+02	5.2E+05
Nitrobenzene	0	-		6.9E+02	-		7.8 E+ 04		-			-				7.8E+04
N-Nitrosodimethylamine ^C	0		·	3.0E+01	 ,		3.4E+03		· –	, -	-	-	-	. ••	••	3.4E+03
N-Nitrosodiphenylamine ^C	0		-	6.0E+01		_	6.8 E+ 03		-		-	-	-	-		6.8E+03
N-Nitrosodi-n-propylamine ^C	0	-		5.1E+00		· –	5.8E+02	-			-			_		5.8E+02
Nonylphenol	# O	7.0E+00	1.7E+00	' <u></u>	2.9E+02	1.9E+02		- .		· –	_		-	2.9E+02	1.9E+02	
Parathion	145 A	-	. –	-		-		_			-	-		-		••
PCB Total ^C	0	-	3.0E-02	6.4E-04	-	3.4E+00	7.2E-02	_	** 1		_	_		-	3.4E+00	7.2E-02
Pentachlorophenol ^c	0	1.3E+01	7.9E+00	3.0E+01	5.3E+02	8.9E+02	3.4E+03					••		5.3E+02	8.9E+02	3.4E+03

Parameter	Background	Wat	er Quality C	riteria	Wast	teload Alloca	ations	Antide	gradation Bas	eline	Antideg	radation Allo	cations	Most L	imiting Alloc	ations
(ug/l unless noted)	Conc.	Acute	Chronic	H	Acute	Chronic	нн	Acute	Chronic	НН	Acute	Chronic	НН	Acute	Chronic	нн
Phenol	0		, –	8.6E+05	-		9.7E+07	_	· -		-	· –		-		9.7E+07
Phosphorus (Elemental)	0		1.0E-01	- 1	_	1.1E+01	-	-	_			'	_	_	1.1E+01	
Pyrene .	0			4.0E+03			4.5 E+ 05	-	·			-	_	-	• -	4.5E+05
Selenium	0	2.9E+02	7.1E+01	4.2E+03	1.2E+04	8.0E+03	4.7E+05		~				<u></u>	1.2E+04	8.0E+03	4.7E+05
Silver	0	1.9E+00	-	-	7.8E+01		· 			-		-	-	7.8E+01		-
1,1,2,2-Tetrachloroethane ^C	0			4.0E+01			4.5E+03			·				_	-	4.5E+03
Tetrachloroethylene ^C	-,0			3.3E+01	-		3.7E+03				-	<u> -</u> :	- , ·		-	3.7E+03
Thatlium	0 0			4.7E-01	 ,		5.3E+01		-						· <u></u>	5.3E+01
Toluene	**************************************			6.0E+03			6.8E+05						_		••	6.8E+05
Toxaphene ^C	0	2.1E-01	2.0E-04	2.8E-03	8.6E+00	2.3E-02	3.2E-01			-		-	_	8.6E+00	2.3E-02	3.2E-01
Tributyltin	0	4.2E-01	7.4E-03		1.7E+01	8.4E-01			-	_		-	-	1.7E+01	8.4E-01	- ,
1,2,4-Trichlorobenzene	%• O		- '	7.0E+01		-	7.9E+03	-	-	_	-	_			-	7.9E+03
1,1,2-Trichloroethane ^c		<u></u> '		1.6E+02	·	-	1.8E+04		-	- ·	_ ·	-			. .	1.8E+04
Trichloroethylene ^c	0			3.0E+02	-		3.4E+04	-	-	_	-	-		-		3.4E+04
2,4,6-Trichlorophenol ^c	0	-	· –	2.4E+01		_	2.7E+03	_	-			_			- `	2.7E+03
Vinyl Chloride ^c	0	_	_	2.4E+01	· –		2.7E+03			· -						2.7E+03
Zinc	0	9.0E+01	8.1E+01	2.6E+04	3.7E+03	9.2E+03	2.9E+06	-			_	_		3.7E+03	9.2E+03	2.9E+06

Notes:

- 1. All concentrations expressed as micrograms/liter (ug/l), unless noted otherwise
- 2. Discharge flow is highest monthly average or Form 2C maximum for Industries and design flow for Municipals
- 3. Metals measured as Dissolved, unless specified otherwise
- 4. "C" indicates a carcinogenic parameter
- 5. For transition zone waters, spreadsheet prints the lesser of the freshwater and saltwater water quality criteria.
- 6. Regular WLA = (WQC x WLA multiplier) (WLA multiplier 1)(background conc.)
- 7. Antideg. Baseline = (0.25(WQC background conc.) + background conc.) for acute and chronic

= (0.1(WQC - background conc.) + background conc.) for human health

8. Antideg. WLA = (Antideg. Baseline)(WLA multiplier) - (WLA multiplier - 1)(background conc.)

Elizabeth River Data Used from 2006 for Stream Information. See 2007 FS for actual data.

	Site Specific
<u>Metal</u>	Target Value (SSTV)
Antimony	7.2E+04
Arşenic III	1.1E+03
Cadmium	6.0E+02
Chromium III	#VALUE!
Chromium VI	3.4E+03
Соррег	1.5E+02
Lead	6.3E+02
Mercury	3.0E+01
Nickel	5.6E+02
Selenium	4.8E+03
Silver	3.1E+01
Zinc	1.5E+03

Note: do not use QL's lower than the minimum QL's provided in agency guidance

ATTACHMENT 7

SPECIAL CONDITIONS RATIONALE

VPDES PERMIT PROGRAM LIST OF SPECIAL CONDITIONS RATIONALE

Name of Condition:

B. Additional Total Residual Chlorine (TRC) Limitations and Monitoring Requirements

Rationale: Required by Water Quality Standards, 9VAC 25-260-170, Fecal coliform bacteria; other waters. Also, 40 CFR 122.41(e) requires the permittee, at all times, to properly operate and maintain all facilities and systems of treatment in order to comply with the permit. This ensures proper operation of chlorination equipment to maintain adequate disinfection.

C. OTHER REQUIREMENTS OR SPECIAL CONDITIONS

1.a. Sludge Reopener

Rationale: Required by the VPDES Permit Regulation, 9 VAC 25-31-220 C., and 40 CFR 122.44 (c)(4), which note that all permits for domestic sewage treatment plants (including sludge-only facilities) include any applicable standard for sewage sludge use or disposal promulgated under section 405(d) of the Clean Water Act.

1.b. Water Quality Standards Reopener

Rationale: The VPDES Permit Regulation, 9 VAC 25-31-220 D requires effluent limitations to be established which will contribute to the attainment or maintenance of water quality criteria.

1.c. Nutrient Reopener

<u>Rationale</u>: 9 VAC 25-40-70 A authorizes DEQ to include technology-based annual concentration limits in the permits of facilities that have installed nutrient control equipment, whether by new construction, expansion or upgrade. 9 VAC 25-31-390 A authorizes DEQ to modify VPDES permits to promulgate amended water quality standards.

1.d. Nutrient Removal Facilities Reopener

<u>Rationale</u>: 9 VAC 25-40-70 A authorizes DEQ to include technology-based annual concentration limits in the permits of facilities that have installed nutrient control equipment, whether by new construction, expansion or upgrade.

1.e. Total Maximum Daily Load (TMDL) Reopener

Rationale: For specified waters, section 303(d) of the Clean Water Act requires the development of total maximum daily loads necessary to achieve the applicable water quality standards. The TMDL must take into account seasonal variations and a margin of safety. In addition, section 62.1-44.19:7 of the State Water Control Law requires the development and implementation of plans to address impaired waters, including TMDLs. This condition allows for the permit to be either modified or, alternatively, revoked and reissued to incorporate the requirements of a TMDL once it is developed. In addition, the reopener recognizes that, in according to section 402(o)(l) of the Clean Water Act, limits and/or conditions may be either more or less stringent than those contained in this permit. Specifically, they can be relaxed if they are the result of a TMDL, basin plan or other wasteload allocation prepared under section 303 of the Act.

2. Licensed Operator Requirement

Rationale: The Permit Regulation, 9 VAC 25-31-200 D and Code of Virginia 54.1-2300 et. seq., Rules and Regulations for Waterworks and Wastewater Works Operators (18 VAC 160-20-10 et seq.) requires licensure of operators.

3. Reliability Class

Rationale: Required by Sewage Collection and Treatment Regulations, 12 VAC 5-581-20 and 120 for all municipal facilities.

4. CTC, CTO and O & M Manual Requirements

Rationale: Required by the State Water Control Law, Section 62.1-44.19; the Sewage Collection and Treatment Regulations (12 VAC 5-581 et seq); Section 401 of the Clean Water Act; 40 CFR 122.41(e); and the VPDES Permit Regulation (9 VAC-25-31-190E).

9 VAC 25-40-70 A authorizes DEQ to include technology-based annual concentration limits in the permits of facilities that have installed nutrient control equipment, whether by new construction, expansion or upgrade.

5. 95% Design Capacity Notification

Rationale: Required by the VPDES Permit Regulation, 9 VAC 25-31-200 B.2. for all POTW and PVOTW permits. Best professional judgment is used to apply this condition to other (private) municipal treatment facilities.

6. Alternative discharge Point - 002

Rationale: This condition originated under 9 VAC 25-31-190.M. of the VPDES permit regulation and Section MN of the VPDES Permit Manual that addresses bypasses under specific conditions. Because all treatment processes must be utilized prior to discharging to the alternate location, this discharge does not meet the definition of a bypass. A BPJ decision was made to include a reference to this alternate discharge point in the Part I.A. page and further address this discharge point in a special condition. This is similar to the way alternate discharge points in other VPDES permits have been addressed by the agency. The language of the condition is based on BPJ to address the alternate discharge location, differentiate this treated discharge from an actual bypass at the treatment facility and address EPA comments on bypasses in VPDES permits. It was a BPJ decision to require reporting similar to reporting requirements under the bypass condition in 9 VAC 25-31-190.M., in accordance with the Permit Manual. Since the discharge is fully treated, it is a BPJ decision that there is no need for specific discharge criteria or conditions in order to discharge from this alternate discharge point. Previous data have been reviewed and the determination has been made that dilution is not an issue for the treated wastewater to meet water quality standards, include general standard. Additional toxicity sampling may be requested at 100% effluent to demonstrate continued compliance with the general standard.

7. Quantification Levels Under Part I.A.

Rationale: States are authorized to establish monitoring methods and procedures to compile and analyze data on water quality, as per 40 CFR part 130, Water Quality Planning and Management, subpart 130.4.

8. Compliance Reporting Under Part I.A.

Rationale: Defines reporting requirements for toxic parameters with quantification levels and other limited parameters to ensure consistent, accurate reporting on submitted reports.

9. Effluent Monitoring Frequencies

Rationale: The incentive for reduced monitoring is an effort to reduce the cost of environmental compliance and to provide incentives to facilities which demonstrate outstanding performance and consistent compliance with their permits. Facilities which cannot comply with specific effluent parameters or have other related violations will not be eligible for this benefit. This is in conformance with Guidance Memorandum No. 98-2005 - Reduced Monitoring and EPA's proposed "Interim Guidance For Performance-Based Reduction of NPDES Permit Monitoring Frequencies" (EPA 833-B-96-001) published in April 1996.

10. Indirect Dischargers

Rationale: Required by VPDES Permit Regulation, 9 VAC 25-31-200 B.1. for POTWs and PVOTWs that receive waste from someone other than the owner of the treatment works.

11. Sludge Management Plan

Rationale: The VPDES Permit Regulation, 9 VAC 25-31-420, and 40 CFR 503.1 specify the purpose and applicability for sludge management plans. The VPDES Permit Regulation, 9 VAC 25-31-100 J.4., also sets forth certain detailed information which must be included in a sludge management plan. The VPDES sewage sludge permit application form and its attachments constitute the sludge management plan and will be considered for approval with the VPDES permit. In addition, the Biosolids Use Regulation, 12 VAC 5-585-330 and 340, specifies the general purpose and control requirements for an O&M manual in order to facilitate proper O&M of the facilities to meet the requirements of the regulation.

12. Total Phosphorus reporting calculations

Rationale: §62.1-44.19:13 of the Code of Virginia defines how annual nutrient loads are to be calculated; this is carried forward in 9 VAC 25-820-70. As annual concentrations (as opposed to loads) are limited in the individual permit, this special condition is intended to reconcile the reporting calculations between the permit programs, as the permittee is collecting a single set of samples for the purpose of ascertaining compliance with two permits.

13. Suspension of concentration limits for E3/E4 facilities

Rationale: 9 VAC 25-40-70 B authorizes DEQ to approve an alternate compliance method to the technology-based effluent concentration limitations as required by subsection A of this section. Such alternate compliance method shall be incorporated into the permit of an Exemplary Environmental Enterprise (E3) facility or an Extraordinary Environmental Enterprise (E4) facility to allow the suspension of applicable technology-based effluent concentration limitations during the period the E3 or E4 facility has a fully implemented environmental management system that includes operation of installed nutrient removal technologies at the treatment efficiency levels for which they were designed.

D. PRETREATMENT

Rationale: The permit regulation, 9 VAC 25-31-10 et seq., Part VII, establishes the legal requirements for State, local government and industry to implement National Pretreatment Standards. The Pretreatment Standards are implemented to prevent POTW plant pass through, interference, violation of water quality standards or contamination of sewage sludge. The regulation requires POTWs with a total design flow greater than 5 MGD with significant or categorical industrial input to establish a Pretreatment Program. The regulation also may apply to POTWs with design flows less than 5 MGD if circumstances warrant control of industrial discharges.

E. TOXICS MANAGENENT PROGRAM (TMP)

Rationale: To determine the need for pollutant specific and/or whole effluent toxicity limits as may be required by the VPDES Permit Regulation, 9 VAC 25-31-220 D. and 40 CFR 122.44 (d). See Attachment 9 of this fact sheet for additional justification.

ATTACHMENT 8

TOXICS MONITORING/TOXICS REDUCTION/
WET LIMIT RATIONALE

MEMORANDUM

VIRGINIA DEPARTMENT OF ENVIRONMENTAL QUALITY

TIDEWATER REGIONAL OFFICE

5636 Southern Boulevard

Virginia Beach, VA 23462

SUBJECT: Toxics Management Program (TMP) testing for HRSD-VIP Plant (VA0081281)

TO:

File

FROM:

Deanna Austin

DATE:

4/3/12

COPIES:

HRSD-VIP plant is a major municipal discharger (design flow 40 MGD) of treated domestic sewage. Discharge from outfall 001 to the Elizabeth River will continue to be monitored for toxicity during this permit term.

There has been no change in the dilution from the previous permit; therefore the nearfield (acute) dilution factor (41) remains the same. The following calculation shows how the TU_a was derived.

Acute dilution = 100/IWC_a

41= 100/IWCa

100/41 = 2.44% IWC_a

LC₅₀₌ IWC/Acute Water Quality Instream criterion

 $LC_{50}=2.44/0.3=8.13\%$

During the last permit term the LC_{50} of 8.13% was rounded to 9% effluent. Due to antibacksliding regulations, a LC_{50} of 9% will be used again.

 $TU_a = 1/LC_{50} \times 100$

 $1/9 \times 100 = 11.11$

•TUa = 11.1

The following table details the results of the TMP tests for the last permit term. Since all data met the LC_{50} , a WET limit is not needed at this time and annual TMP testing should continue.

OUTFALL	DESCRIPT	SPECIES	SAMPLEDT	LC50	SURVIVAL:	≨ TUÈ	TESTCOM	LAB
001	1st Annual Acute	A.b.	10/21/08	. 11.2	100	<8.9	100% survival in 11.2% effluent TUa.<8.9	HRSD
001	1st Annual Acute	C.v.	10/21/08	11.2	100	<8.9	100% survival in 11.2% effluent	HRSD
001	2nd Annual Acute	C.v.	11/03/09	11.2	100	<8.9	100% survival in 11.2% effluent	HRSD
001	2nd Annual Acute	A.b.	11/03/09	11.2	100	<8.9	100% survival in 11.2% effluent	HRSD
001	3rd Annual Acute	C.v.	03/09/10	11.2	100	<8.9	100% survival in 11.2% effluent	HRSD

001	3rd Annual Acute	A.b.	03/09/10	11.2	100	<8.9	100% survival in 11.2% effluent	HRSD
001	4th Annual Acute	C.v.	09/13/11	11.2	· 100	<8.9	100% survival in 11.2% effluent	HRSD
001 、	4th Annual Acute	A.b.	09/13/11	11.2	. 100	<8.9	100% survival in 11.2% effluent	HRSD

C.v. - Cyprinodon variegatus A.b. - Americamysis bahia

The following TMP language is recommended for the reissuance of the HRSD VIP permit (VA0081281).

D. TOXICS MANAGEMENT PROGRAM (TMP)

1. Biological Monitoring

a. In accordance with the schedule in 2. below, the permittee shall conduct annual acute toxicity tests for the duration of the permit. The permittee shall collect 24-hour flow-proportioned composite samples of final effluent from outfall 001 in accordance with Part 1.A. of this permit. The acute tests to use are:

48 Hour Static Acute test using Americanysis bahia and 48 Hour Static Acute test using Cyprinodon variegatus

These acute tests shall be performed with a minimum of 5 dilutions, derived geometrically, for the calculation of a valid LC_{50} . Express the results as TU_a (Acute Toxic Units) by dividing 100/ LC_{50} for reporting. Both species should be analyzed at the same time from the 24-hour flow-proportioned composite sample. Toxicity samples shall be taken at the same time as the other chemical parameter monitoring listed in Part I.A. of this permit for outfall 001.

Test procedures and reporting shall be in accordance with the WET testing methods cited in 40 CFR 136.3.

- b. The permittee may provide additional samples to address data variability during the period of initial data generation. These data shall be reported and may be included in the evaluation of the effluent toxicity. Test procedures and reporting shall be in accordance with the WET testing methods cited in 40 CFR 136.3.
- c. The test dilutions shall be able to determine compliance with the following endpoints:
 - (1) Acute LC₅₀ of 9% equivalent to a TU_a of 11.1
- d. All applicable data will be evaluated for reasonable potential at the conclusion of the test period. The data may be evaluated sooner if requested by the permittee, or if toxicity has been noted. Should evaluation of the data indicate that a limit is needed, a WET limit and compliance schedule will be required and the toxicity tests of D.1.a. may be discontinued.

2. Reporting Schedule

The permittee shall report the results and supply **two** complete copies of the toxicity test reports to the Tidewater Regional Office in accordance with the schedule below.

(a)	Conduct first annual TMP test for outfall 001 using Americamysis bahia and Cyprinodon variegatus	By December 31, 2014
(b)	Submit results of all biological tests	Within 60 days of the sample date and no later than January 10, 2015
(c)	Conduct subsequent annual TMP tests for outfall 001 using Americamysis bahia and Cyprinodon variegatus	By December 31, 2015, 2016, and 2017
(d)	Submit subsequent annual biological tests	Within 60 days of the sample date and no later than January 10, 2016, 2017, and 2018

r

.

ATTACHMENT 9

RECEIVING WATERS INFO./
TIER DETERMINATION/STORET DATA/
STREAM MODELING

303(d) LISTED SEGMENTS

TMDL Permit Review

Date: 3/16/2012

To: Jennifer Howell, TRO

√ JSH 3/22/2012

Permit Writer: Deanna Austin

Facility: HRSD-Virginia Initative STP

Permit Number: VA0081281 New or Renewal: Renewal

Permit Expiration Date: 1/27/2013

Waterbody ID: VAT G15 E Elizabeth River-All outfalls

Topo Name:

035A Norfolk North

Facility Address 4201 Powhatan Ave Norfolk, VA 23508

Receiving Stream:

Stream Name: Elizabeth Rive	r-Outfall 001		
Click here to enter text.			
Stream Data Requested? Cli	ck here to enter text.	•	<u> </u>
Outfall #: 001		Lat Lon: 36 52 57 76 19 20	
Stream Name (2): Click here	o enter text.		
All stormwater outfalls are not	monitored-No Expos	sure Certifications have been given	
Stream Data Requested? Cli	ck here to enter text.		
			•
			•

Is there a design flow change? If yes give the change. No change

TMDL Review:

Has a TMDL been approved that includes the receiving stre	am?		
Yes		,	
If yes, Include TMDL Name, Pollutant(s) and date of appro-	val:		
Chesapeake Bay TMDL EPA approved 12/29/2010: nitrogen, phospi	norus, and TSS		
Is the facility assigned a WLA from the TMDL?	No	<u> </u>	
If Yes, what is the WLA?			
VACCOLOGIA CONTRACTOR AND	TI IDII	inniformat dinahaman T	

VA0081281 was listed in the Chesapeake Bay TMDL under Bay segment ELIPH as a non-significant discharger. Because an aggregated WLA exists, this permit did not receive an individual WLA. The aggregated WLA is presented as a delivered load for each of the impaired 92 Bay segments. (Appendix Q)

Review will be completed in 30 days of receipt of request.

Additional Comments:

This permit falls within the Tidal James River PCB TMDL Watershed. The anticipated TMDL completion date is 2014

Planning Permit Review

Date: 3/16/2012

To: Kristie Britt, TRO

Permit Writer: Deanna Austin

Facility: HRSD-Virginia Initiative STP

Permit Number: VA0081281 New or Renewal: Renewal

Permit Expiration Date: 1/27/2013

Waterbody ID: VAT G15 E Elizabeth River-All outfalls

Topo Name:

035A Norfolk North

Facility Address 4201 Powhatan Ave Norfolk, VA 23508

Receiving Stream:

Stream Name: Elizabeth River-Outfal	H 001
Stream Data Requested? No	
Outfall #: 001	Lat Lon: 36 52 57 76 19 20
Stream Name (2):	
All stormwater outfalls are not monitor determination	red-No Exposure Certifications have been given-No need for a tier
Stream Data Requested?	
•	·

Planning Review:

303 (d): Indica	te Outfalls which discharge direc	tly to an impaired	
(Category 5) st	ream segment		
Outfall 001 disch	arges to impaired segment VAT-G15E	E_ELI02A06. Attachm	ent 1 provides a list of impaired parameters.
	·		
Tier Determina	ation		
Tier	The Elizabeth River Mainste	m is a Tier 1 water. S	See Attachment 1 for listed impairments.
Tier			
Management P	lan		
Is the facility Ref	erenced in a Management Plan?	No	

Review will be completed in 30 days of receipt of request.

Additional Comments:

	1	 _
T/NID 2/20/2012		1
KNB 3/20/2012		
		1
į.		1
i		
I		



2010 Impaired Waters - 303(d) List

Category 5 - Waters needing Total Maximum Daily Load Study

	Category	Estuary (Sq. Miles)	Reservoir (Acres)	River (Miles)	List Date	Dev. Date
Appomattox River						
Aquatic Plants (Macrophytes)	5A	2.705	į.		2006	2010
Aquatic Plants (Macrophytes)	, 5A	2.705			2006	2010
Eastern Branch Elizabeth River, Broad Cr	eek and Indian	River				
Oxygen, Dissolved	5A	2.287			2006	2010
Oxygen, Dissolved	5A	2.287		/	2006	2010
Chesapeake Bay segment ELIPH (Elizabe	eth River Mains	stem)				
· · · · · · · · · · · · · · · · · · ·					2006	2010
	5A	8.162			2006	2010
	foreheads one a managed-fitting ASP-MATCHES		, , , , , , ,			
•	. 5Δ	1.466			1996	2010
		• •				2010
•	5A 5A	1.964			2008	2010
Note that the state of the stat				, , , , , , , , , , , , , , , , , , ,		
,		E E 10	•		. 2009	2010
	•					2010
Vol. 2011 10 11 11 11 11 11 11 11 11 11 11 11		J.J 12			2000	
•					,	
						201
•						2010
		191.816		7.50		2018 2018
		0.012		7.50		201
		•				201
			* * * * * * * * * * * * * * * * * * *			
_			22.27	*	2020	
Escherichia coli	5A	and the state of t	88.37		2008	202
Falling Creek Reservoir						
· ' pH	5C		88.37		2010	202
Goode Creek						
Escherichia coli	5 A		·	1.25	2006	201
Almond Creek	<u> </u>					·
Escherichia coli	5A			2.36	2006	201
XVO and XVP (Almond Creek LITs)						
· ·	5A			0.54	2004	201
· · · · · · · · · · · · · · · · · · ·						
-	5 A			2.44	0000	004
	- 5A			3.11	ZUU6	201
Falling Creek						
Escherichia coli	5A			16.99	2006	201
Falling Creek				-7-44-18-18-18-18-18-18-18-18-18-18-18-18-18-		
	5A			0.98	2008	202
	Eastern Branch Elizabeth River, Broad Cr Oxygen, Dissolved Oxygen, Dissolved Chesapeake Bay segment ELIPH (Elizabe Oxygen, Dissolved Oxygen, Dissolved Oxygen, Dissolved James River Escherichia coli Escherichia coli Escherichia coli Escherichia coli Escherichia coli Escherichia coli Issue PCB in Fish Tissue PCB in Fi	Eastern Branch Elizabeth River, Broad Creek and Indian Oxygen, Dissolved 5A Oxygen, Dissolved 5A Chesapeake Bay segment ELIPH (Elizabeth River Mains Oxygen, Dissolved 5A James River Escherichia coli 5A Escherichia coli 5A Escherichia coli 5A Chlorophyll-a 5A Chlorophyll-a 5A Chlorophyll-a 5A Chlorophyll-a 5A PCB in Fish Tissue 5A PCB	Eastern Branch Elizabeth River, Broad Creek and Indian River Oxygen, Dissolved 5A 8.162 Dames River Escherichia coli 5A 1.466 Escherichia coli 5A 2.828 Escherichia coli 5A 1.964 James River Chlorophyll-a 5A 5.512 Chlorophyll-a 5A 5.512 James River and Various Tributaries PCB in Fish Tissue FCB	Eastern Branch Elizabeth River, Broad Creek and Indian River	Eastern Branch Elizabeth River, Broad Creek and Indian River Oxygen, Dissolved 5A 2.287 Oxygen, Dissolved 5A 2.287 Chesapeake Bay segment ELIPH (Elizabeth River Mainstem) Oxygen, Dissolved 5A 8.162 Oxygen, Dissolved 5A 8.162 James River Escherichia coli 5A 1.466 Escherichia coli 5A 1.964 James River Chlorophyll-a 5A 5.512 Chlorophyll-a 5A 5.512 James River and Various Tributaries PCB in Fish Tissue 5A 1.837 PCB in Fish Tissue 5A 191.816 PCB in Fish Tissue 5A 0.012 PCB in Fish Tissue 5A 0.003 Falling Creek Reservoir Escherichia coli 5A 1.25 Almond Creek Escherichia coli 5A 2.828 Escherichia coli 5A 2.828 Escherichia coli 5A 3.837 Falling Creek Reservoir pH 5C 88.37 Falling Creek Escherichia coli 5A 1.25 Almond Creek Escherichia coli 5A 2.36 XVO and XVP (Almond Creek, UTs) pH 5A 0.54 Falling Creek Escherichia coli 5A 1.25 Falling Creek Escherichia coli 5A 1.25 Falling Creek Escherichia coli 5A 0.54 Falling Creek Escherichia coli 5A 0.59 Eastern Branch Elizabeth River, Broad Creek and Indian River	



2010 Impaired Waters - 303(d) List

Category 5 - Waters needing Total Maximum Daily Load Study

James River Bas					*	Initial	TMD
Cause Group Code Impaired Use	Water Name Cause	Cause Category	Estuary (Sq. Miles)	Reservoir (Acres)	River (Miles)	List Date	Dev. Date
G14R-01-PH	Carbell Swamp - Upper						
Aquatic Life	Hq	5A			2.55	2002	2014
G14R-02-BAC	Carbell Swamp - Lower						
Recreation	Escherichia coli	5A	•	•	2.86	2010	2022
G14R-02-DO	Carbell Swamp - Lower	H.A. CHILLIAN CO.					
Aquatic Life	Oxygen, Dissolved	5A			2.86	2008	2020
G15E-01-01-EBEN	Elizabeth River Southern Branch, Parad in SBEMH	ise, Saint Julian	, New Mill and	Deep Creeks	s & unsegm	ented est	uaries
Aquatic Life	Estuarine Bioassessments	5A	2.256			2004	2016
	Estuarine Bioassessments	5A	0.854			2006	2018
G15E-01-01-TCDD	Elizabeth, River Southern Branch and its	tidal tributaries	- Advanced to the state of the	,			
Fish Consumption	Dioxin (including 2,3,7,8-TCDD)	5A	3.137		·	2010	2022
G15E-02-02-BAC	Elizabeth River Upper Mainstem, Easter	n Branch, Broad	Creek, South	nern Branch a	nd Paradis	e Creek	
Recreation	Enterococcus	5A	1.979			1998	2010
	Enterococcus	5A	0.539			2006	2018
G15E-02-04-EBEN	Eastern Branch Elizabeth River, Broad (Creek and Indiar	River				
Aquatic Life	Estuarine Bioassessments	5A	1,759			2004	201
•	Estuarine Bioassessments	5A	0.586		•	2006	201
G15E-02-05-BAC	Indian River tributary of Eastern Branch,	Elizabeth River			,		,
Recreation	Enterococcus	. 5A	0.268			2002	2014
G15E-03-01-EBEN	Elizabeth River Mainstem	MILE 11 11 11 11 11 11 11 11 11 11 11 11 11			1		
Aquatic Life	Estuarine Bioassessments	5A	4.528			2004	2016
	Estuarine Bioassessments	5A	3.440			2010	2022
G15E-04-01-BAC	Western Branch, Elizabeth River		vrue magair - malait d'11				
Recreation	Enterococcus	5A	2.021			2004	201
G15E-04-02-EBEN	Western Branch Elizabeth River and Un	seamented estu	aries in WBEI	MH			
Aquatic Life	Estuarine Bioassessments	5A	0.562			2006	2018
•	Estuarine Bioassessments	5A	2.166			2010	2022
G15E-05-02-BAC	Lafayette River						
Recreation	Enterococcus	5A	1.558			2002	201
G15E-06-01-BAC	Hampton River						
Recreation	Enterococcus	5A	0.545			2010	202
	PH-The arms of the second seco						
G15E-06-03-BAC Recreation	Hoffler Creek Enterococcus	5A	0.057			2008	202
	and the second of the second o	** IMA					
H01R-01-HG	James River	E۸			15.55	2010	202
Fish Consumption	Mercury in Fish Tissue	5Ą			10.00	2010	
H02R-01-BAC	Pedlar River						
Recreation	Escherichia coli	5A			9.46	2006	201

James River Basin

Cause Group Code: ELIPH-DO-BAY

Chesapeake Bay segment ELIPH (Elizabeth River Mainstem)

Location: This cause encompasses the complete CPB segment ELIPH

City / County: Norfolk City

Portsmouth City

Use(s): Aquatic Life

Open-Water Aquatic Life

Cause(s) /

VA Category: Oxygen, Dissolved / 5A

The Aquatic Life and Open-Water Aquatic Life Uses are impaired based on failure to meet the CBP dissolved oxygen criteria for Open Water - Summer & "Rest of Year (ROY) for the 2008 IR cycle. The 30-day dissolved oxygen criteria for open water use failed for the 2008 assessment. There is insufficient data to assess remaining shorter-term dissolved oxygen criteria for this use.

Chesapeake Bay segment ELI	PH (Elizabeth River Mainstem)		•	Estuary	Reservoir	River
Aquatic Life	1	,		(Sq. Miles)	(Acres)	(Miles)
		Oxygen, Dissolve	ed - Total Impaired Size by Water Type:	8.162		
Chesapeake Bay segment ELI Open-Water Aquatic Life	PH (Elizabeth River Mainstem)	,		Estuary (Sq. Miles)	Reservair (Acres)	River (Miles)
		Oxygen, Dissolve	d - Total Impaired Size by Water Type:	8.162		
ources:						
Agriculture	Atmospheric Deposition - Nitrogen	Industrial Point Source Discharge	Internal Nutrient Recycling			
Loss of Riparian Habitat	Municipal Point Source Discharges	Sources Outside State Jurisdiction or Borders	Wet Weather Discharges (Non-Point Source)			
Wet Weather Discharges						

Wet Weather Discharges (Point Source and Combination of Stormwater, SSO or CSO)

James River Basin

Cause Group Code: G01E-03-PCB James River and Various Tributaries

Location: Estuarine James River from the fall line to the Hampton Roads Bridge Tunnel, including several tributaries listed below. Appoint to Lake

Chesdin Dam

Bailey Creek up to Route 630

Bailey Bay

Chickahominy River up to Walkers Dam Skiffes Creek up to Skiffes Creek Dam Pagan River and its tributary Jones Creek

Chuckatuck Creek

Nansemond River and its tributaries Bennett Creek and Star Creek

Hampton River

Willoughby Bay and the Elizabeth R. system (Western, Eastern, and Southern Branches and Lafayette R.) and tributaries St. Julian Creek, Deep Creek,

and Broad Creek

City / County: Charles City Co.

Chesapeake City

Chesterfield Co.

Colonial Heights City (

Dinwiddie Co.

Hampton City

Henrico Co.

Hopewell City

Isle Of Wight Co.

James City Co.

New Kent Co.

Newport News City Richmond City Norfolk City Suffolk City Petersburg City Surry Co. Portsmouth City
Virginia Beach City

Prince George Co. Williamsburg City

Use(s): Fish Consumption

Cause(s) /

VA Category: PCB in Fish Tissue / 5A

PCB in Fish Tissue / 5D

The Fish Consumption Use is impaired based on the VDH fish consumption advisory for PCBs fish tissue contamination within the James River and select tidal tributaries, issued 12/13/04. During the 2002 cycle, the James River from the Fall line to Queens Creek was considered not supporting of the Fish Consumption Use due to PCBs in multiple fish species at multiple DEQ monitoring locations.

During the 2004 cycle, a VDH Fish Consumption Restriction was issued from the fall line to Flowerdew Hundred and the segment was adjusted slightly to match the Restriction.

However, during the 2006 cycle, the restriction was extended on 12/13/2004 to extend from the I-95 bridge downstream to the Hampton Roads Bridge Tunnel and include the tidal portions of the following tributaries:

Appomattox River up to Lake Chesdin Dam

Bailey Creek up to Route 630

Bailey Bay

Chickahominy River up to Walkers Dam

Skiffes Creek up to Skiffes Creek Dam

Pagan River and its tributary Jones Creek

Chuckatuck Creek

Nansemond River and its tributaries Bennett Creek and Star Creek

Hampton River

Willoughby Bay and the Elizabeth R. system (Western, Eastern, and Southern Branches and Lafayette R.) and tributaries St. Julian Creek, Deep Creek, and Broad Creek

James River Basin

The advisory was modified again on 10/10/2006 to add Poythress Run.

James River and Various Tributaries

Estuary Reservoir River
(Sq. Miles) (Acres) (Miles)

PCB in Fish Tissue - Total Impaired Size by Water Type: 256.441 7.50

Sources:

Contaminated Sediments

Source Unknown

Sourcés Outside State Jurisdiction or Borders

James River Basin

Cause Group Code: G15E-03-01-EBEN

Elizabeth River Mainstem

Location: This cause encompasses the entirety of the Elizabeth River Mainstem. CBP segment SBEMH. BIBI segment ELIMHa.

City / County: Norfolk City

Portsmouth City

Use(s): Aquatic Life

Cause(s) /

VA Category: Estuarine Bioassessments / 5A

The Aquatic Life Use is impaired based on failure to meet a statistical evaluation constituting an un-impacted benthic organism population per CBP (Benthic-BIBI) analysis. The source/stressor tool yielded an unknown source for the impairment. This segment was previously included (2004 IR) in TMDL ID: VAT-G15E-01-09.

The TMDL due date is carried from the previous 2004 IR impairment identification date.

Previous Use ID = VAT-G15E-01-09 for benthic impairment.

This Cause Code (G15E-03-01-EBEN) relates to all benthic impairments within the Elizabeth River system.

Elizabeth River Mainstem

Estuary (Sq. Miles) Reservoir (Acres)

River (Miles)

Aquatic Life

Estuarine Bioassessments - Total Impaired Size by Water Type:

7.968

Sources:

Contaminated Sediments

Source Unknown

VIRGINIA

305(b)/303(d)

WATER QUALITY INTEGRATED REPORT

to

CONGRESS and the EPA ADMINISTRATOR

for the

PERIOD

January 1, 2003 to December 31, 2008





Richmond, Virginia
November 2010

ATTACHMENT 10

TABLE III(a) AND TABLE III(b) - CHANGE SHEETS

TABLE III(a)

VPDES PERMIT PROGRAM Permit Processing Change Sheet

1. Effluent Limits and Monitoring Schedule: (List any changes FROM PREVIOUS PERMIT and give a brief rationale for the changes).

OUTFALL NUMBER	PARAMETER CHANGED	MONITORING LIMITS FROM / TO	CHANGED	EFFLUENT LIMITS CHANGED FROM / TO	RATIONALE	DATE & INITIAL
	~					,
				,	. ,	

F OTHER CHANGES:	COMMENTS:	DATE & INITIAL
Changed boilerplate language to include the VELAP information		3/16/12 DDA
Changed special condition C.11 (Sludge Management Plan) to not have a VDH reference since they no longer are involved in the program.		3/16/12 DDA
QL changed for BOD from 5 mg/l to 2 mg/l.	Changed to be consistent with other HRSD permits.	3/16/12 DDA

TABLE III(b)

VPDES PERMIT PROGRAM Permit Processing Change Sheet

1. Effluent Limits and Monitoring Schedule: (List any changes MADE DURING PERMIT PROCESS and give a brief rationale for the changes).

OUTFALL NUMBER	PARAMET CHANGE					CHANGED	EFFLU	ENT LIM FROM	ITS CHA	NGED		RATIO	ONALE		DATE & INITIAL
	4						:	•					-	Ì	
			-						÷ v				•		
			· ·							,					, ,
	,														
							,			,					
			_		a.										
-										,					
						٤		,							
									-						21
							let tetebere.						1 TERRER		
THER CHANG	ES FROM:						CHANG	ED TO:						,	DATE & INITIAL
				attification to the second											
		12.1.11.21									-			$\neg \dagger$	<u> </u>

ATTACHMENT 11

EPA PERMIT CHECKLIST

State "Transmittal Checklist" to Assist in Targeting Municipal and Industrial Individual NPDES Draft Permits for Review

Part I. State Draft Permit Submission Checklist

In accordance with the MOA established between the Commonwealth of Virginia and the United States Environmental Protection Agency, Region III, the Commonwealth submits the following draft National Pollutant Discharge Elimination System (NPDES) permit for Agency review and concurrence.

Facility Name.	hrob-virginia initiative STP			
NPDES Permit Number:	VA0081281			·
Permit Writer Name:	Deanna Austin	<u></u>	,	
Date:	4/3/12	Muni Yes X X X X		
Major [X]	Minor[] Industrial[]	Yes X X X X	Municipal [X]	
I.A. Draft Permit Package S	Submittal Includes:	Yes	No	N/A
1. Permit Application?		Х		
Complete Draft Permit (for including boilerplate information)	or renewal or first time permit – entire permit, mation)?	х		
3. Copy of Public Notice?			· X	
4. Complete Fact Sheet?		Х		
5. A Priority Pollutant Scree	ning to determine parameters of concern?	Х		
6. A Reasonable Potential a	analysis showing calculated WQBELs?	Х	•	
7. Dissolved Oxygen calculate	ations?			×
8. Whole Effluent Toxicity T	est summary and analysis?	Х		
9. Permit Rating Sheet for r	new or modified industrial facilities?	Yes No X X X X X X X X Yes No X X Yes No X X Yes No X X	Х	
I.B. Pe	ermit/Facility Characteristics	Yes	No	N/A
1. Is this a new, or currently	unpermitted facility?		Х	
	ls (including combined sewer overflow points, non- water) from the facility properly identified and	x		
Does the fact sheet or peterstreatment process?	ermit contain a description of the wastewater	х		
I.B. Permit	/Facility Characteristics - cont.	Yes	No	N/A
	DMR data for at least the last 3 years indicate se with the existing permit?		Х	
5. Has there been any char was developed?	nge in streamflow characteristics since the last permit		х	

	·			
6.	Does the permit allow the discharge of new or increased loadings of any pollutants?		Х	
7.	Does the fact sheet or permit provide a description of the receiving water body(s) to which the facility discharges, including information on low/critical flow conditions and designated/existing uses?	X		
8.	Does the facility discharge to a 303(d) listed water?	Х		
	a. Has a TMDL been developed and approved by EPA for the impaired water?	Х		
	b. Does the record indicate that the TMDL development is on the State priority list and will most likely be developed within the life of the permit?	٠ .		Х
	c. Does the facility discharge a pollutant of concern identified in the TMDL or 303(d) listed water?	х		
9.	Have any limits been removed, or are any limits less stringent, than those in the current permit?	J	Х	
10	. Does the permit authorize discharges of storm water?	Х		
11	. Has the facility substantially enlarged or altered its operation or substantially increased its flow or production?		х	
12	. Are there any production-based, technology-based effluent limits in the permit?	х		
13	Do any water quality-based effluent limit calculations differ from the State's standard policies or procedures?		X	
14	. Are any WQBELs based on an interpretation of narrative criteria?		Х	
15	Does the permit incorporate any variances or other exceptions to the State's standards or regulations?		х	
16	. Does the permit contain a compliance schedule for any limit or condition?		Х	
17	. Is there a potential impact to endangered/threatened species or their habitat by the facility's discharge(s)?		х	
18	. Have impacts from the discharge(s) at downstream potable water supplies been evaluated?	х		
19	. Is there any indication that there is significant public interest in the permit action proposed for this facility?		х	
20	. Have previous permit, application, and fact sheet been examined?	Х		

Part II. NPDES Draft Permit Checklist

Region III NPDES Permit Quality Checklist – for POTWs (To be completed and included in the record <u>only</u> for POTWs)

	II.A. Permit Cover Page/Administration	Yes	No	N/A
1.	Does the fact sheet or permit describe the physical location of the facility, including latitude and longitude (not necessarily on permit cover page)?	х		
2.	Does the permit contain specific authorization-to-discharge information (from where to where, by whom)?	Х	_	

II.B. Effluent Limits - General Elements	Yes	No	N/A
 Does the fact sheet describe the basis of final limits in the permit (e.g., that a comparison of technology and water quality-based limits was performed, and the most stringent limit selected)? 	x		
2. Does the fact sheet discuss whether "ant backsliding" provisions were met for any limits that are less stringent than those in the previous NPDES permit?			х

II.C	C. Technology-Based Effluent Limits (POTWs)	Yes	No	N/A
1.	Does the permit contain numeric limits for <u>ALL</u> of the following: BOD (or alternative, e.g., CBOD, COD, TOC), TSS, and pH?	х		
2.	Does the permit require at least 85% removal for BOD (or BOD alternative) and TSS (or 65% for equivalent to secondary) consistent with 40 CFR Part 133?	х		
	a. If no, does the record indicate that application of WQBELs, or some other means, results in more stringent requirements than 85% removal or that an exception consistent with 40 CFR 133.103 has been approved?			
3.	Are technology-based permit limits expressed in the appropriate units of measure (e.g., concentration, mass, SU)?	X.		
4.	Are permit limits for BOD and TSS expressed in terms of both long term (e.g., average monthly) and short term (e.g., average weekly) limits?	×		
5.	Are any concentration limitations in the permit less stringent than the secondary treatment requirements (30 mg/l BOD5 and TSS for a 30-day average and 45 mg/l BOD5 and TSS for a 7-day average)?		х	
	a. If yes, does the record provide a justification (e.g., waste stabilization pond, trickling filter, etc.) for the alternate limitations?	,		х

	II.D. Water Quality-Based Effluent Limits	Yes	No	N/A
1.	Does the permit include appropriate limitations consistent with 40 CFR 122.44(d) covering State narrative and numeric criteria for water quality?	х		
2.	Does the fact sheet indicate that any WQBELs were derived from a completed and EPA approved TMDL?			×
11.1	D. Water Quality-Based Effluent Limits – cont.	Yes	No	N/A
3.	Does the fact sheet provide effluent characteristics for each outfall?	Х		
4.	Does the fact sheet document that a "reasonable potential" evaluation was performed?	х		
	a. If yes, does the fact sheet indicate that the "reasonable potential" evaluation was performed in accordance with the State's approved procedures?	Х		
	b. Does the fact sheet describe the basis for allowing or disallowing in-stream dilution or a mixing zone?	Х		
	c. Does the fact sheet present WLA calculation procedures for all pollutants that were found to have "reasonable potential"?			X
	d. Does the fact sheet indicate that the "reasonable potential" and WLA calculations accounted for contributions from upstream sources (i.e., do calculations include ambient/background concentrations)?	х		

	e. Does the permit contain numeric effluent limits for all pollutants for which "reasonable potential" was determined?			X
5.	Are all final WQBELs in the permit consistent with the justification and/or documentation provided in the fact sheet?	Х		
6.	For all final WQBELs, are BOTH long-term AND short-term effluent limits established?		X	
7.	Are WQBELs expressed in the permit using appropriate units of measure (e.g., mass, concentration)?	X		
8.	Does the record indicate that an "antidegradation" review was performed in accordance with the State's approved antidegradation policy?	X		

	II.E. Monitoring and Reporting Requirements	Yes	No	N/A
1.	Does the permit require at least annual monitoring for all limited parameters and other monitoring as required by State and Federal regulations?	Х		
	a. If no, does the fact sheet indicate that the facility applied for and was granted a monitoring waiver, AND, does the permit specifically incorporate this waiver?			
2.	Does the permit identify the physical location where monitoring is to be performed for each outfall?	×		
3.	Does the permit require at least annual influent monitoring for BOD (or BOD alternative) and TSS to assess compliance with applicable percent removal requirements?		X	
4.	Does the permit require testing for Whole Effluent Toxicity?	Х		

	II.F. Special Conditions	Yes	No	N/A
1.	Does the permit include appropriate biosolids use/disposal requirements?	X	-	
2.	Does the permit include appropriate storm water program requirements?	X		

II.F	F. Special Conditions – cont.	Yes	No	N/A
3.	If the permit contains compliance schedule(s), are they consistent with statutory and regulatory deadlines and requirements?		-	X
4.	Are other special conditions (e.g., ambient sampling, mixing studies, TIE/TRE, BMPs, special studies) consistent with CWA and NPDES regulations?	X		
5.	Does the permit allow/authorize discharge of sanitary sewage from points other than the POTW outfall(s) or CSO outfalls [i.e., Sanitary Sewer Overflows (SSOs) or treatment plant bypasses]?		X	
6.	Does the permit authorize discharges from Combined Sewer Overflows (CSOs)?	:	Х	
	a. Does the permit require implementation of the "Nine Minimum Controls"?			Х
	b. Does the permit require development and implementation of a "Long Term Control Plan"?			Х
	c. Does the permit require monitoring and reporting for CSO events?			X
7.	Does the permit include appropriate Pretreatment Program requirements?	Х		

II.G.	Standard Conditions		Yes	No	N/A
Does the permit contain all 4 equivalent (or more stringent)	0 CFR 122.41 standard conditions conditions?	or the State	Х		
List of Standard Conditions – 4	0 CFR 122.41				
Duty to comply Duty to reapply Need to halt or reduce activity not a defense Duty to mitigate Proper O & M Permit actions	Property rights Duty to provide information Inspections and entry Monitoring and records Signatory requirement Bypass Upset	24-Hour	change ted nonc rs ng repor ince sch	omplia ts edules g	ince

new introduction of pollutants and new industrial users [40 CFR 122.42(b)]?

Part III. Signature Page

Based on a review of the data and other information submitted by the permit applicant, and the draft permit and other administrative records generated by the Department/Division and/or made available to the Department/Division, the information provided on this checklist is accurate and complete, to the best of my knowledge.

Name Deanna Austin

Title Environmental Specialist Senior II

Signature 4/3/12

ATTACHMENT 12

CHRONOLOGY SHEET

Chronology

Wednesday, April 04, 2012

Facility Name: HRSD - Virginia Initiative			VA0081281	
Event	Date	Comment		•
Application fee deposited:	- .	NA-Reissuance	· .	
First Application Reminder Phone Call:	<u> </u>	NA-App Received 3/15/12		
Second Application Reminder Phone Call:		NA-App Received 3/15/12		
Site visit:	— 2/11/2010			
Site inspection report:	— 2/25/2010	,		
Reissuance letter mailed:	— 1/17/2012			
Application received at RO 1st time:	— 3/15/2012			
App sent to State Agencies (list in comment field):	— 3/16/2012	VDH, DSS, VMRC		
App complete letter sent to permittee:	— 3/20/2012	•		
Application Administratively complete:	— 3/20/2012			
Application totally / technically complete:	— 3/20/2012			
Draft permit developed:	— 4/3/2012			
Old expiration date:	— 1/27/2013	NULL		
First DMR due:	— 3/10/2013			